

GENERIC BILL OF QUANTITIES

FOR

CONSTRUCTION AND REFURBISHMENT OF BUILDINGS AND FACILITIES

AROUND CITY OF EKURHULENI

GENERIC BILL OF QUANTITIES (PROVISIONAL)

<u>FINAL SUMMARY</u>			
<u>BUILDERS WORK</u>			
BILL NO. 1	PRELIMINARIES AND GENERAL	R	2994000
BILL NO. 2	ALTERATIONS (PROVISIONAL)	R	12,508,412.23
BILL NO. 3	EARTHWORKS (PROVISIONAL)	R	5,595,109.52
BILL NO. 4	CONCRETE, FORMWORK AND REINFORCEMENT	R	9,818,201.66
BILL NO. 5	MASONRY	R	623,743.09
BILL NO. 6	WATERPROOFING	R	211,988.02
BILL NO. 7	ROOF COVERINGS, ETC.	R	683,057.09
BILL NO. 8	CARPENTRY AND JOINERY	R	2,180,921.26
BILL NO. 9	CEILINGS, PARTITIONS AND ACCESS FLOORING	R	656,423.66
BILL NO. 10	FLOOR COVERINGS, WALL LININGS, ETC.	R	669,477.01
BILL NO. 11	IRONMONGERY	R	3,968,636.80
BILL NO. 12	METALWORK	R	2,600,932.82
BILL NO. 13	PLASTERING	R	94,819.05
BILL NO. 14	TILING	R	150,105.20
BILL NO. 15	GLAZING	R	114,358.80
BILL NO. 16	PAINTWORK	R	121,147.05
BILL NO. 17	PROVISIONAL SUMS, ETC.	R	49,620.00
BILL NO. 18	EXTERNAL WORKS	R	4,161,642.64
Sub-Total		R	44,208,595.89
BILL No. 19	MISCELLANEOUS CHARGES-GENERAL BUILDING ITEMS	R	135,231.35
BILL No. 20	INSPECTION AND REPORT	R	54,243.57
BILL NO. 21	PLUMBING AND DRAINAGE	R	3,465,025.63
BILL No. 22	ELECTRICAL INSTALLATION , AIRCONDITION UNITS & AUDIO VISUAL EQUIPMENT	R	5,824,590.88
Sub-Total		R	53,687,687.32

FINAL SUMMARY

VAT

15%

8,053,153.10

<u>FINAL SUMMARY</u>			
Carried to form of tender			
		R	61,740,840.42

Item	Description	Uom	Rate	Amount
	<u>BILL NO. 1</u> <u>PRELIMINARIES AND GENERAL</u> <u>PRELIMINARIES</u> <u>NOTES</u> The JBCC Series 2000 Principal Building Agreement (Edition 5.0 July 2007 code 2101) prepared by the Joint Building Contract Committee shall be the applicable building agreement, amended as hereinafter described The ASAQs Preliminaries (November 2007 edition) published by the Association of South African Quantity Surveyors for use with the said JBCC Principal Building Agreement shall be deemed to be incorporated in these bills of quantities Contractors are referred to the abovementioned documents for the full intent and meaning of each clause thereof These clauses are hereinafter referred to by clause number and heading only. Where standard clauses or alternatives are not entirely applicable to this contract such modifications, corrections or supplements as will apply are given under each relevant clause heading and such modifications, corrections or supplements shall take precedence notwithstanding anything contrary contained in the abovementioned documents Where any item is not relevant to this specific contract such item is marked N/A, signifying "not applicable" <u>PREAMBLES FOR TRADES</u> The Model Preambles for Trades (2008 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said Model Preambles will be entertained			

Item	Description	Uom	Rate	Amount
	Supplementary preambles as well as the Project Specifications are incorporated in these bills of quantities to satisfy the requirements of this project. Such supplementary preambles shall take precedence over the provisions of the said Model Preambles			
	The contractor's prices for all items throughout these bills of quantities must take account of and include for all of the obligations, requirements and specifications given in the said Model Preambles and in any supplementary preambles			
	Total Carried Forward			

Item	Description	Uom	Rate	Amount
	Total Brought Forward			-
	<u>PRICING OF PRELIMINARIES</u>			
	Should the contractor select Option A in terms of subclause 3.2.1 in the Contract Data - Contractor to Employer (CE) for the purpose of adjustment of these preliminaries, the amount entered into the amount column in these preliminaries is to be divided into one or more of the three categories provided namely Fixed (F), Value Related (V) and Time Related (T)			
	<u>SECTION A - PRINCIPAL BUILDING AGREEMENT</u>			
	<u>Definitions</u>			
1	Clause 1.0 - Definitions and interpretation F:..... V:..... T:.....	Item	1.00	10,000.00
	<u>Objective and preparations</u>			
2	Clause 2.0 - Offer acceptance and performance obligations F:..... V:..... T:.....	Item	1.00	10,000.00
3	Clause 3.0 - Documents Delete clause 3.3 and replace it with the following clause: The contractor shall waive its lien or right of continuing possession of the works in favour of the employer. The waiver shall be according to the JBCC Waiver of Contractor's Lien form, and shall ensure that any selected or nominated subcontractors or contractor's domestic subcontractors, also waive their lien or right of continuing possession, in favour of the employer and sign the JBCC Waiver of Contractor's Lien form. F:..... V:..... T:.....	Item	1.00	30,000.00
4	Clause 4.0 - Design responsibility F:..... V:..... T:.....	Item	1.00	50,000.00
5	Clause 5.0 - Employer's agents F:..... V:..... T:.....	Item	1.00	
6	Clause 6.0 - Contractor's site representative The Contractor shall not make any change to the management of the Works without the Principal Agent's written approval. Should the Principal Agent consider that the Contractor's representative appears to be incompetent, or act in an uncooperative or improper manner, he may instruct that the representative be removed from the Works and be replaced by a competent and cooperative person to the Principal Agent's satisfaction.F:..... V:..... T:.....	Item	1.00	145,000.00

Item	Description	Uom	Rate	Amount
	Total Carried Forward			245,000.00

Item	Description	Uom	Rate	Amount
	Total Brought Forward			245,000.00
	Clause 7.0 - Compliance with laws and regulations Without limiting the generality of the provisions of clause 7.0, the contractor's attention is drawn to the provisions of the Construction Regulations, 01 March 2014 issued in terms of the Occupational Health and Safety Act 1993, as amended. It is specifically stated that the employer shall prepare a documented health and safety specification for the works and that the employer shall ensure that the contractor has made provision for the cost of health and safety measures during the execution of the works. The contractor shall price opposite this item for compliance with the act and the regulations and the reasonable provisions of the aforementioned health and safety specifications.F:..... V:..... T:.....			
7		Item	1.00	80,000.00
	Clause 8.0 - Works risk F:..... V:..... T:.....			
8		Item	1.00	45,000.00
	Clause 9.0 - Indemnities F:..... V:..... T:.....			
9		Item	1.00	45,000.00
	Clause 10.0 - General insurances F:..... V:..... T:.....			
10		Item	1.00	35,000.00
	Clause 11.0 - Special insurances F:..... V:..... T:.....			
11		Item	1.00	15,000.00
	Clause 12.0 - Effecting insurances F:..... V:..... T:.....			
12		Item	1.00	15,000.00
	Clause 13.0 - Assignment F:..... V:..... T:.....			
13		Item	1.00	
	Clause 14.0 - Security F:..... V:..... T:.....			
14		Item	1.00	55,000.00
	<u>Execution</u>			
	Clause 15.0 - Preparation for and execution of the works F:..... V:..... T:.....			
15		Item	1.00	
	Clause 16.0 - Site and access F:..... V:..... T:.....			
16		Item	1.00	

Item	Description	Uom	Rate	Amount
17	Clause 17.0 - Contract instructions Only the Principal Agent is empowered to resolve cost aspects of any matter pertaining to the Contract. In addition to the provisions of sub-clause 17.3, contract instructions are to be recorded in triplicate in a contract instruction book, which is to be supplied and maintained on site by the Contractor F:..... V:..... T:.....	Item	1.00	
Total Carried Forward				535,000.00

Item	Description	Uom	Rate	Amount
	Total Brought Forward			535,000.00
	Clause 18.0 - Setting out of the works The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc. exist in order that the necessary arrangements may be made for the rectification of any such encroachments.F:..... V:..... T:.....			
18		Item	1.00	53,000.00
	Clause 19.0 - Temporary works and plant F:..... V:..... T:.....			
19		Item	1.00	66,000.00
	Clause 20.0 - Nominated subcontractors In addition to the provisions of sub-clause 20.1.2, the Contractor shall, at any time on being requested to do so by the Principal Agent, furnish a copy of the JBCC Nominated Sub-Contract Agreement to the Employer, within five (5) working days of such requestF:..... V:..... T:.....			
20		Item	1.00	0.30
	Clause 21.0 - Selected subcontractors F:..... V:..... T:.....			
21		Item	1.00	
	Clause 22.0 - Employer's direct contractors F:..... V:..... T:.....			
22		Item	1.00	10,000.00
	Clause 23.0 - Contractor's domestic subcontractors In addition to the provisions of sub-clause 23.1, the Contractor shall, at any time on being requested to do so by the Principal Agent, furnish a copy of the Domestic Sub-Contract Agreement to the Employer, within five (5) working days of such request F:..... V:..... T:.....			
23		Item	1.00	
	<u>Completion</u>			
	Clause 24.0 - Practical completion F:..... V:..... T:.....			
24		Item	1.00	25,000.00
	Clause 25.0 - Works completion F:..... V:..... T:.....			
25		Item	1.00	25,000.00
	Clause 26.0 - Final completion F:..... V:..... T:.....			
26		Item	1.00	25,000.00
	Clause 27.0 - Latent defects liability period F:..... V:..... T:.....			
27		Item	1.00	50,000.00
	Clause 28.0 - Sectional completion F:..... V:..... T:.....			
28		Item	1.00	19,000.00

Item	Description	Uom	Rate	Amount
29	Clause 29.0 - Revision of date for practical completion F:..... V:..... T:.....	Item	1.00	
30	Clause 30.0 - Penalty for late or non-completion F:..... V:..... T:.....	Item	1.00	
Total Carried Forward				808,000.30

Item	Description	Uom	Rate	Amount
	Total Brought Forward			808,000.30
	<u>Payment</u>			
31	Clause 31.0 - Interim payment Notwithstanding this or any other clause, payment for unfixed materials on Site shall be at the sole discretion of the Principal Agent. Clause 31.4.2 is amended by adding the following: "Materials and goods stored off site shall not be included in the amount authorised for payment." Clause 31.9 is amended to read: "The Employer shall pay to the Contractor the amount certified in an interim payment certificate within thirty (30) calendar days of the date for issue of the payment certificate. Payment shall be subject to the Contractor giving the Employer a tax invoice for the amount due. F:..... V:..... T:....."	Item	1.00	
32	Clause 32.0 - Adjustment to the contract value .Notwithstanding the provisions of clause 32.13 or any other clause all fluctuations in costs shall be for the account of the contractor. See also clause 41.4.6 No qualification in respect of fluctuations in cost in respect of labour, plant, materials, preliminaries, etc., will be accepted. All fluctuations in cost - inter alia - of labour, materials, taxes (excluding Value Added Tax) exchange rates, transport charges, plant, overheads, etc., after the closing tenders shall be to the Contractor's account. Rates tendered shall remain fixed irrespective of any fluctuations in the value of the Works, and shall remain so for the duration of the Contract, and also for any extension of the Contract Period granted by the Principal Agent. Where prices are submitted by the contractor or n/s subcontractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final payment certificate, it shall be in writing. F:..... V:..... T:.....	Item	1.00	
33	Clause 33.0 - Recovery of expense and loss F:..... V:..... T:.....	Item	1.00	
34	Clause 34.0 - Final account and final payment Clause 34.10 is amended to read: "The Employer shall pay to the Contractor the amount certified for payment in the Final Payment Certificate within thirty (30) calendar days of the date of issue of the Final Payment Certificate, subject to Contractor giving the Employer a Tax Invoice for the amount due". F:..... V:..... T:.....	Item	1.00	

Item	Description	Uom	Rate	Amount
35	Clause 35.0 - Payment to other parties F:..... V:..... T:..... <u>Termination</u>	Item	1.00	
36	Clause 36.0 - Termination by employer - contractor's default F:..... V:..... T:..... Total Carried Forward	Item	1.00	
				808,000.30

Item	Description	Uom	Rate	Amount
	Total Brought Forward			808,000.30
37	Clause 37.0 - Termination by employer - loss and damage F:..... V:..... T:.....	Item	1.00	
38	Clause 38.0 - Termination by contractor - employer's default F:..... V:..... T:.....	Item	1.00	
39	Clause 39.0 - Termination - cessation of the works F:..... V:..... T:.....	Item	1.00	
	<u>Dispute</u>			
40	Clause 40.0 - Settlement of disputes F:..... V:..... T:.....	Item	1.00	
	<u>Contract agreement</u>			
41	Clause 41.0 - Post tender provisions The required post tender information shall be inserted in the post tender provisions after consultation with the contractor	Item	1.00	
42	Clause 42.0 - Contractual agreement The required information of the contracting parties and the amount of the accepted contract sum shall be inserted in the contractual agreement for signature of the agreement by the contracting parties	Item	1.00	

Item	Description	Uom	Rate	Amount
	TOTAL SECTION A - CARRIED TO SUMMARY			808,000.30

Item	Description	Uom	Rate	Amount
	<u>SECTION B - PRELIMINARIES</u>			
	<u>Definitions and interpretation</u>			
43	Clause 1.0 - Definitions and interpretation F:..... V:..... T:.....	Item	1.00	
	<u>Documents</u>			
44	Clause 2.1 - Checking of documents F:..... V:..... T:.....	Item	1.00	
45	Clause 2.2 - Provisional bills of quantities 1. The work set out in these Bills of Quantities is provisional and the quantities and specifications do not purport to represent a final assessment of the work eventually required to be done. The quantities and specifications herein have been set down solely in order to form a basis for the obtaining of competitive tenders. 2. The Contractor shall be obliged, on instruction from the Principal Agent to execute such work as the Principal Agent in his sole discretion may consider necessary, whether or not such work is reflected in these Bills of Quantities or the Contract Drawings. 3. The value of work executed shall be determined by the Principal Agent by applying, or with reference to, the rates contained in the priced Bills of Quantities. The rates (or rates analogues to them) will be applied irrespective of changes to the scope or nature of the works instructed by the Principal Agent; and no claims for extras, variations, loss of profits; the basis for which is the use of any alternate method of pricing; will be entertained. 4. Provisional Sum Amounts, or Prime Cost Amounts may be replaced, reduced or omitted at the sole discretion of the Principal Agent, and no claim for loss of discount, profit, attendance mark-up percentage will be entertained. F:..... V:..... T:.....	Item	1.00	
46	Clause 2.3 - Availability of construction documentation The Tenderer shall together with his programme, submit the lead in periods for each area of sub-contract or independent activity. The Principal Agent shall, in his sole discretion determine the dates by which documentation should be prepared in order to meet the agreed construction programme. F:..... V:..... T:.....	Item	1.00	5,000.00
	<u>Previous work and adjoining properties</u>			
47	Clause 3.1 - Previous work - dimensional accuracy F:..... V:..... T:.....	Item	1.00	

Item	Description	Uom	Rate	Amount
48	Clause 3.2 - Previous work - defects F:..... V:..... T:.....	Item	1.00	
49	Clause 3.3 - Inspection of adjoining properties F:..... V:..... T:.....	Item	1.00	
Total Carried Forward				5,000.00

Item	Description	Uom	Rate	Amount
	Total Brought Forward			5,000.00
	<u>Samples, shop drawings and manufacturer's instructions</u>			
50	Clause 4.1 - Samples of materials F:..... V:..... T:.....	Item	1.00	1,000.00
51	Clause 4.2 - Workmanship samples The Principal Agent may instruct the Contractor to prepare certain samples or "mock-ups" of works to be executed. Once the workmanship and materials in such a sample is approved by the Principal Agent, he shall be entitled to reject any workmanship that does not correspond with the approved simple.The Contractor shall submit the samples or prepare the Mock-ups within a reasonable time of the request, and allow sufficient time for their consideration.F:..... V:..... T:.....	Item	1.00	
52	Clause 4.3 - Shop drawings F:..... V:..... T:.....	Item	1.00	3,000.00
53	Clause 4.4 - Compliance with manufacturer's instructions F:..... V:..... T:.....	Item	1.00	
	<u>Deposits and fees</u>			
54	Clause 5.1 - Deposits and fees F:..... V:..... T:.....	Item	1.00	
	<u>Temporary services</u>			
55	Clause 6.1 - Water F:..... V:..... T:.....	Item	1.00	
56	Clause 6.2 - Electricity F:..... V:..... T:.....	Item	1.00	
57	Clause 6.3 - Telecommunication facilities F:..... V:..... T:.....	Item	1.00	
58	Clause 6.4 - Ablution facilities F:..... V:..... T:.....	Item	1.00	
	<u>Prime cost amounts</u>			
59	Clause 7.1 - Responsibility for prime cost amounts F:..... V:..... T:.....	Item	1.00	
	<u>Special attendance on n/s subcontractors</u>			

Item	Description	Uom	Rate	Amount
60	Clause 8.1 - Special attendance F:..... V:..... T:.....	Item	1.00	
Total Carried Forward				9,000.00

Item	Description	Uom	Rate	Amount
	Total Brought Forward			9,000.00
	<u>General</u>			
61	Clause 9.1 - Protection of the works F:..... V:..... T:.....	Item	1.00	14,000.00
62	Clause 9.2 - Protection/isolation of existing/sectionally occupied works F:..... V:..... T:.....	Item	1.00	5,500.00
63	Clause 9.3 - Security of the works F:..... V:..... T:.....	Item	1.00	
64	Clause 9.4 - Notice before covering work F:..... V:..... T:.....	Item	1.00	1,500.00
65	Clause 9.5 - Disturbance F:..... V:..... T:.....	Item	1.00	
66	Clause 9.6 - Environmental disturbance F:..... V:..... T:.....	Item	1.00	15,000.00
67	Clause 9.7 - Works cleaning and clearing No claims for additional carting away of, or clearing of rubble of any description will be entertained. The Tenderer is to allow herein for all necessary cleaning; including a provision for cleaning waste not removed by sub-contractors. F:..... V:..... T:.....	Item	1.00	
68	Clause 9.8 - Vermin F:..... V:..... T:.....	Item	1.00	
69	Clause 9.9 - Overhand work F:..... V:..... T:.....	Item	1.00	
	<u>Schedule of variables</u>			
	Information necessary for elections and completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder. Where no information is given it shall mean that no specific requirements are expected or that the clause is not relevant to this specific contract			
	10.1 - ☒ Provisional bills of quantities [clause 2.2] The quantities are provisional ☒ Yes			
	10.2 - ☒ Availability of construction documentation [clause 2.3] ☒ Construction documentation is complete ☒ No			
	10.3 - ☒ Previous work - dimensional accuracy [clause 3.1]			

Item	Description	Uom	Rate	Amount
10.4 -	Previous work - defects [clause 3.2]			
10.5 -	Inspection of adjoining properties [clause 3.3]			
Total Carried Forward				45,000.00

Item	Description	Uom	Rate	Amount
	Total Brought Forward			45,000.00
	10.6 - W ater [clause 7.2] ☐			
	Option A (by contractor) Yes ☐			
	Option B (by employer - free of charge) No ☐			
	Option C (by employer - metered) No			
	10.7 - E lectricity [clause 7.3] ☐			
	Option A (by contractor) Yes ☐			
	Option B (by employer - free of charge) No ☐			
	Option C (by employer - metered) No			
	10.8 - T elecommunications [clause 7.4] ☐			
	Telephone ☒ Yes ☐			
	Facsimile ☒ Yes ☐			
	E-mail ☒ Yes			
	10.9 - A blution facilities [clause 7.5] ☐			
	Option A (by contractor) Yes ☐			
	Option B (by employer) No			
	10.10 - P rotection of the works [clause 9.1]			
	10.11 - P rotection/isolation of existing/sectionally occupied works [clause 9.2]			
	Protection/isolation is required ☐ Yes			
	10.12 - D isturbance [clause 9.5]			
	10.13 - E nvironmental disturbance [clause 9.6]			

Item	Description	Uom	Rate	Amount
	TOTAL SECTION B - CARRIED TO SUMMARY			45,000.00

Item	Description	Uom	Rate	Amount
<u>SECTION C - SPECIFIC PRELIMINARIES</u>				
70	Site instructions Instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the contractor F:..... V:..... T:.....	Item	1.00	6,000.00
71	Warranties for material and workmanship Where warranties for materials and/or workmanship are called for, the contractor shall obtain a written warranty, addressed to the employer, from the firm supplying the materials and/or doing the work and shall deliver same to the principal agent on the certified completion of the contract. The warranty shall state that workmanship, materials and installation are warranted for a specified period from the date of final completion and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice to do so. The warranty will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall rest entirely with the contractor F:..... V:..... T:.....	Item	1.00	56,000.00
72	Co-operation of contractor for cost management It is specifically agreed that the contractor accepts the obligation of assisting the principal agent in implementing proper cost management. The contractor will be advised by the principal agent of all cost management procedures which will be implemented to ensure that the final building cost does not exceed the budget. The principal agent undertakes to make available to the contractor all budgetary allowances and cost assessments/reports to enable the proper procedure to be implemented and the contractor shall attend all cost plan review and cost management meetings. The contractor undertakes to extend these procedures, as necessary, to all subcontractors F:..... V:..... T:.....	Item	1.00	45,000.00
73	Testing of windows for watertightness Each window shall be tested for watertightness with water sprayed on using adequate pressure. If in the opinion of the principal agent, the pressure proves to be inadequate, then the pressure shall be boosted by means of compressed air or other approved means F:..... V:..... T:.....	Item	1.00	25,000.00

Item	Description	Uom	Rate	Amount
	Total Carried Forward			132,000.00

Item	Description	Uom	Rate	Amount
	Total Brought Forward			132,000.00
74	Testing of flat roof waterproofing for watertightness Flat roof waterproof areas shall be prepared with small sand dykes around them of a size and enclosing an area approved by the principal agent, flooded with water and kept "ponded" for at least 36 hours as a test to ensure the watertightness of the waterproofing and before any further construction work is carried out above the waterproofing F:..... V:..... T:.....	Item	1.00	95,000.00
75	Non-Cession of Monies The Contractor shall not cede or assign his right or claims to any monies due to or to become due under this Contract. F:..... V:..... T:.....	Item	1.00	35,000.00
76	Proprietary Branded Products The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after construction with the manufacturer's authorised representative. F:..... V:..... T:.....	Item	1.00	15,000.00
77	Overtime Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the Principal Agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the Employer. F:..... V:..... T:.....	Item	1.00	25,000.00
78	Drawings on Site The Contractor shall maintain on Site at all times, a complete set of the latest revisions of the working drawings issued by the Architect, the Engineer, and the Electrical Consultant. F:..... V:..... T:.....	Item	1.00	3,000.00
79	Labour Record At the end of each week the contractor shall provide the Principal Agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day. F:..... V:..... T:.....	Item	1.00	65,000.00

Item	Description	Uom	Rate	Amount
80	Scaffolding No scaffolding is measured as these Bills of Quantities are based on the sixth edition of the Standard System for Measuring Building Work. However, the Tenderer is advised to study the drawings as scaffolding shall be required in certain areas for use by himself and selected/nominated subcontractors and the contractor must establish or otherwise required by him or selected/nominated subcontractor including taking down and re-erecting as may be necessary and no claims whatsoever will be entertained. F:..... V:..... T:.....	Item	1.00	45,000.00
Total Carried Forward				415,000.00

Item	Description	Uom	Rate	Amount
	Total Brought Forward			415,000.00
81	Plant Record At the end of each week the contractor shall provide the Principal Agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works. F:..... V:..... T:.....	Item	1.00	10,000.00
82	Daywork Where in the opinion of the Principal Agent any extra work cannot properly be measured or valued, the Contractor will be allowed daywork prices therefore calculated upon the costs defined hereunder together with the stated percentages. The total thus arrived at shall be the total amount recoverable by the Contractor for performing such work. 1. The costs to the Contractor or sub-contractor of materials, being the net cost (at current market prices) actually paid for such materials after the deduction of cash discounts or if materials are supplied from the Contractor's or sub-contractor's stock then the cost of such materials shall be based upon the current market price plus the cost of delivery to Site; to which net cost 7,5% thereof shall be added. 2. The cost of labour to the Contractor or sub-contractor, being all items of direct cost of labour actually remunerated to the workmen concerned which shall include the cost of all allowances in terms of the industrial Conciliation Act (where applicable) or any other wage determination applying in the area where the daywork is executed: to which labour cost 7,5% shall be added. Hourly base rates for labour shall be the current market rates for labour based upon standard working hours and shall be applied in respect of the time spent by workers directly engaged on the particular day works including any operators mechanical plant and transport and erecting and dismantling other plant. If a claim is made that individual workmen have been paid wages and allowances in excess of the minimum legalised rates, then proof must be furnished that such workmen had been so paid prior to the commencement of the daywork referred to. 3. The rate for mechanical plant shall be commercial hire rates current at the time of executing the daywork and shall include fuel and insurance	Item	1.00	15,000.00

Item	Description	Uom	Rate	Amount
	or executing the daywork and shall include fuel and insurance costs. The above percentages shall cover head office charges; Site staff including Site supervision; third party and Contractors workmen compensation and unemployment insurance fund contributions; use, repair and sharpening of non-mechanical hand tools; use of erected scaffolding, staging, trestles and the like; use of tarpaulins, protective clothing, artificial lighting, safety and welfare facilities, storage and the like as may be available on the Site; and profit. Supporting vouchers reflecting the time spent and materials used in each week shall be delivered for verification to the Principal Agent not later than twenty calendar days after the end of the week concerned. Should the Contractor fail to submit the vouchers within this time, the Principal Agent shall determine a fair price for the work. F:..... V:..... T:.....			
	Total Carried Forward			440,000.00

Item	Description	Uom	Rate	Amount
	Total Brought Forward			440,000.00
83	Unauthorised Persons/Workmen on Premises The Contractor shall at all times strictly exclude all unauthorized persons from the site and shall set up notice boards to that effect. F:..... V:..... T:.....	Item	1.00	85,000.00
84	Guarantees and Maintenance Instructions/Manuals The Contractor shall obtain and hand over to the Architect on Practical Completion, all relevant guarantees, any operating and maintenance manuals, data or instructions required by the Architect or provided by the Manufacturers, Suppliers, or Sub-contractors. The Contractor shall ensure that all warranties and guarantees received are fully ceded to the Employer on Final Completion, failing which the release of the Construction Guarantee will be withheld until this is satisfactorily completed. F:..... V:..... T:.....	Item	1.00	60,000.00
85	Shop Drawings The term "Shop Drawings" shall mean drawings, layout drawings, illustrations, schedules, performance charts, brochures, operating manuals, other data which are prepared by the Contractor or Sub-contractor, Manufacturer, Supplier or Distributor and which illustrate some portion of the work. The Contractor shall ensure that all shop drawings required for the work in terms of this Contract, all selected/nominated Sub-contracts and/or Architect's instructions, are prepared and submitted timeously in accordance with the following procedure: (a) Three prints of shop drawings of all fabricated work, working or setting out drawings, shop details and schedules shall be submitted to the Architect for approval. Such work shall not be carried out until such approval has been given. (b) Shop drawings shall be submitted to the Architect for approval at least two weeks prior to the date on which such approval is required in order to comply with the Contract Programme. (c) All submissions shall be prepared in accordance with the Contract Drawings and Specifications and/or any Architect's instructions and any deviation shall be specifically highlighted in writing, with a detailed explanation of the reason for such deviation, together with any cost and/or time implication. Delays in approval of shop drawings due to non-compliance with drawings, specifications and/or Architect's instructions shall not constitute grounds for any claims for delays. F:..... V:..... T:.....	Item	1.00	186,000.00

Item	Description	Uom	Rate	Amount
	Total Carried Forward			771,000.00

Item	Description	Uom	Rate	Amount
	Total Brought Forward			771,000.00
86	Location of Temporary Buildings and Temporary Services The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hardstanding, and services, etc., required for his own Sub-contractors use during the construction and maintenance period. There is no guarantee given or implied that site conditions will be such that the Contractor will be able to erect such offices, stores and temporary accommodation within the site boundaries and it shall be the Contractors responsibility to adopt whatever measures he deems necessary in this regard and to obtain all necessary permission and pay all costs in connection therewith. F:..... V:..... T:.....	Item	1.00	175,000.00
87	Removal and Making Good of Temporary Works, etc. on Completion The Contractor shall remove all temporary works, roads, services and the like used for this contract and shall make good to the entire satisfaction of the Architect any damages resulting therefrom. F:..... V:..... T:.....	Item	1.00	150,000.00
88	Indemnities Indemnities shall be sought by the Architect from all Contractors and Sub-contractors undertaking any design responsibility. F:..... V:..... T:.....	Item	1.00	275,000.00
89	Cost of Claims Costs incurred by the Contractor in the preparation of claims accepted by the Principal Agent shall be borne by the Contractor. F:..... V:..... T:.....	Item	1.00	
90	Overloading The Contractor shall take all necessary steps to ensure that no damage occurs due to overloading of any portion of the works. The Contractor shall submit details of his proposed loading, storage, plant, erection, etc., to the Architect for their approval prior to proceeding with such loading, storing or erecting and shall comply with and pay for the Engineer's requirements in connection with the provision of temporary support work, etc. Any damage caused to the works by overloading shall be made good by the Contractor at his sole expense. F:..... V:..... T:.....	Item	1.00	100,000.00

Item	Description	Uom	Rate	Amount
91	Commodities to be New All commodities, goods, articles or materials throughout the building are to be new except where re-use of existing is specified and are to be handled, stored, used and/or fixed with care to ensure that they are in perfect condition when incorporated into the works and thereafter properly protected so as to ensure that they are likewise in perfect condition when handed over at completion of the works. F:..... V:..... T:.....	Item	1.00	
	Total Carried Forward			1,471,000.00

Item	Description	Uom	Rate	Amount
	Total Brought Forward			1,471,000.00
92	Media Release All rights of publication of articles in the media, together with any advertising relating to, or in any way connected with this project shall vest in the Employer. The Contractor, together with his Sub-contractors shall not, without the written consent of the Employer, cause any statement or advertisement to be printed, screened or aired by the media. F:..... V:..... T:.....	Item	1.00	135,000.00
93	Environmental Management Plan The contractor shall take all necessary measures to comply with the Environmental Management Plan (EMP) and make adequate provision to accommodate the requirements of the EMP. F:..... V:..... T:.....	Item	1.00	135,000.00
94	Transformation and Empowerment Requirements The contractor shall take all necessary measures to comply with empowerment as per Ekurhuleni Metropolitan requirements and make adequate provision to accommodate the requirements relating to job creation, job intensity, training and development, local SMME utilisation, local material utilisation, enterprise development, etc. F:..... V:..... T:.....	Item	1.00	200,000.00
95	Covid19 Compliance Requirements: The contractor shall take all necessary precautions to comply with all available measures to make sure the spread of the virus is controlled by including provision of equipment and PPE such as providing masks, sanitisers, thermometers, screening of employees for any symptoms etc. all in accordance with the OHS amended ACT and Baseline/guidline to be provided by the client F:..... V:..... T:.....	Item	1.00	200,000.00

Item	Description	Uom	Rate	Amount
	TOTAL SECTION C - CARRIED TO SUMMARY			2,141,000.00

Item	Description	Uom	Rate	Amount
	<u>SUMMARY OF CATEGORIES</u>			
1	SECTION A - PRINCIPAL BUILDING AGREEMENT			808,000.30
2	SECTION B - PRELIMINARIES			45,000.00
3	SECTION C - SPECIFIC PRELIMINARIES			2,141,000.00

Item	Description	Uom	Rate	Amount
	Total Carried to Final Summary Page			2,994,000.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>BILL NO. 2</u>				
	<u>ALTERATIONS (PROVISIONAL)</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	Site inspection Contractors are required to inspect the site and acquaint themselves with all aspects of the works to be executed under this contract prior to the submission of their tender. No claim whatsoever will be entertained in the event of any unforeseen difficulties arising during the execution of the contract that could have been foreseen by a thorough investigation of the site, drawings and specifications.				
	The contractor shall carry out the whole of the Works with as little mess and noise as possible and with a minimum of disturbance to adjoining premises and their tenants/occupants. he/she shall provide proper protection and provide, erect and maintain in position proper temporary tarpaulins that may ne necessary to protect existing fixtures, fittings and furniture during the progress of the works and remove on completion or when directed, all to the satisfaction of the Project Manager/ Principal Agent				
	Water supply pipes and other piping that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings, to the satisfaction of the Project Manager/Principal Agent				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	Doors, fanlights, fittings, frames, linings, etc which are to be re-used shall be thoroughly overhauled before re-fixing, including taking off, easing and re-hanging, cramping up, re-wedging as required and making good cramps, dowels, etc, and easing, oiling, adjusting and repairing ironmongery as necessary, replacing any glass damaged in removal or subsequently and stopping up all nail and screw holes with tinted plastic wood to match timber, unless otherwise described. Re-painting or re-vanishing is given separately				
	Prices for taking out doors, windows, etc. shall include for removal of all beads, architraves, ironmongery, etc				
	Prices for taking out and removing doors and frames shall include for removing door stops, cabin hooks, etc. and making good floor and wall finishes to match existing				
	With regards to building up of openings in existing walls, cement screeds and paving, granolithic, tops of walls, etc. shall be levelled and prepared for raising of brickwork				
	Making good finishes shall include making good of the brick and concrete surfaces onto which the new finishes are applied, where necessary				
	The contractor will be required to take all dimensions affecting the existing buildings on the site and he will be held solely responsible for the accuracy of all such dimensions where used in the manufacture of new items (Doors, windows, fittings, etc)				
	<u>TEMPORARY BARRIERS, SCREENS, ETC.</u>				
	<u>Temporary barriers, screens, etc., including removal</u>				
1	Half brick barrier wall 3000mm high including cement plaster and two coats interior quality PVA emulsion paint on one side.	m	85	988.27	84,002.95
2	Dust screen 3000mm high between concrete floor and ceiling formed of suitable timber framing with 250 micron polyethylene sheeting stapled on including corners, ends, etc.	m	85	196.35	16,689.75
3	Dust screen 3600mm high between concrete floor and ceiling formed of suitable timber framing with 250 micron polyethylene sheeting stapled on including corners, ends, etc.	m	85	236.67	20,116.95

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
4	Drywall barrier 3000mm high formed of galvanised steel channel section rails and studs covered on one side with 12,7mm gypsum board panels and finished with two coats interior quality PVA emulsion paint on one side including corners, ends, etc.	m	85	750.00	63,750.00
5	Drywall barrier 3600mm high formed of galvanised steel channel section rails and studs covered on one side with 12,7mm gypsum board panels and finished with two coats interior quality PVA emulsion paint on one side including corners, ends, etc.	m	85	750.00	63,750.00
6	Drywall barrier 3600mm high formed of galvanised steel channel section rails and studs covered on one side with 12,7mm gypsum board panels and finished with two coats interior quality PVA emulsion paint on one side including corners, ends, etc.	m	85	950.00	80,750.00
	<u>REMOVAL OF EXISTING WORK</u>		85		0.00
	<u>Break up and removing mass concrete</u>		85		0.00
7	Steps	m ²	85	209.36	17,795.60
8	85mm thick surface bed	m ²	85	18.21	1,547.85
9	150mm thick surface bed	m ²	85	31.21	2,652.85
	<u>Break up and removing reinforced concrete including cutting off and removing reinforcement</u>				
10	Steps and landings	m ³	85	650.00	55,250.00
11	Beams	m ³	85	650.00	55,250.00
12	Columns	m ³	85	650.00	55,250.00
13	250mm thick slabs	m ²	350	162.50	56,875.00
14	Opening through 250mm thick slab not exceeding 2,5m ²	No	335	172.95	57,938.25
	<u>Breaking down and removing brickwork etc.</u>		350		0.00
15	Mass brickwork	m ³	350	226.26	79,191.00
16	Half brick wall	m ²	350	62.10	21,735.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
17	One brick wall	m ²	350	81.62	28,567.00
18	One and a half brick wall	m ²	350	103.72	36,302.00
19	280mm Hollow walls of two half brick skins	m ²	350	103.72	36,302.00
	<u>Taking out and removing doors, windows, etc. from brickwork to be demolished</u>				
20	Timber single door and frame not exceeding 2,5m ²	No	350	115.00	40,250.00
21	Timber double door and frame exceeding 2,5m ² and not exceeding 5,0m ²	No	350	193.76	67,816.00
22	Timber single door and steel frame not exceeding 2,5m ²	No	350	115.73	40,505.50
23	Timber double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ²	No	200	231.46	46,292.00
24	Timber single door not exceeding 2,5m ²	No	200	68.11	13,622.00
25	Timber double door exceeding 2,5m ² and not exceeding 5,0m ²	No	200	97.83	19,566.00
26	Steel single door and steel frame not exceeding 2,5m ²	No	200	115.73	23,146.00
27	Steel double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ²	No	300	231.46	69,438.00
28	Glazed timber window not exceeding 2,5m ²	No	300	134.72	40,416.60
29	Glazed timber window exceeding 2,5m ² and not exceeding 5,0m ²	No	300	271.26	81,379.20
30	Glazed steel window not exceeding 2,5m ²	No	300	162.02	48,606.60
31	Glazed steel window exceeding 2,5m ² and not exceeding 5,0m ²	No	300	324.04	97,213.20
32	Glazed aluminium window not exceeding 2,5m ²	No	300	162.02	48,606.60
33	Glazed aluminium window exceeding 2,5m ² and not exceeding 5,0m ²	No	300	324.04	97,213.20
	<u>Taking out and removing doors, windows, etc. including thresholds, sills, etc. (building up openings elsewhere)</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
34	Timber single door and frame not exceeding 2,5m ² from half or one brick wall	No	142	271.26	38,519.49
35	Timber single door and frame exceeding 2,5m ² and not exceeding 5,0m ² from half or one brick wall	No	118	257.47	30,381.46
36	Timber double door and frame not exceeding 2,5m ² from half or one brick wall	No	120	283.48	34,017.60
37	Timber double door and frame exceeding 2,5m ² and not exceeding 5,0m ² from half or one brick wall	No	120	309.49	37,138.80
38	Timber single door and steel frame not exceeding 2,5m ² from half brick wall	No	165	211.96	34,973.40
39	Timber single door and steel frame not exceeding 2,5m ² from one brick wall	No	128	231.46	29,626.88
40	Timber double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from half brick wall	No	150	283.48	42,522.00
41	Timber double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	118	309.49	36,519.82
42	Steel single door and frame not exceeding 2,5m ² from half or one brick wall	No	120	211.96	25,435.20
43	Steel double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from half brick wall	No	120	309.49	37,138.80
44	Steel double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	120	309.49	37,138.80
45	Glazed timber window not exceeding 2,5m ² from half or one brick wall	No	120	193.76	23,251.20
46	Glazed timber window exceeding 2,5m ² and not exceeding 5,0m ² from half or one brick wall	No	120	257.47	30,896.40
47	Glazed steel window not exceeding 2,5m ² from half or one brick wall	No	120	202.85	24,342.00
48	Glazed steel window exceeding 2,5m ² and not exceeding 5,0m ² from half or one brick wall	No	120	283.48	34,017.60
49	Glazed aluminium window not exceeding 2,5m ² from half or one brick wall	No	120	202.85	24,342.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
50	Glazed aluminium window exceeding 2,5m ² and not exceeding 5,0m ² from half or one brick wall	No	120	283.48	34,017.60
	<u>Taking out doors, windows, etc. including thresholds, sills, etc. and setting aside for re-use (refaxing and building up openings elsewhere)</u>				
51	Timber single door and frame not exceeding 2,5m ² from half or one brick wall	No	98	211.96	20,772.08
52	Timber single door and frame exceeding 2,5m ² and not exceeding 5,0m ² from half or one brick wall	No	98	283.48	27,781.04
53	Timber single door and steel frame not exceeding 2,5m ² from half brick wall	No	98	234.06	22,937.88
54	Timber single door and steel frame not exceeding 2,5m ² from one brick wall	No	98	254.87	24,977.26
55	Timber double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from half brick wall	No	98	312.09	30,584.82
56	Timber double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	98	339.39	33,260.22
57	Steel single door and steel frame not exceeding 2,5m ² from half or one brick wall	No	98	254.87	24,977.26
58	Steel double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from half brick wall	No	98	312.09	30,584.82
59	Steel double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	98	339.39	33,260.22
60	Aluminium single door and frame not exceeding 2,5m ² from half or one brick wall	No	98	211.96	20,772.08
61	Aluminium single door and frame exceeding 2,5m ² and not exceeding 5,0m ² from half or one brick wall	No	109	283.48	30,899.32
62	Aluminium double door and frame exceeding 2,5m ² and not exceeding 5,0m ² from half brick wall	No	88	312.09	27,463.92
63	Aluminium double door and frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	98	339.39	33,260.22

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
64	Glazed timber window not exceeding 2,5m ² from half or one brick wall	No	71	211.96	15,049.16
65	Glazed timber window exceeding 2,5m ² and not exceeding 5,0m ² from half or one brick wall	No	98	283.48	27,781.04
66	Glazed steel window not exceeding 2,5m ² from half or one brick wall	No	98	223.66	21,918.68
67	Glazed steel window exceeding 2,5m ² and not exceeding 5,0m ² from half or one brick wall	No	98	312.09	30,584.82
68	Glazed aluminium window not exceeding 2,5m ² from half or one brick wall	No	98	223.66	21,918.68
69	Glazed aluminium window exceeding 2,5m ² and not exceeding 5,0m ² from half or one brick wall	No	98	312.09	30,584.82
70	Steel roller shutter door not exceeding 2,5m ² from half or one brick wall	No	98	201.55	19,751.90
71	Steel roller shutter door exceeding 2,5m ² and not exceeding 5,0m ² from half or one brick wall	No	98	283.48	27,781.04
72	Steel roller shutter door exceeding 5,0m ² from half or one brick wall	No	98	422.62	41,416.76
	<u>Taking out and removing doors, windows, etc. including thresholds, sills, etc. and building up openings in brick walls including making good cement plaster on both sides (making good paintwork elsewhere)</u>				0.00
73	Timber single door and frame not exceeding 2,5m ² from half brick wall	No	35	972.67	34,043.45
74	Timber single door and frame not exceeding 2,5m ² from one brick wall	No	31	1,699.56	52,686.36
75	Timber single door and frame exceeding 2,5m ² and not exceeding 5,0m ² from half brick wall	No	35	1,821.79	63,762.65
76	Timber single door and frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	27	3,215.76	86,825.52
77	Timber single door and steel frame not exceeding 2,5m ² from half brick wall	No	39	992.16	38,694.24

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
78	Timber single door and steel frame not exceeding 2,5m ² from one brick wall	No	47	1,729.46	81,284.62
79	Timber double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from half brick wall	No	35	1,855.60	64,946.00
80	Timber double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	42	3,267.78	137,246.76
81	Steel single door and steel frame not exceeding 2,5m ² from half brick wall	No	35	992.16	34,725.60
82	Steel single door and steel frame not exceeding 2,5m ² from one brick wall	No	35	1,729.46	60,531.10
83	Steel single door and steel frame not exceeding 2,5m ² from one brick wall	No	35	1,855.60	64,946.00
84	Steel double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,267.78	114,372.30
85	Aluminium single door and frame not exceeding 2,5m ² from half brick wall	No	35	992.16	34,725.60
86	Aluminium single door and frame not exceeding 2,5m ² from one brick wall	No	16	1,729.46	27,671.36
87	Aluminium double door and frame exceeding 2,5m ² and not exceeding 5,0m ² from half brick wall	No	26	1,855.60	48,245.60
88	Aluminium double door and frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,267.78	114,372.30
89	Glazed timber window not exceeding 2,5m ² from half brick wall	No	48	972.67	46,688.16
90	Glazed timber window not exceeding 2,5m ² from one brick wall	No	35	1,699.56	59,484.60
91	Glazed timber window exceeding 2,5m ² and not exceeding 5,0m ² from half brick wall	No	52	1,821.79	94,733.08
92	Glazed timber window exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,267.78	114,372.30
93	Glazed steel window not exceeding 2,5m ² from half brick wall	No	35	992.16	34,725.60

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
94	Glazed steel window not exceeding 2,5m ² from one brick wall	No	35	1,729.46	60,531.10
95	Glazed steel window exceeding 2,5m ² and not exceeding 5,0m ² from half brick wall	No	35	1,855.60	64,946.00
96	Glazed steel window exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,267.78	114,372.30
97	Glazed aluminium window not exceeding 2,5m ² from half brick wall	No	35	992.16	34,725.60
98	Glazed aluminium window not exceeding 2,5m ² from one brick wall	No	46	1,729.46	79,555.16
99	Glazed aluminium window exceeding 2,5m ² and not exceeding 5,0m ² from half brick wall	No	26	1,855.60	48,245.60
100	Glazed aluminium window exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,267.78	114,372.30
101	Timber shopfront exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,267.78	114,372.30
102	Timber shopfront exceeding 5,0m ² from one brick wall	No	35	4,901.67	171,558.45
	<u>Taking out and removing doors, windows, etc. including thresholds, sills, etc. and building up openings in brick walls including making good face brickwork on one side and cement plaster on other side (making good paintwork elsewhere)</u>		35		0.00
103	Timber single door and frame not exceeding 2,5m ² from one brick wall	No	35	2,012.95	70,453.25
104	Timber single door and frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,843.84	134,534.40
105	Timber single door and steel frame not exceeding 2,5m ² from one brick wall	No	35	2,042.85	71,499.75
106	Timber double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,894.56	136,309.60
107	Steel single door and steel frame not exceeding 2,5m ² from one brick wall	No	35	2,042.85	71,499.75
108	Steel double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,894.56	136,309.60

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
109	Glazed timber window not exceeding 2,5m ² from one brick wall	No	35	2,012.95	70,453.25
110	Glazed timber window exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,843.84	134,534.40
111	Glazed steel window not exceeding 2,5m ² from one brick wall	No	35	2,042.85	71,499.75
112	Glazed steel window exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,894.56	136,309.60
113	Glazed aluminium window not exceeding 2,5m ² from one brick wall	No	35	2,042.85	71,499.75
114	Glazed aluminium window exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,894.56	136,309.60
	<u>Taking out and removing doors, windows, etc. including thresholds, sills, etc. and building up openings in brick walls including making good face brickwork on both side.</u>				
115	Timber single door and frame not exceeding 2,5m ² from one brick wall	No	35	2,366.64	82,832.40
116	Timber single door and frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	4,548.64	159,202.40
117	Timber single door and steel frame not exceeding 2,5m ² from one brick wall	No	35	2,395.26	83,834.10
118	Timber single door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	2,802.26	98,079.10
119	Timber double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	4,600.64	161,022.40
120	Steel single door and steel frame not exceeding 2,5m ² from one brick wall	No	35	2,802.26	98,079.10
121	Steel single door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	3,278.19	114,736.65
122	Steel double door and steel frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	4,600.64	161,022.40

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
123	Aluminium single door and frame not exceeding 2,5m ² from one brick wall	No	35	2,395.26	83,834.10
124	Aluminium single door and frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	2,802.26	98,079.10
125	Aluminium double door and frame exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	4,600.64	161,022.40
126	Glazed timber window not exceeding 2,5m ² from one brick wall	No	35	2,366.64	82,832.40
127	Glazed timber window exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	4,548.64	159,202.40
128	Glazed steel window not exceeding 2,5m ² from one brick wall	No	35	2,395.26	83,834.10
129	Glazed steel window exceeding 2,5m ² and not exceeding 5,0m ² from one brick wall	No	35	4,600.64	161,022.40
			35		0.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Refaxing of existing doors, windows, etc. (removal and setting aside elsewhere)</u>				
130	Setting up and building in timber door frame 813 x 2032mm high in brickwork, rehanging single door on new 100mm brass hinges and replacing lock with four lever mortice lock	No	35	906.34	31,721.90
131	Setting up and building in steel door frame 813 x 2032mm high in brickwork, re- hanging single door and replacing lock with four lever mortice lock	No	35	906.34	31,721.90
132	Setting up and building in steel door frame 813 x 2032mm high, including fanlight 813 x 305mm high in brickwork, rehanging single door and replacing lock with four lever mortice lock	No	35	906.34	31,721.90
133	Setting up and building in timber double door frame 1600 x 2032mm high in brickwork, rehanging double door on new 100mm brass hinges and replacing lock with four lever mortice lock including rebated conversion set	No	35	1,360.16	47,605.60
134	Setting up and building in steel double door frame 1600 x 2032mm high, including fanlight 1600 x 305mm high in brickwork, rehanging double door and replacing lock with four lever mortice lock including rebated conversion set	No	35	1,360.16	47,605.60
135	Setting up steel window not exceeding 1,0m ² in brickwork and replacing any broken glass panes with 4mm clear float glass	No	68	331.59	22,548.12
136			68		0.00
136	Setting up wooden window not exceeding 1,0m ² in brickwork and replacing any broken glass panes with 4mm clear float glass	No	68	331.59	22,548.12
137	Setting up steel window not exceeding 1,0m ² in brickwork and replacing any broken glass panes with 4mm patterned glass	No	68	413.51	28,118.68
138	Setting up wooden window not exceeding 1,0m ² in brickwork and replacing any broken glass panes with 4mm patterned glass	No	68	413.51	28,118.68
139	Setting up steel window exceeding 1,0m ² and not exceeding 2,0m ² in brickwork and replacing any broken glass panes with 4mm clear float glass	No	68	579.96	39,437.28
140	Setting up wooden window exceeding 1,0m ² and not exceeding 2,0m ² in brickwork and replacing any broken glass panes with 4mm clear float glass	No	68	579.96	39,437.28

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
141	Setting up wooden window exceeding 1,0m ² and not exceeding 2,0m ² in brickwork and replacing any broken glass panes with 4mm clear float glass	No	68	695.69	47,306.92
142	Setting up wooden window exceeding 1,0m ² and not exceeding 2,0m ² in brickwork and replacing any broken glass panes with 4mm patterned glass	No	68	695.69	47,306.92
143	Setting up steel window exceeding 2,0m ² and not exceeding 3,0m ² in brickwork and replacing any broken glass panes with 4mm clear float glass	No	17	1,014.27	17,242.59
144	Setting up wooden window exceeding 2,0m ² and not exceeding 3,0m ² in brickwork and replacing any broken glass panes with 4mm clear float glass	No	17	1,014.27	17,242.59
145	Setting up steel window exceeding 2,0m ² and not exceeding 3,0m ² in brickwork and replacing any broken glass panes with 4mm patterned glass	No	17	1,217.12	20,691.04
146	Setting up wooden window exceeding 2,0m ² and not exceeding 3,0m ² in brickwork and replacing any broken glass panes with 4mm patterned glass	No	17	1,217.12	20,691.04
	<u>Removing, cutting and refaxing of door to specified heights as per site condition, eg: tile and floor covering</u>				
147	Single wooden door 813 x 2032mm high	No	63	218.46	13,762.73
148	Double wooden door 1600 x 2032mm high	No	63	358.62	22,593.31
149	Single aluminium glass door 813 x 2032mm high	No	63	564.37	35,555.18
150	Double aluminium door 1600 x 2032mm high	No	63	819.22	51,611.11
	<u>Taking down and removing roofs, floors, panelling, ceilings, partitions, etc.</u>				
151	Corrugate sheet iron roof covering, valley linings, ridge flashings and timber purlins	m ²	500	46.90	23,450.00
152	Concrete, Harveytile sheet iron tile, slate, thatch, etc. roof covering, valley linings, ridge, hip cappings, flashings and timber brandering,purlins, etc.	m ²	232	74.76	17,344.32

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
153	Pitched corrugated iron roof 10000 x 10000 by not exceeding 2000mm high overall including roof covering, timber trusses, ceilings and cornices, eaves soffit covering, fascias, barge boards, gutters and rainwater pipes	m ²	289	137.31	39,682.59
154	Timber rafters, beams, etc	m	895	7.80	6,981.00
155	Tongued and grooved timber suspended floor including skirting, joists, bearers, etc.	m ²	569	56.90	32,376.10
156	Gypsum plasterboard ceilings including cornices, timber brandering, etc	m ²	765	16.90	12,928.50
157	Flush plastered gypsum plasterboard suspended ceilings, including cornices, suspension grid, hangers, etc.	m ²	658	29.13	19,170.17
158	Flush plastered gypsum plasterboard bulkheads, including cornices, suspension grid, hangers, etc.	m ²	478	50.81	24,287.18
159	Wood panel bulkheads, including cornices, suspension grid, hangers, etc.	m ²	478	50.90	24,330.20
160	Acoustic tiles suspended ceiling including suspension grid, hangers, etc.	m ²	478	50.90	24,330.20
161	Acoustic tiles suspended ceiling only	m ²	478	11.84	5,661.43
162	Drywall partitioning 3000mm high including doors, ironmongery, glazed borrowed lights, etc	m	478	86.81	41,495.18
163	Carefully cut out rusted or damaged roof sheeting	m ²	478	30.81	14,727.18
	<u>Taking down and removing rainwater goods</u>				
164	100 x 125mm Box gutters including downpipes	m	812	10.92	8,867.04
	<u>Taking out and removing sundry joinery work</u>				
165	Timber cornices from brickwork	m	812	8.60	6,983.20
166	Timber skirting from brickwork	m	812	8.60	6,983.20
167	Timber or asbestos cement sills from brickwork	m	812	8.60	6,983.20
168	Timber or asbestos cement fascias and barge boards	m	812	8.60	6,983.20
	<u>Taking out and removing joinery fittings etc</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
169	Timber wall cupboard 600 x 300 x 900mm high	No	77	154.62	11,905.74
170	Timber wall cupboard 900 x 300 x 900mm high	No	77	154.62	11,905.74
171	Timber wall cupboard 1200 x 300 x 900mm high	No	77	167.62	12,906.74
172	Timber floor cupboard 600 x 600 x 900mm high	No	77	154.62	11,905.74
173	Timber floor cupboard 900 x 600 x 900mm high	No	77	154.62	11,905.74
174	Timber floor cupboard 1200 x 600 x 900mm high	No	77	167.62	12,906.74
175	Timber sink cupboard 900 x 600 x 900mm high including disconnecting waste pipe and taps	No	77	265.02	20,406.54
176	Timber sink cupboard 1200 x 600 x 900mm high including disconnecting waste pipe (new trap and connecting to new waste pipe elsewhere)	No	77	280.62	21,607.74
177	Timber sink cupboard 1800 x 600 x 900mm high including disconnecting waste pipe (new trap and connecting to new waste pipe elsewhere)	No	77	220.94	17,012.38
178	Timber counter 1200 x 600 x 900mm high	No	77	99.47	7,658.81
179	Timber counter 1600 x 600 x 900mm high	No	77	99.47	7,658.81
180	Timber counter 1800 x 600 x 900mm high	No	77	99.47	7,658.81
181	Timber counter 2400 x 600 x 900mm high	No	77	99.47	7,658.81
	<u>Taking out and removing joinery fittings etc, setting aside for re-use and later refixing in new position</u>				
182	Timber wall cupboard 600 x 300 x 900mm high	No	36	159.81	5,753.16
183	Timber wall cupboard 900 x 300 x 900mm high	No	36	159.81	5,753.16
184	Timber wall cupboard 1200 x 300 x 900mm high	No	36	174.12	6,268.32
185	Timber floor cupboard 600 x 600 x 900mm high	No	36	159.81	5,753.16
186	Timber floor cupboard 900 x 600 x 900mm high	No	36	159.81	5,753.16
187	Timber floor cupboard 1200 x 600 x 900mm high	No	36	174.12	6,268.32

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
188	Timber sink cupboard 900 x 600 x 900mm high including disconnecting waste pipe and taps	No	36	174.12	6,268.32
189	Timber sink cupboard 1200 x 600 x 900mm high including disconnecting waste pipe (new trap and connecting to new waste pipe elsewhere)	No	36	189.72	6,829.92
190	Timber sink cupboard 1800 x 600 x 900mm high including disconnecting waste pipe (new trap and connecting to new waste pipe elsewhere)	No	36	133.94	4,821.84
191	Timber counter 1200 x 600 x 900mm high	No	36	99.47	3,580.74
192	Timber counter 1600 x 600 x 900mm high	No	36	99.47	3,580.74
193	Timber counter 1800 x 600 x 900mm high	No	36	99.47	3,580.74
194	Timber counter 2400 x 600 x 900mm high	No	36	99.47	3,580.74

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Take up and remove wooden wall panneling, vinyl wall covering, wall carpeting, waterproofing, etc.</u>				
195	Wood panels including preparing walls for new finishes.	m ²	372	66.90	24,886.80
196	Vinyl wall covering including preparing walls for new finishes.	m ²	372	60.40	22,468.80
197					
	Carpet wall covering including preparing walls for new finishes.	m ²	372	60.40	22,468.80
198					
	Derbigum waterproofing from vertical roof sheeting, walls, etc.	m ²	372	62.52	23,257.44
					0.00
	<u>Take up and remove wood block floor covering, vinyl floor covering, carpeting, waterproofing, etc.</u>				0.00
					0.00
199	Wood block floor covering including preparing screed for new floor covering.	m ²	364	66.90	24,351.60
200	Vinyl tile floor covering including preparing screed for new floor covering.	m ²	364	60.40	21,985.60
201	Vinyl sheet floor covering with welded joints including preparing screed for new floor covering.	m ²	364	60.40	21,985.60
202					
	Carpet tile floor covering including preparing screed for floor covering	m ²	364	60.40	21,985.60
203					
	Carpet sheet floor covering including preparing screed for floor covering	m ²	364	60.40	21,985.60
204					
	Derbigum waterproofing from roof sheeting, wood flooring, etc.	m ²	364	52.52	19,117.28
	<u>Taking out and removing ironmongery</u>				
205					
	Mortice lock and striking plate from timber door and steel frame	No	13	15.20	197.60
206					
	Mortice lock and striking plate from timber door and wooden frame	No	13	15.20	197.60
207	Mortice lock and rebate conversion set from timber doors	No	13	15.20	197.60
208	Mortice lock and rebate conversion set from steel doors	No	13	15.63	203.19
209	Metal striking plate from steel door frame	No	13	15.20	197.60

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
210	Metal striking plate from timber door frame	No	13	15.20	197.60
211	Overhead door closer	No	13	22.10	287.30
212	150mm Metal cabin hook and eye including chamfered hardwood block	No	13	15.00	195.00
213	Chromium plated towel rail not exceeding 1000mm long	No	13	15.00	195.00
214	Chromium plated toilet roll holder	No	13	15.00	195.00
215	Chromium plated hat and coat hook	No	13	15.00	195.00
216	Side hung window catch	No	13	22.10	287.30
217	Side or top hung window stay	No	13	22.10	287.30
	<u>Taking out/off and removing sundry metalwork</u>				
218	Steel pipe handrail from walls including making good plaster finish	m	89	32.52	2,894.28
219	Steel balustrade 900mm high from concrete stairs including making good granolithic finish to kerb	m	89	65.02	5,786.78 0.00
220	Steel staircase comprising two flights and one landing, 3,5 x 2,00m overall on plan and rising 3,20m, including supporting columns, balustrades, etc.	No	12	1,874.64	22,495.68
221	Steel wire mesh burglar proofing not exceeding 1,0m ² bolted to brickwork and making good face brickwork	No	12	65.51	786.12
222	Steel wire mesh burglar proofing exceeding 1,0m ² and not exceeding 2,0m ² bolted to brickwork and making good face brickwork	No	12	92.33	1,107.96
223	Steel wire mesh burglar proofing exceeding 2,0m ² and not exceeding 3,0m ² bolted to brickwork and making good face brickwork	No	12	137.83	1,653.96
224	Steel single leaf security gate not exceeding 2,5m ²	No	12	114.43	1,373.16
225	Steel double leaf security gate exceeding 2,5m ² and not exceeding 5,0m ²	No	12	228.86	2,746.32
226	Sheet metal eaves gutters and rainwater down pipes	No	12	9.11	109.32

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Hacking up/off and removing granolithic, screeds, plaster, etc from concrete or brickwork and preparing surfaces for new screeds, plaster, etc.</u>				
227	30mm Granolithic from floors	m ²	275	50.81	13,972.75
228	30mm Granolithic from treads and risers of stairs	m ²	275	52.10	14,327.50
229	Granolithic skirting 100mm high	m	98	14.30	1,401.40
230	30mm Screed from floors	m ²	275	50.81	13,972.75
231	Internal plaster from walls and columns	m ²	275	52.10	14,327.50
232	Internal plaster from ceilings and beams	m ²	275	58.61	16,117.75
233	External plaster from walls, columns and beams	m ²	275	52.10	14,327.50
	<u>Hacking up/off and removing ceramic tile floor and wall finishers including removing mortar bed or backing and preparing concrete or brick surfaces for new screed, plaster or tile finishers</u>				
234	Tiles to floors	m ²	275	50.81	13,972.75
235	Tiles to treads and risers of stairs	m ²	275	52.10	14,327.50
236	Tiles to walls	m ²	275	52.10	14,327.50
237	Tile skirting 100mm high	m	98	14.30	1,401.40
	<u>Sandblasting to finished surfaces</u>				
238	Wall plaster	m ²	100	84.62	8,462.00
239	Floor screeds	m ²	100	84.62	8,462.00
	<u>Taking out and cleaning</u>				
240	Expansion joints not exceeding 300mm deep and prepare to receive new	m	98	62.41	6,116.18
	<u>Scraping off paint in bad conditions and prepare for new paint</u>				
241	On plaster	m ²	100	22.10	2,210.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
242	On gamma zenith	m ²	100	32.10	3,210.00
243	On Ceilings	m ²	100	25.60	2,560.00
244	On Metal roofs, doors, frames, etc.	m ²	100	25.60	2,560.00
245	On Wood	m ²	100	25.60	2,560.00
	<u>IN HERITAGE BUILDINGS - Scraping off paint in bad conditions and prepare for new paint</u>				
246	On plaster	m ²	100	33.16	3,316.00
247	On gamma zenith	m ²	100	33.16	3,316.00
248	On Ceilings	m ²	100	23.40	2,340.00
249	On Metal roofs, doors, frames, etc.	m ²	100	23.40	2,340.00
250	On Wood	m ²	100	23.40	2,340.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Taking out and removing piping, sanitary fittings, etc including disconnecting piping from fittings and making good floor and wall finishes (making good tiling and paintwork elsewhere)</u>		18		
251	110mm PVC piping including fittings and brackets	m	18	10.41	187.38
252	75mm PVC piping including fittings and brackets	m	18	10.41	187.38
253	75mm Galvanised steel piping including fittings and brackets	m	18	10.41	187.38
254	25mm Galvanised steel piping including fittings and brackets	m	18	10.41	187.38
255	40mm Galvanised steel piping including fittings and brackets	m	18	10.41	187.38
256	100mm Cast iron piping including fittings and brackets	m	18	19.11	343.98
257	15mm Copper piping including fittings and brackets	m	18	5.41	97.38
258	22mm Copper piping including fittings and brackets	m	18	5.41	97.38
259	32mm Copper piping including fittings and brackets	m	18	5.41	97.38
260	Stainless steel wash hand basin	No	6	136.01	816.06
261	Stainless steel sink and drainer on timber cupboard 900 x 600 x 900mm high	No	6	139.01	834.06
262	Stainless steel sink and drainer on timber cupboard 1200 x 600 x 900mm high	No	6	139.01	834.06
263	Stainless steel sink and drainer on timber cupboard 1800 x 600 x 900mm high	No	6	152.01	912.06
264	Stainless steel wash trough 1200 x 600 x 900mm high	No	6	139.01	834.06
265	Precast concrete wash trough 1200 x 600 x 900mm high	No	6	139.01	834.06
266	Vitreous china high level urinal cistern	No	6	239.01	1,434.06
267	Vitreous china wash hand basin	No	6	239.01	1,434.06
268	Vitreous china WC pan and cistern	No	6	252.01	1,512.06
269	Vitreous china WC pan and high level cistern	No	6	265.02	1,590.12
270	Vitreous china WC pan with flush valve	No	6	252.01	1,512.06

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
271	Vitreous china wall hung urinal with flush valve	No	6	239.01	1,434.06
272	Vitreous china urinal 1200 x 1500mm high including breaking up and removing 400mm wide concrete urinal step	No	6	404.41	2,426.46
273	Vitreous china urinal 1200 x 1500mm high and high level cistern including breaking up and removing 400mm wide concrete urinal step	No	6	409.62	2,457.72
274	Stainless steel urinal 900 x 1500mm high including breaking up and removing 400mm wide concrete urinal step	No	6	370.47	2,222.82
275	Stainless steel high level urinal cistern	No	6	141.62	849.72
276	Stainless steel urinal 900 x 1500mm high and high level cistern including breaking up and removing 400mm wide concrete urinal step	No	6	436.93	2,621.56
277	Stainless steel urinal 1200 x 1500mm high including breaking up and removing 400mm wide concrete urinal step	No	6	566.17	3,397.04
278	Stainless steel urinal 1200 x 1500mm high and high level cistern including breaking up and removing 400mm wide concrete urinal step	No	6	566.17	3,397.04
279	Stainless steel urinal 1800 x 1500mm high including breaking up and removing 400mm wide concrete urinal step	No	6	566.17	3,397.04
280	Stainless steel urinal 1800 x 1500mm high and high level cistern including breaking up and removing 400mm wide concrete urinal step	No	6	813.75	4,882.50
281	Glass from steel windows including cleaning out rebates and preparing for new glass	m ²	200	20.40	4,080.00
282	Glass from timber windows with beads including cleaning out rebates and preparing for new glass	m ²	27	20.40	550.80
283	Mirror from wall	m ²	27	20.81	561.87
284	Mirror from wall, including making good tiling	m ²	27	201.55	5,441.85
285	Stainless steel sheet mirror	m ²	27	20.81	561.87
<u>CUTTING THROUGH FLOORS AND CEILINGS</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
286	Cutting through 100mm thick concrete surface bed for 460mm wide concrete wall footing including making good concrete on both sides of new half brick wall.	m	96	83.22	7,989.12
287	Cutting through 100mm thick concrete surface bed for 700mm wide concrete wall footing including making good concrete on both sides of new one brick wall.	m	96	146.94	14,106.24
288	Cutting through gypsum ceiling and brndering for half brick wall including making good on both sides of wall (new cornices elsewhere)	m	96	23.01	2,208.96
289	Cutting through gypsum ceiling and brndering for one brick wall including making good on both sides of wall (new cornices elsewhere)	m	96	39.50	3,792.00
290	Cutting through "Nutec" fibre-cement ceiling and brndering for half brick wall including making good on both sides of wall (new cornices elsewhere)	m	96	33.01	3,168.96
291	Cutting through "Nutec" fibre-cement ceiling and brndering for one brick wall including making good on both sides of wall (new cornices elsewhere)	m	96	39.50	3,792.00
<u>BUILDING UP OPENINGS</u>					
<u>Brickwork in NFP bricks in class II mortar in building up openings</u>					
292	Half brick walls	m ²	200	265.00	53,000.00
293	One brick walls	m ²	200	485.00	97,000.00
294	280mm Cavity wall of two half brick skins	m ²	200	579.96	115,992.00
295	One and half brick walls	m ²	200	859.53	171,906.00
<u>Sundries</u>					
296	Cutting toothing and bonding new brickwork to existing	m ²	200	28.61	5,722.00
<u>Face brick pointed with flush or recessed horizontal and vertical joints</u>					
297	Extra over brickwork for face brickwork in patches (PC R6,000.00 per thousand appupled and delivered to site)	m ²	200	265.40	53,080.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
298	230mm wide brick-on-edge header course lintel	m	75	125.75	9,431.25
299	230mm wide brick-on-edge header course sill set sloping and slightly projecting	m	75	125.75	9,431.25
300	Cutting toothing and bonding new face brickwork to existing	m	75	28.61	2,145.75
<u>PREPARATORY WORK TO EXISTING SURFACES</u>					
<u>Preparatory work to existing surfaces</u>					
301	Cutting out joints of existing brickwork to receive plaster.	m ²	200	28.61	5,722.00
302	Hacking face of existing concrete columns, beams, etc to receive plaster	m ²	200	39.50	7,900.00
303	Hacking face of existing face brickwork to receive plaster	m ²	200	48.61	9,722.00
304	Making good defects in existing screeded floors with "Pavelite"	m ²	285	61.62	17,561.70
305	Chasing existing brick / concrete walls	m	85	28.61	2,431.85
<u>MAKING GOOD OF FINISHES ETC.</u>					
<u>Making good of finishes etc.</u>					
306	Making good brickwork at ends of half brick wall	m	85	26.01	2,210.85
307	Making good brickwork at ends of one brick wall	m	85	39.01	3,315.85
308	Making good brickwork at ends of one and half brick wall	m	85	52.01	4,420.85
309	Making good brickwork to face of wall where half brick cross wall removed	m	85	39.01	3,315.85
310	Making good brickwork to face of wall where one brick cross wall removed	m	85	52.01	4,420.85
311	Making good brickwork to face of wall where one and half brick cross wall removed	m	85	91.03	7,737.55
312	Making good face brickwork at ends of half brick wall	m	85	36.40	3,094.00
313	Making good face brickwork at ends of one brick wall	m	85	54.62	4,642.70

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
314	Making good face brickwork at ends of one and half brick wall	m	85	91.03	7,737.55
315	Making good face brickwork to face of wall where half brick cross wall removed	m	85	36.40	3,094.00
316	Making good face brickwork to face of wall where one brick cross wall removed	m	85	71.52	6,079.20
317	Making good face brickwork to face of wall where one and half brick cross wall removed	m	85	107.93	9,174.05
	<u>Making good "Rhino" gypsum board ceiling and brandering.</u>				
318	Ceilings in patches	m ²	285	135.23	38,540.55
319	Ceilings where half brick walls removed	m ²	285	61.11	17,416.35
320	Ceilings where one brick walls removed	m ²	285	101.43	28,907.55
321	Ceilings where one and half brick walls removed	m ²	285	162.55	46,326.75
	<u>Making good "Nutec" fibre-cement board ceiling and brandering.</u>				
322	Ceilings in patches	m ²	285	140.43	40,022.55
323	Ceilings where half brick walls removed	m	86	62.41	5,367.26
324	Ceilings where one brick walls removed	m	86	72.21	6,210.06
325	Ceilings where one and half brick walls removed	m	86	170.35	14,650.10
	<u>Making good 300 x 300 x 2,0mm Vinyl floor tiles</u>				
326	Floors in patches	m ²	285	182.04	51,881.40
327	Floors where partitions removed	m	86	52.01	4,472.86
328	Floors where half brick walls removed	m	86	52.01	4,472.86
329	Floors where one brick walls removed	m	86	87.12	7,492.32
330	Floors where one and half brick walls removed	m	86	139.14	11,966.04
	<u>Making good 2,0mm "Superflex" fully flexible vinyl sheeting</u>				
331	Floors in patches	m ²	285	182.04	51,881.40

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
332	Floors where partitions removed	m	86	52.01	4,472.86
333	Floors where half brick walls removed	m	86	52.01	4,472.86
334	Floors where one brick walls removed	m	86	87.12	7,492.32
335	Floors where one and half brick walls removed	m	86	139.14	11,966.04
	<u>Making good 2,5mm "Superflex" fully flexible vinyl sheeting</u>				
336	Floors in patches	m ²	285	218.47	62,263.95
337	Floors where partitions removed	m	86	62.41	5,367.26
338	Floors where half brick walls removed	m	86	62.41	5,367.26
339	Floors where one brick walls removed	m	86	104.02	8,945.72
340	Floors where one and half brick walls removed	m	86	166.45	14,314.70
	<u>Making good 3,5mm "Industrial floor" flexible vinyl sheeting</u>				
341	Floors in patches	m ²	285	282.18	80,421.30
					0.00
342	Floors where partitions removed	m	86	80.62	6,933.32
343	Floors where half brick walls removed	m	86	80.62	6,933.32
344	Floors where one brick walls removed	m	86	133.94	11,518.84
345	Floors where one and half brick walls removed	m	86	214.57	18,453.02
	<u>Making good untinted granolithic</u>				
346	Floors in patches	m ²	285	140.18	39,951.87
347	Floors where partitions removed	m	86	52.78	4,539.08
348	Floors where half brick walls removed	m	86	52.78	4,539.08
349	Floors where one brick walls removed	m	86	58.51	5,031.86
350	Floors where one and half brick walls removed	m	86	96.23	8,275.78

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
351	Floor structural cracks not exceeding 300mm wide and 300mm deep with "Duraquartz" sealant including hacking, saw-cutting, structural anchoring and support.	m	495	1,020.14	504,969.30
	<u>Making good screed and 300 x 300 x 2,0mm Vinyl floor tiles</u>				
352	Floors in patches	m ²	285	205.45	58,553.25
353	Floors where partitions removed	m	86	53.32	4,585.52
354	Floors where half brick walls removed	m	86	53.32	4,585.52
355	Floors where one brick walls removed	m	86	88.41	7,603.26
356	Floors where one and half brick walls removed	m	86	141.74	12,189.64
	<u>Making good screed and 2,0mm "Superflex" fully flexible vinyl sheeting</u>				
357	Floors in patches	m ²	285	205.45	58,553.25
358	Floors where partitions removed	m	86	53.32	4,585.52
359	Floors where half brick walls removed	m	86	53.32	4,585.52
360	Floors where one brick walls removed	m	86	88.41	7,603.26
361	Floors where one and half brick walls removed	m	86	141.74	12,189.64
	<u>Making good screed and 2,5mm "Superflex" fully flexible vinyl sheeting</u>				
362	Floors in patches	m ²	285	241.86	68,930.10
363	Floors where partitions removed	m	86	81.92	7,045.12
364	Floors where half brick walls removed	m	86	81.92	7,045.12
365	Floors where one brick walls removed	m	86	111.82	9,616.52
366	Floors where one and half brick walls removed	m	86	193.76	16,663.36
	<u>Making good screed and 3,5mm "Industrial floor" flexible vinyl sheeting</u>				
367	Floors in patches	m ²	280	305.58	85,562.40
368	Floors where partitions removed	m	86	110.53	9,505.58

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
369	Floors where half brick walls removed	m	86	110.53	9,505.58
370	Floors where one brick walls removed	m	86	140.43	12,076.98
371	Floors where one and half brick walls removed	m	86	250.97	21,583.42
	<u>Making good internal cement plaster.</u>				
372	Walls in patches	m ²	285	88.41	25,196.85
373	Walls where half brick walls removed.	m	87	36.40	3,166.80
374	Walls where one brick walls removed.	m	87	55.93	4,865.91
375	Walls where one and half brick walls removed.	m	87	75.42	6,561.54
376	Concrete ceilings in patches	m ²	275	88.41	24,312.75
377	Concrete ceilings where half brick walls removed	m	95	36.40	3,458.00
378	Concrete ceilings where one brick walls removed	m	95	55.93	5,313.35
379	Concrete ceilings where one and half brick walls removed	m	95	75.42	7,164.90
380	Making good of chased walls	m	95	42.91	4,076.45
	<u>Making good internal cement plaster including chicken mesh spiked to (bases) walls.</u>				
381	Walls in patches	m ²	285	107.93	30,760.05
382	Walls where half brick walls removed.	m	96	39.01	3,744.96
383	Walls where one brick walls removed.	m	96	53.32	5,118.72
384	Walls where one and half brick walls removed.	m	96	92.33	8,863.68
385	Concrete ceilings in patches	m ²	285	107.93	30,760.05
386	Concrete ceilings where half brick walls removed	m	75	39.01	2,925.75
387	Concrete ceilings where one brick walls removed	m	75	53.32	3,999.00
388	Concrete ceilings where one and half brick walls removed	m	75	92.33	6,924.75
389	In scum channels not exceeding 300mm wide	m	75	62.41	4,680.75

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Making good internal two coat plaster with gypsum finish</u>				
390	Walls in patches	m ²	285	117.03	33,353.55
391	Walls where half brick walls removed.	m	76	39.01	2,964.76
392	Walls where one brick walls removed.	m	76	62.41	4,743.16
393	Walls where one and half brick walls removed.	m	76	101.43	7,708.68
394	Concrete ceilings in patches	m ²	285	117.03	33,353.55
395	Concrete ceilings where half brick walls removed	m	65	39.01	2,535.65
396	Concrete ceilings where one brick walls removed	m	65	62.41	4,056.65
397	Concrete ceilings where one and half brick walls removed	m	65	101.43	6,592.95
	<u>Making good external cement plaster.</u>				
398	Walls in patches	m ²	233	88.41	20,599.53
399	Walls where half brick walls removed.	m	65	36.40	2,366.00
400	Walls where one brick walls removed.	m	65	55.93	3,635.45
401	Walls where one and half brick walls removed.	m	65	92.33	6,001.45
	<u>Making good external cement plaster including chicken mesh spiked to (bases) walls.</u>				
402	Walls in patches	m ²	233	107.93	25,147.69
403	Walls where half brick walls removed.	m	65	39.01	2,535.65
404	Walls where one brick walls removed.	m	65	53.32	3,465.80
405	Walls where one and half brick walls removed.	m	65	92.33	6,001.45
	<u>Making good 200 x 200 x 4mm white glazed ceramic tiles</u>				
406	Walls in patches	m ²	233	210.65	49,081.45
407	Walls where half brick walls removed.	m	65	50.71	3,296.15
408	Walls where one brick walls removed.	m	65	83.22	5,409.30

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
409	Walls where one and half brick walls removed.	m	65	133.94	8,706.10
	<u>OPENINGS THROUGH EXISTING WALLS, ETC.</u>				
	<u>Altering openings</u>				
410	Altering opening in half brick wall where 813 x 2032mm high steel combination door and steel frame removed to form opening for new single door and frame 813 x 2337mm high overall by breaking out brickwork including necessary precast concrete lintel and making good plaster on both sides and into reveals with concrete threshold with steel trowelled finish (new door and frame and making good paintwork elsewhere)	No	1	1,003.09	1,003.09
411	Altering opening in half brick wall where 813 x 2032mm high timber door and steel frame removed to form opening for new single door and frame 813 x 2337mm high overall by breaking out brickwork including necessary precast concrete lintel and making good plaster on both sides and into reveals with concrete threshold with steel trowelled finish (new door and frame and making good paintwork elsewhere)	No	1	1,003.09	1,003.09
412	Altering opening in one brick wall where 813 x 2032mm high steel combination door and frame removed to form opening for new single door and frame 813 x 2337mm high overall by breaking out brickwork on both sides including necessary precast concrete lintel and making good plaster on both sides and into reveals with concrete threshold with steel trowelled finish (new door and frame and making good paintwork elsewhere)	No	1	1,369.00	1,369.00
413	Altering opening in one brick wall where 813 x 2032mm high timber door and steel frame removed to form opening for new single door and frame 813 x 2337mm high overall by breaking out brickwork on both sides including necessary precast concrete lintel and making good plaster on both sides and into reveals with concrete threshold with steel trowelled finish (new door and frame and making good paintwork elsewhere)	No	1	1,369.00	1,369.00
414	Altering opening in one brick wall where 813 x 2032mm high timber door and steel frame removed to form opening for new single door and frame 945 x 2065mm high overall by breaking out brickwork on both sides including necessary precast concrete lintel and making good plaster on both sides and into reveals with concrete threshold with steel trowelled finish (new door and frame and making good paintwork elsewhere)	No	1	1,048.09	1,048.09

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
415	Altering opening in one brick wall where 813 x 2032mm high timber door and steel frame removed to form opening for new single door and frame 965 x 2065mm high overall by breaking out brickwork on both sides including necessary precast concrete lintel and making good plaster on both sides and into reveals with concrete threshold with steel trowelled finish (new door and frame and making good paintwork elsewhere)	No	1	1,133.90	1,133.90
416	Altering opening in half brick wall where 813 x 2032mm high steel combination door and steel frame removed to form opening for new single door and frame 965 x 2065mm high overall by breaking out brickwork including necessary precast concrete lintel and making good plaster on both sides and into reveals with concrete threshold with steel trowelled finish (new door and frame and making good paintwork elsewhere)	No	1	1,133.90	1,133.90
417	Altering opening in half brick wall where 813 x 2032mm high timber door and steel frame removed to form opening for new single door and frame 965 x 2337mm high overall by breaking out brickwork including necessary precast concrete lintel and making good plaster on both sides and into reveals with concrete with quarry tile finish to threshold (new door and frame and making good paintwork elsewhere)	No	1	1,134.17	1,134.17
418	Altering opening in half brick wall where 813 x 2032mm high steel combination door and frame removed to form opening for new single door and frame 965 x 2337mm high overall by breaking out brickwork including necessary precast concrete lintel and making good plaster on both sides and into reveals with concrete with quarry tile finish to threshold (new door and frame and making good paintwork elsewhere)	No	1	1,134.17	1,134.17
419	Altering opening in one brick wall where 813 x 2032mm high timber door and steel frame removed to form opening for new single door and frame 1613 x 2337mm high overall by breaking out brickwork on both sides including necessary precast concrete lintel and making good plaster on both sides and into reveals with concrete with quarry tile finish to threshold (new door and frame and making good paintwork elsewhere)	No	1	1,573.42	1,573.42

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
420	Altering opening in one brick wall where window not exceeding 2,5m ² removed to form opening for new single leaf timber door and steel frame 965 x 2065mm high overall by breaking out brickwork on both sides and bottom including necessary precast concrete lintel and making good plaster on both sides (new door and frame and making good paintwork elsewhere)	No	1	1,048.09	1,048.09
421	Altering opening in one brick wall where window not exceeding 2,5m ² removed to form opening for new double leaf timber door and steel frame 1575 x 2065mm high overall by breaking out brickwork on both sides and bottom including necessary precast concrete lintel and making good plaster on both sides (new door and frame and making good paintwork elsewhere)	No	1	1,222.33	1,222.33
422	Altering opening in one brick wall where window not exceeding 2,5m ² removed to form opening for new single leaf timber door and steel frame 1575 x 2065mm high overall by breaking out brickwork on both sides and bottom including necessary precast concrete lintel and making good plaster on one side and into reveals and face brickwork on other side and into reveals (new door and frame and making good paintwork elsewhere)	No	1	1,466.80	1,466.80
	<u>Breaking out for and forming plain openings through brick walls including necessary precast concrete lintels and making good plaster on both sides and into reveals and with concrete thresholds with steel trowelled finish (making good paintwork elsewhere)</u>				
423	Opening 900 x 2100mm high through half brick wall	No	2	733.40	1,466.80
424	Opening 1200 x 2100mm high through half brick wall	No	2	806.23	1,612.46
425	Opening 1500 x 2100mm high through half brick wall	No	2	880.34	1,760.68
426	Opening 900 x 2100mm high through one brick wall	No	2	1,100.09	2,200.18
427	Opening 1200 x 2100mm high through one brick wall	No	2	1,174.22	2,348.44
428	Opening 1500 x 2100mm high through one brick wall	No	2	1,247.04	2,494.08
429	Opening 900 x 2100mm high through one and half brick wall	No	2	1,466.80	2,933.60
430	Opening 1200 x 2100mm high through one and half brick wall	No	2	1,542.20	3,084.40

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
431	Opening 1500 x 2100mm high through one and half brick wall <u>Breaking out for and forming plain openings through brick walls including necessary precast concrete lintels and making good plaster on side and face brick on the other and into reveals and with concrete thresholds with steel trowelled finish (making good paintwork elsewhere</u>	No	2	1,613.73	3,227.46
432	Opening 900 x 2100mm high through half brick wall	No	1	770.06	770.06
433	Opening 1200 x 2100mm high through half brick wall	No	1	846.53	846.53
434	Opening 1500 x 2100mm high through half brick wall	No	1	924.36	924.36
435	Opening 900 x 2100mm high through one brick wall	No	1	1,155.10	1,155.10
436	Opening 1200 x 2100mm high through one brick wall	No	1	1,232.93	1,232.93
437	Opening 1500 x 2100mm high through one brick wall	No	1	1,309.39	1,309.39
438	Opening 900 x 2100mm high through one and half brick wall	No	1	1,540.14	1,540.14
439	Opening 1200 x 2100mm high through one and half brick wall	No	1	1,619.33	1,619.33
440	Opening 1500 x 2100mm high through one and half brick wall <u>Breaking out for and forming plain openings through brick walls including necessary precast concrete lintels and making good plaster on side and face brick on the other and into reveals and with concrete thresholds with steel trowelled finish (making good paintwork elsewhere</u>	No	1	1,694.42	1,694.42
441	Opening 900 x 2100mm high through half brick wall	No	2	808.57	1,617.14
442	Opening 1200 x 2100mm high through half brick wall	No	2	888.85	1,777.70
443	Opening 1500 x 2100mm high through half brick wall	No	2	970.57	1,941.14
444	Opening 900 x 2100mm high through one brick wall	No	2	1,212.86	2,425.72
445	Opening 1200 x 2100mm high through one brick wall	No	2	1,294.58	2,589.16
446	Opening 1500 x 2100mm high through one brick wall	No	2	1,374.86	2,749.72
447	Opening 900 x 2100mm high through one and half brick wall	No	2	1,617.15	3,234.30
448	Opening 1200 x 2100mm high through one and half brick wall	No	2	1,700.30	3,400.60

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
449	Opening 1500 x 2100mm high through one and half brick wall <u>Breaking out for and forming plain openings through brick walls for new doors and frames including necessary precast concrete lintels and making good plaster on both side and into reveals and with concrete threshold with steel trowelled finish (new door and frame and making good paintwork elsewhere)</u>	No	2	1,779.15	3,558.30
450	Opening for door with steel frame 880 x 2065mm high overall through half brick wall	No	3	733.40	2,200.20
451	Opening for door with steel frame 964 x 2065mm high overall through half brick wall	No	3	733.40	2,200.20
452	Opening for door with steel frame 1575 x 2065mm high overall through half brick wall	No	3	880.34	2,641.02
453	Opening for door with steel frame 880 x 2065mm high overall through one brick wall	No	3	1,100.09	3,300.27
454	Opening for door with steel frame 964 x 2065mm high overall through one brick wall	No	3	1,100.09	3,300.27
455	Opening for door with steel frame 1575 x 2065mm high overall through one brick wall	No	3	1,247.04	3,741.12
456	Opening for door with steel frame 880 x 2065mm high overall through one and half brick wall	No	3	1,466.80	4,400.40
457	Opening for door with steel frame 964 x 2065mm high overall through one and half brick wall	No	3	1,466.80	4,400.40
458	Opening for door with steel frame 1575 x 2065mm high overall through one and half brick wall	No	3	1,613.73	4,841.19
459	Opening for door with timber frame 880 x 2065mm high overall through half brick wall	No	3	733.40	2,200.20
460	Opening for door with timber frame 964 x 2065mm high overall through half brick wall	No	3	733.40	2,200.20
461	Opening for door with timber frame 1575 x 2065mm high overall through half brick wall	No	3	880.34	2,641.02

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
462	Opening for door with timber frame 880 x 2065mm high overall through one brick wall	No	3	1,100.09	3,300.27
463	Opening for door with timber frame 964 x 2065mm high overall through one brick wall	No	3	1,100.09	3,300.27
464	Opening for door with timber frame 1575 x 2065mm high overall through one brick wall	No	3	1,247.04	3,741.12
465	Opening for door with timber frame 880 x 2065mm high overall through one and half brick wall	No	3	1,466.80	4,400.40
466	Opening for door with timber frame 964 x 2065mm high overall through one and half brick wall	No	3	1,466.80	4,400.40
467	Opening for door with timber frame 1575 x 2065mm high overall through one and half brick wall	No	3	1,613.73	4,841.19
	<u>Breaking out for and forming openings through brick walls for new windows including necessary precast concrete lintels and making good plaster on both sides and into reveals (new windows, sills and making good paintwork elsewhere)</u>				
468	Opening for window not exceeding 2,5m ² through half brick wall	No	2	886.85	1,773.70
469	Opening for window exceeding 2,5m ² and not exceeding 5.0m ² through half brick wall	No	2	1,037.69	2,075.38
470	Opening for window not exceeding 2,5m ² through one brick wall	No	2	1,222.33	2,444.66
471	Opening for window exceeding 2,5m ² and not exceeding 5.0m ² through one brick wall	No	2	1,466.80	2,933.60
472	Opening for window not exceeding 2,5m ² through one and half brick wall	No	2	1,557.83	3,115.66
473	Opening for window exceeding 2,5m ² and not exceeding 5.0m ² through one and half brick wall	No	2	1,895.91	3,791.82
	<u>Breaking out for and forming openings through brick walls for new windows including necessary precast concrete lintels and making good plaster on one side and into reveals and face brickwork on other side and into reveals (new windows, sills and making good paintwork elsewhere)</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule. <u>SUPPLEMENTARY PREAMBLES</u> <u>Nature of ground</u> No soil investigation is available. <u>Carting away of excavated material</u> Descriptions of carting away of excavated material shall be deemed to include for loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site. <u>Subterranean water</u> No information regarding subterranean water is available. The contractor must acquaint himself of the presence and depth of subterranean water and allow thereof in his rates. <u>Prices</u> Prices for all filling and carting away of surplus materials must make allowance for bulking. <u>Carting away of excavated material</u> Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site <u>DEMOLITIONS ETC</u> <u>Breaking up and removing</u>				
1	85mm thick concrete surface beds, paving, etc.	m ²	908	55.25	50,167.00
2	100mm thick concrete surface beds, paving, etc.	m ²	112	65.00	7,280.00
3	150mm thick concrete surface beds, paving, etc	m ²	112	97.50	10,920.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
4	85mm thick mesh reinforced concrete surface beds, paving, etc	m ²	112	55.25	6,188.00
5	100mm thick mesh reinforced concrete surface beds, paving, etc	m ²	112	69.00	7,728.00
6	150mm thick mesh reinforced concrete surface beds, paving, etc	m ²	112	103.50	11,592.00
7	60mm thick brick paving with mortar joints	m ²	112	36.41	4,078.37
8	80mm thick brick paving with mortar joints	m ²	112	38.25	4,283.78
9	300 x 300 x 30mm thick paving	m ²	112	38.25	4,283.78
10	230 x 75mm concrete kerb	m	112	21.84	2,446.08
11	300 x 150mm half-battered concrete kerb	m	112	30.94	3,465.28
12	280 x 180 x 140mm mountable concrete kerb	m	112	30.94	3,465.28
13	300 x 200 x 100mm mountable concrete kerb	m	112	30.94	3,465.28
14	230 x 110mm brick kerb with mortar joints	m	112	9.11	1,020.77
	<u>Take down and removing</u>				
15	Steel palisade, round bar, square tube, etc. gate size 813 x 2032mm high	No	60	136.54	8,192.40
16	Steel palisade, round bar, square tube, etc. gate size 1200 x 2032mm high	m	220	136.54	30,038.80
17	Steel sliding palisade, round bar, square tube, etc. gate size 6000 x 1800mm high	No	60	318.58	19,114.80
18	Steel two leaf palisade, round bar, square tube, etc. gate size 6000 x 1800mm high	No	60	318.58	19,114.80
19	Steel burglar gates, screens, etc. size 813 x 2032mm high	No	60	136.54	8,192.40
20	Steel burglar gates, screens, etc. size 1626 x 2032mm high	No	60	273.08	16,384.80
21	Steel two leaf palisade, round bar, square tube, etc. fence panel size 3000 x 1800mm high	No	60	162.55	9,753.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
22	Diamond mesh fence 2,1m high with flat wrap razor wire fixed to top and bottom and 75mm high overall with steel post and droppers	m	200	41.87	8,374.80
23	Diamond mesh fence 1,2m high formed of 50mm mesh chain link netting 2,5mm diameter galvanised mild steel wire stained and secured to top and bottom rails and posts	m	259	21.84	5,656.56
24	Half brick, precast, etc. boundary or yard wall 1,8m high	m	259	169.05	43,783.95
25	One brick boundary or yard wall 1,8m high	m	259	309.49	80,157.91
26	Steel Palisade fencing not exceeding 2400mm high	m	259	109.01	28,233.59
27	Concrete Palisade fencing not exceeding 2400mm high	m	259	108.51	28,104.09
28	Wooden picket fence 1500mm high	m	259	108.21	28,026.39
<u>SITE CLEARANCE, ETC.</u>					
<u>Site clearance</u>					
29	Dig up and remove rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush etc.	m ²	287	10.40	2,984.80
30	Dig up and remove contaminated rubbish, debris	m ³	287	107.21	30,769.27
31	Strip average 150mm thick layer top soil and stockpile on site where directed	m ²	287	27.32	7,840.84
32	Rip, scarify and compact ground 150mm average	m ²	287	27.32	7,840.84
33	Carting away rubble up to 5km radius (to dumping area, return distance not covered)	m ³	68	125.64	8,543.25
34	Overhaul exceeding 5km limited overhaul to dumping area, return distance not covered	m ³	68	125.64	8,543.25
<u>REMOVAL OF TREES, ETC.</u>					
<u>Taking out and removing, grubbing up roots and filling in holes</u>					
35	Tree stump exceeding 200mm. and not exceeding 500mm. girth	No	12	1,690.46	20,285.52
36	Tree stump exceeding 500mm. and not exceeding 1000mm. girth	No	12	2,470.67	29,648.04

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
37	Tree stump exceeding 1000mm. and not exceeding 2000mm. girth	No	12	3,575.97	42,911.64
38	Tree stump exceeding 2000mm. and not exceeding 3000mm. girth	No	12	4,681.27	56,175.24
	<u>Cutting down and removing, grubbing up roots and filling in holes including importing filling where required</u>				
39	Hedge not exceeding 1500mm high	m	12	27.32	327.84
40	Hedge exceeding 1500mm high and not exceeding 2500mm high	m	12	36.40	436.80
41	Tree exceeding 200mm and not exceeding 500mm girth	No	12	1,944.02	23,328.24
42	Tree exceeding 500mm and not exceeding 1000mm girth	No	12	2,841.26	34,095.12
43	Tree exceeding 1000mm and not exceeding 2000mm girth	No	12	5,383.45	64,601.40
44	Tree exceeding 2000mm and not exceeding 3000mm girth	No	12	14,124.09	169,489.08
	<u>Cutting of tree excluding tree stump and carting away off site</u>				
45	Tree exceeding 200mm and not exceeding 500mm girth	No	12	1,408.72	16,904.64
46	Tree exceeding 500mm and not exceeding 1000mm girth	No	12	2,058.88	24,706.56
47	Tree exceeding 1000mm and not exceeding 2000mm girth	No	12	2,979.97	35,759.64
48	Tree exceeding 2000mm and not exceeding 3000mm girth	No	12	3,901.05	46,812.60
	<u>BULK EXCAVATION, FILLING, ETC.</u>				
	<u>EXCAVATION, FILLING, ETC.</u>				
	<u>Open face excavations in earth over sloping site</u>				
49	Open face excavations	m ³	300	89.21	26,762.40
	<u>Excavation in earth not exceeding 2m deep</u>				
50	Reducing levels under floors	m ³	300	99.86	29,959.20
51	Trenches	m ³	300	99.86	29,959.20

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
52	Holes	m ³	300	99.86	29,959.20
53	Trenches and holes for thickening under surface beds etc.	m ³	300	99.86	29,959.20
	<u>Hand excavation to expose existing services where ordered by the Engineer / QS</u>				
54	In Soft material	m ³	300	256.04	76,812.00
55	In Intermediate material	m ³	300	382.04	114,612.00
56	In Hard material	m ³	300	450.13	135,039.00
	<u>Extra over Blasting of trench and hole excavations in earth for excavation in</u>				
57	Soft rock.	m ³	280	256.55	71,834.00
58	Hard rock.	m ³	280	1,095.15	306,642.00
59	Back excavation in earth for working space for excavation in soft rock	m ²	83	143.05	11,873.15
	<u>Extra over excavations in earth for breaking up and removing</u>				
60	Brickwork	m ³	102	353.70	36,077.40
61	Unreinforced concrete	m ³	102	353.70	36,077.40
62	Reinforced concrete	m ³	102	708.68	72,285.36
	<u>Extra over all excavations for carting away</u>				
63	Surplus material from excavations and /or stock pile on site to a dumping site to be located by the contractor (up to a radius of 5km-return distance not covered)	m ³	102	124.62	12,711.24
64	Overhaul exceeding 5km limited overhaul to dumping area, return distance not covered	m ³	102	156.26	15,938.52
	<u>Risk of collapse of excavations</u>				
65	Sides of trench and hole excavations not exceeding 1,5m deep including keeping excavations free from water	m ²	306	9.11	2,787.66
66	Sides of trench and hole excavations exceeding 1,5m deep including keeping excavations free from water	m ²	306	12.11	3,705.66

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
67	Sides of bulk excavations not exceeding 1,5m deep including keeping excavations free from water	m ²	306	12.11	3,705.66
68	Sides of bulk excavations exceeding 1,5m deep including keeping excavations free from water.	m ²	306	13.01	3,981.06
	<u>Keeping excavations free of water</u>				
69	Keeping excavations free of water other than subterranean water	Item	1	5,000.00	5,000.00
	<u>Earth filling obtained from excavations and/or prescribed stock piles on site (not compacted)</u>				
70	Over site	m ³	50	94.92	4,746.00
71	Landscape mounds, berms, etc	m ³	50	105.28	5,264.00
	<u>Earth filling obtained from excavations and/or prescribed stock piles on site compacted to 95% Mod AASHTO density</u>				
72	Under floors, steps, pavings, etc.	m ³	389	93.63	36,422.07
73	Backfill behind retaining walls	m ³	389	98.83	38,444.87
74	Backfill to trenches, holes, etc.	m ³	389	98.83	38,444.87
75	Over site to make up levels	m ³	389	98.83	38,444.87
76	Bedding	m ³	221	98.83	21,841.43
	<u>Earth filling supplied by the contractor compacted to 95% Mod AASHTO density</u>				
77	Under floors, steps, pavings, etc.	m ³	521	454.08	236,575.68
78	Backfill behind retaining walls	m ³	521	460.31	239,820.47
79	Backfill to trenches, holes, etc.	m ³	521	460.31	239,820.47
	<u>Garden top soil filling obtained from the excavations and/or prescribed stock piles on site</u>				
80	In flower boxes	m ³	195	88.94	17,344.08
81	Over site	m ³	195	99.86	19,473.48

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
82	Landscape mounds, berms, etc.	m ³	195	112.36	21,909.42
	<u>Garden top soil filling supplied by the contractor</u>				
83	In flower boxes	m ³	50	427.26	21,362.86
84	Over site	m ³	50	427.26	21,362.86
85	Landscape mounds, berms, etc	m ³		436.55	0.00
	<u>Coarse river sand filling supplied by the contractor</u>				
86	Under floors etc	m ³	70	451.21	31,584.70
87	Behind retaining walls	m ³	70	457.72	32,040.40
88	In floor ducts	m ³	70	457.72	32,040.40
	<u>Hardcore filling</u>				
89	Under floors etc	m ³	70	455.13	31,858.82
	<u>Crusher filling of 19mm stone</u>				
90	Under floors etc	m ³	70	474.12	33,188.62
91	Behind retaining walls	m ³	70	474.12	33,188.62
92	In flower boxes	m ³	70	472.13	33,049.15
	<u>Compaction of surfaces</u>				
93	Compaction of ground surface under floors, etc. including scarifying depth of 100mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m ²	462	45.60	21,067.20
	<u>TESTS</u>				
	<u>Prescribed density test on filling.</u>				
94	Modified AASHTO density test	No	60	375.80	22,548.00
95	Natural California Bearing Ratio test	No	60	517.55	31,053.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
96	Field Density test including "Optimum Moisture Content" (four readings per test)	No	1	676.18	676.18
97	Maximum dry density and optimum moisture content test in accordance with Method A7 of TMH1 (Technical Method of Highways)	No	100	676.18	67,618.00
98	In situ dry density (sand replacement) test in accordance with method A7 of TMH1 (Technical Method of Highways)	No	100	676.18	67,618.00
<u>STONE PITCHING</u>					
<u>Stone pitching of approximately 250mm diameter river stones tightly packed including preparation of ground surface under</u>					
99	250mm thick against sloping banks	m ²	489	118.50	57,946.50
100	250mm thick against sloping banks bedded and jointed in 1:8 cement mortar and pointed with hollow recessed joints	m ²	489	192.84	94,298.76
<u>GABIONS</u>					
<u>Gabions of Mesh Type 80 with 3mm Class A galvanised wire boxes laced and braced together and filled with broken stone as per Maccaferri SA (Pty) Ltd specifications</u>					
101	1000mm thick retaining wall of 1000 x 1000 x 1000mm boxes properly bonded	m ³	287	1,024.68	294,083.16
102	1000mm thick retaining wall of 2000 x 1000 x 1000mm boxes properly bonded	m ³	287	1,229.62	352,899.79
<u>Reno Mattresses of Mesh Type 60 with 2,7mm Class A galvanised wire boxes laced and braced together and filled with broken stone as per Maccaferri SA (Pty) Ltd specifications</u>					
103	300mm thick embankment protection of 2000 x 1000 x 300mm mattresses with diaphragm divisions at 1000mm centres butt jointed	m ³	287	1,241.83	356,405.21
104	300mm thick embankment protection of 3000 x 1000 x 300mm mattresses with diaphragm divisions at 1000mm centres butt jointed	m ³	287	1,618.94	464,635.78
<u>FILTER FABRIC</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>AG 300 Geotextile continuous polyester filament double needle-punched filter fabric with 300mm laps as per Maccaferri SA (Pty) Ltd specifications</u>				
105	Under stone filled gabions including preparing ground surface under	m ²	2,200	28.61	62,942.00
106	Vertically behind stone filled gabion retaining walls	m ²	2,200	28.61	62,942.00
107	Over stone percolation beds in flower boxes	m ²	2,200	29.91	65,802.00
108	Around stone filling in sub-soil drain trenches	m ²	2,200	29.91	65,802.00
	<u>SOIL POISONING</u>				
	<u>Weed killers, Insecticides, etc. Environmentally friendly and SABS approved</u>				
109	Under paving, etc	m ²	2,200	20.81	45,782.00
110	Under floors etc, including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming.	m ²	2,200	20.81	45,782.00
111	Bottoms and sides of trenches etc.	m ²	2,200	20.81	45,782.00
					5,595,109.52

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
					18,103,521.75
	SUB-TOTAL <i>(Carried To Summary)</i>				
	<u>BILL NO. 4</u>				
	<u>CONCRETE, FORMWORK AND REINFORCEMENT</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	<u>Cost of tests</u>				
	The costs of making, storing and testing of concrete test cubes as required under clause 7 "Tests" of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the Principal Agent/Project Manager. The testing shall be undertaken by an independent firm or institution nominated by the contractor to the approval of the Principal Agent/Project Manager. (Test cubes are measured separately)				
	<u>Formwork</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use. The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself. Formwork to soffits of solid slabs, etc., shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described. Formwork to sides of bases, pile caps, ground beams, etc. will only be measured where it is prescribed by the engineer for design reasons. Formwork necessitated by irregularity or collapse of excavated faces will not be measured and the cost thereof shall be deemed to be included in the allowance for taking the risk of collapse of the sides of the excavations, provision for which is made in "Earthworks"				
	<u>RAPID HARDENING CONCRETE</u>				
	<u>Backfill trenches in high trafficked road surfaces</u>				
1	25 Mpa concrete	m ³	45	2,389.07	107,508.06
2	30 Mpa concrete	m ³	45	2,389.07	107,508.06
	<u>CELLULAR LIGHT RAPID HARDENING CONCRETE</u>				
	<u>Cellular light Breeze concrete - Backfill trenches in high trafficked road surfaces</u>				
3	Grading to slabs	m ³	40	1,503.23	60,129.20
4	Finishing smooth top surfaces of grading to falls for waterproofing including 1:8 monolithic cement plaster screed as necessary	m ²	846	15.91	13,459.86
5	Finishing smooth top surfaces of grading to falls and currents for waterproofing including 1:8 monolithic cement plaster screed as necessary	m ²	846	15.91	13,459.86
6	70 x 70mm 1:8 Cement plaster triangular fillets against walls, etc.	m	846	16.44	13,908.24

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
<u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>					
<u>15MPa/20mm. concrete</u>					
7	Surface blinding under surface beds	m ³	86	1,676.90	144,213.40
8	Surface blinding under footings and bases	m ³	86	1,676.90	144,213.40
<u>20MPa/20mm concrete</u>					
9	Strip footings	m ³	86	1,958.91	168,466.26
10	Surface bed	m ³	86	1,958.91	168,466.26
11	Surface bed on waterproofing	m ³	86	1,958.91	168,466.26
12	Surface bed cast in panels	m ³	86	1,958.91	168,466.26
13	Surface bed cast in panels on waterproofing	m ³	86	1,958.91	168,466.26
14	Pavings	m ³	86	1,958.91	168,466.26
15	Pavings cast in panels	m ³	86	1,958.91	168,466.26
16	Ramps	m ³	86	1,958.91	168,466.26
17	Bottoms and sides of floor ducts	m ³	86	1,958.91	168,466.26
18	Machine bases	m ³	86	1,958.91	168,466.26
19	Steps, urinal steps, cupboard platforms, etc.	m ³	86	1,958.91	168,466.26
<u>25MPa/20mm concrete</u>					
20	Strip footings	m ³	86	1,958.91	168,466.26
21	Surface bed	m ³	86	1,958.91	168,466.26
22	Surface bed on waterproofing	m ³	86	1,958.91	168,466.26
23	Surface bed cast in panels	m ³	86	1,958.91	168,466.26
24	Surface bed cast in panels on waterproofing	m ³	86	1,958.91	168,466.26
25	Pavings	m ³	86	1,958.91	168,466.26

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
26	Pavings cast in panels	m ³	86	1,958.91	168,466.26
27	Ramps	m ³	86	1,958.91	168,466.26
28	Bottoms and sides of floor ducts	m ³	86	1,958.91	168,466.26
29	Machine bases	m ³	86	1,958.91	168,466.26
30	Steps	m ³	86	1,958.91	168,466.26
<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>					
<u>20MPa/20mm concrete</u>					
31	Strip footings.	m ³	21	2,044.08	42,925.68
32	Bases	m ³	14	2,044.08	28,617.12
33	Foundation beams	m ³	14	2,044.08	28,617.12
34	Surface beds.	m ³	14	2,044.08	28,617.12
35	Surface bed on waterproofing	m ³	14	2,044.08	28,617.12
36	Surface bed cast in panels	m ³	14	2,044.08	28,617.12
37	Surface bed cast in panels on waterproofing	m ³	14	2,044.08	28,617.12
38	Paving	m ³	14	2,044.08	28,617.12
39	Paving cast in panels	m ³	14	2,044.08	28,617.12
40	Ramps	m ³	14	2,044.08	28,617.12
41	Bottom and sides of floor ducts	m ³	14	2,044.08	28,617.12
42	Machine bases	m ³	14	2,044.08	28,617.12
43	Steps	m ³	14	2,044.08	28,617.12
44	In cavity walls	m ³	14	2,044.08	28,617.12
<u>25MPa/20mm concrete</u>					
45	Strip footings	m ³	14	2,044.08	28,617.12
46	Bases	m ³	14	2,044.08	28,617.12

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
47	Foundation beams	m ³	14	2,044.08	28,617.12
48	Surface beds.	m ³	14	2,044.08	28,617.12
49	Surface bed on waterproofing	m ³	14	2,044.08	28,617.12
50	Surface bed cast in panels	m ³	14	2,044.08	28,617.12
51	Surface bed cast in panels on waterproofing	m ³	14	2,044.08	28,617.12
52	Paving	m ³	14	2,044.08	28,617.12
53	Paving cast in panels	m ³	14	2,044.08	28,617.12
54	Ramps	m ³	14	2,044.08	28,617.12
55	Bottom and sides of floor ducts	m ³	14	2,044.08	28,617.12
56	Machine bases	m ³	14	2,044.08	28,617.12
57	Steps	m ³	14	2,044.08	28,617.12
<u>REINFORCED CONCRETE</u>					
<u>30MPa/20mm concrete</u>					
58	Slabs including beams and inverted beams	m ³	14	2,044.08	28,617.12
59	Stepped slabs including beams and inverted beams	m ³	14	2,044.08	28,617.12
60	Raking slabs, ramps, etc. including beams and inverted beams	m ³	14	2,044.08	28,617.12
61	Coffered slabs including beams and inverted beams	m ³	14	2,044.08	28,617.12
62	Troughed slabs including beams and inverted beams	m ³	14	2,044.08	28,617.12
63	Composite hollow block slabs including beams and inverted beams	m ³	14	2,044.08	28,617.12
64	Composite prefabricated beam and trough slabs including beams and inverted beams	m ³	14	2,044.08	28,617.12
65	Hood slabs	m ³	14	2,044.08	28,617.12
66	Vanity slabs, cupboard slabs, cover slabs, etc	m ³	14	2,044.08	28,617.12

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
67	Isolated beams	m3	14	2,044.08	28,617.12
68	Bottoms and sides of isolated gutter beams	m3	14	2,044.08	28,617.12
69	Lintels	m3	14	2,044.08	28,617.12
70	Stairs including landings, beams and inverted beams	m3	14	2,044.08	28,617.12
71	Retaining walls in foundations (Provisional)	m3	14	2,044.08	28,617.12
72	Retaining walls	m3	14	2,044.08	28,617.12
73	Walls in foundations (Provisional)	m3	14	2,044.08	28,617.12
74	Walls	m3	14	2,044.08	28,617.12
75	Balustrade walls	m3	14	2,044.08	28,617.12
76	Columns in foundations (Provisional)	m3	14	2,044.08	28,617.12
77	Columns	m3	14	2,044.08	28,617.12
<u>TEST BLOCKS</u>					
<u>Prescribed test blocks:</u>					
78	Making and testing set of three 150 x 150 x 150mm concrete strength test cubes (Provisional)	Sets	86	527.58	45,371.88
<u>CONCRETE SUNDRIES</u>					
<u>Curing surfaces of concrete with "Masterseal" curing compound applied at arate of 1 litre/10m2</u>					
79	Horizontal top surfaces	m2	245	45.00	11,025.00
					0.00
80	Vertical surfaces	m2	245	45.00	11,025.00
<u>Colouring surfaces of concrete with "Oxide" including curing compound applied at a rate of 1 litre/10m2</u>					
81	Horizontal top surfaces	m2	245	54.74	13,411.30
82	Vertical surfaces	m2	254	54.74	13,903.96
<u>Finishing top surfaces of concrete smooth with a wood float or steel trowel</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
83	Surface beds, slabs, etc	m2	489	37.13	18,155.59
84	Surface bed, slabs, etc to falls and currents	m2	489	37.13	18,155.59
85	Paving to falls	m2	489	37.13	18,155.59
86	Paving to falls and currents	m2	489	37.13	18,155.59
87	Tops of beams, walls, etc	m2	489	43.75	21,393.75
88	Sloping and splayed tops of beams, walls, etc	m2	489	43.75	21,393.75
	<u>Finishing top surfaces of concrete smooth with a steel trowel</u>				
89	Surface beds, slabs, etc	m2	490	37.13	18,192.72
90	Surface bed, slabs, etc to falls and currents	m2	490	37.13	18,192.72
91	Paving to falls	m2	490	37.13	18,192.72
92	Paving to falls and currents	m2	490	37.13	18,192.72
93	Tops of beams, walls, etc	m2	490	43.75	21,437.50
94	Sloping and splayed tops of beams, walls, etc	m2	490	43.75	21,437.50
	<u>Finishing top surfaces of concrete smooth with a power float</u>				
95	Surface beds, slabs, etc	m2	509	43.75	22,268.75
96	Surface bed, slabs, etc to falls and currents	m2	509	43.75	22,268.75
97	Paving to falls	m2	509	43.75	22,268.75
	<u>Finishing top surfaces of concrete to an evenly ribbed non-slip surface</u>				
98	Surface beds, slabs, etc	m2	657	14.84	9,749.88
99	Surface bed, slabs, etc to falls	m2	657	14.84	9,749.88
100	Surface bed, slabs, etc to falls and currents	m2	657	14.84	9,749.88
101	Paving to falls	m2	657	14.84	9,749.88
102	Paving to falls and currents	m2	657	14.84	9,749.88

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Finishing top surfaces of concrete smooth with a power float with "Masterplate" hardener added (5kg/m²) and curing with "Masterseal" curing compound at a rate of 1 litre/10m²</u>				
103	Surface beds, slabs, etc	m2	652	44.53	29,036.17
	<u>Wire brushing of concrete surfaces to expose aggregate</u>				
104	Sides of walls	m2	652	37.13	24,207.46
105	Sides of columns	m2	652	37.13	24,207.46
106	Soffits of slab	m2	652	37.13	24,207.46
107	Sides and soffits of beams	m2	652	37.13	24,207.46
	<u>Sandblasting of concrete surfaces to expose aggregate</u>				
108	Sides of walls	m2	386	77.95	30,089.47
109	Sides of columns	m2	386	77.95	30,089.47
110	Soffits of slab	m2	386	77.95	30,089.47
111	Sides and soffits of beams	m2	386	77.95	30,089.47
	<u>Bush-hammering of concrete surfaces to expose aggregate</u>				
112	Sides of walls	m2	386	77.95	30,089.47
113	Sides of columns	m2	386	77.95	30,089.47
114	Soffits of slab	m2	386	77.95	30,089.47
115	Sides and soffits of beams	m2	386	77.95	30,089.47
	<u>Grooves, channels, mortices, sinkings, etc in concrete</u>				
116	20 x 20mm Grooves in top	m	95	33.39	3,172.05
117	35 x 35mm Channels in top	m	95	33.39	3,172.05
118	20mm x 20mm segmental channels in top	m	95	33.39	3,172.05
119	Mortice in top, side, etc not exceeding 150mm deep	m	95	33.39	3,172.05

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
120	20 x 20mm Sinking in top <u>Cement work of 1:3 liquid cement and sand mixture applied with a brush</u>	m	95	33.39	3,172.05
121	On concrete walls	m2	278	64.97	18,062.77
122	On soffits of slabs, landings, stairs, etc	m2	278	64.97	18,062.77
123	On soffits of coffered slabs <u>Bedding under base plates etc.</u>	m2	278	64.97	18,062.77
124	25mm thick non-shrink grout under steel base plate size 500 x 350mm including chamfered edge all round <u>HOLLOW BLOCKS ETC</u> <u>SuperSlab hollow blocks in composite slabs</u>	No	89	115.07	10,240.87
125	440 x 220 x 120mm block type S120 laid end to end in rows	No	60	51.95	3,117.24
			60		0.00
126	440 x 220 x 205mm block type S205 laid end to end in rows	No	60	51.95	3,117.24
127	440 x 220 x 290mm block type S290 laid end to end in rows <u>PREFABRICATED CONCRETE BEAMS</u> <u>SuperSlab prefabricated prestressed concrete beams in composite slabs</u>	No	60	51.95	3,117.24
128	150 x 58mm beam with Three 4mm reinforcing wires, in lengths not exceeding 5,0m	m	239	207.86	49,678.06
129	150 x 58mm beam with Five 4mm reinforcing wires, in lengths exceeding 5,0m and not exceeding 7,5m	m	239	215.28	51,451.44
130	150 x 58mm beam with Seven 4mm reinforcing wires, in lengths exceeding 7,5m and not exceeding 10,0m <u>Supporting bearers to prefabricated beams</u>	m	239	222.68	53,221.48
131	Bearers	m	239	436.13	104,235.07
132	Bearers propped up exceeding 3,5m and not exceeding 5,0m high	m	239	616.41	147,321.99

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Rough formwork to composite hollow block slabs</u>				
133	Soffit of composite slabs	m2	239	353.16	84,405.24
134	Soffit of composite slabs propped up exceeding 3,5m and not exceeding 5,0m high	m2	239	371.17	88,709.63
	<u>Echo Floors prefabricated prestressed concrete slabs</u>				
135	Slabs	m2	89	1,020.71	90,843.37
136	Bearers propped up exceeding 3,5m and not exceeding 5,0m high	m	239	762.22	182,170.58
	<u>ROUGH FORMWORK (DEGREE OF ACCURACY II)</u>				
	<u>Rough formwork to sides</u>				
137	Strip footings (Provisional)	m2	128	395.02	50,562.56
138	Bases (Provisional)	m2	128	395.02	50,562.56
139	Foundation beams (Provisional)	m2	128	395.02	50,562.56
140	Foundation beams circular exceeding 1m radius (Provisional)	m2	128	402.98	51,581.44
141	Retaining walls (Provisional)	m2	128	367.19	47,000.32
142	Retaining walls circular exceeding 1m radius (Provisional)	m2	128	373.82	47,848.96
143	Walls (Provisional)	m2	128	372.49	47,678.72
144	Walls circular exceeding 1m radius (Provisional)	m2	128	380.46	48,698.88
145	Stub columns in foundations (Provisional)	m2	128	270.42	34,613.76
	<u>SMOOTH FORMWORK (DEGREE OF ACCURACY II)</u>				
	<u>Smooth formwork to sides</u>				
146	Steps	m2	45	379.13	17,060.85
147	Retaining walls	m2	45	379.13	17,060.85
148	Retaining walls circular exceeding 1m radius	m2	45	387.08	17,418.60

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
149	One face of retaining walls (other face against excavated or existing surfaces)	m2	45	349.96	15,748.20
150	One face of retaining walls (other face against excavated or existing surfaces) circular exceeding 1m radius	m2	45	356.58	16,046.10
151	Walls	m2	45	379.13	17,060.85
152	Walls circular exceeding 1m radius	m2	45	387.08	17,418.60
153	Inner face of balustrade walls	m2	45	349.96	15,748.20
154	Inner face of balustrade walls circular exceeding 1m radius	m2	45	356.58	16,046.10
155	Outer face of balustrade walls	m2	45	349.96	15,748.20
156	Outer face of balustrade walls circular exceeding 1m radius	m2	45	356.58	16,046.10
157	Columns	m2	45	349.96	15,748.20
158	Beams	m2	45	367.19	16,523.55
159	Beams circular exceeding 1m radius	m2	45	375.14	16,881.30
160	Inverted beams	m2	45	367.19	16,523.55
161	Inverted beams circular exceeding 1m radius	m2	45	375.14	16,881.30
162	Isolated beams	m2	45	367.19	16,523.55
163	Isolated beams circular exceeding 1m radius	m2	45	375.14	16,881.30
164	Edges, risers, ends and reveals not exceeding 300mm. high or wide	m2	45	120.63	5,428.35
165	Edges, risers, ends and reveals not exceeding 300mm. high or wide circular exceeding 1m radius	m2	45	128.59	5,786.55
	<u>Smooth formwork to soffits</u>				
166	Slabs	m2	45	319.46	14,375.70
167	Slabs propped up exceeding 3,5m and not exceeding 5,0m high	m2	45	396.37	17,836.65
168	Slabs exceeding 250mm and not exceeding 500mm thick	m2	45	319.46	14,375.70

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
169	Slabs exceeding 250mm and not exceeding 500mm thick propped up exceed 3,5m and not exceeding 5,0m high	m2	45	396.37	17,836.65
170	Slabs with sloping soffits	m2	45	323.44	14,554.80
171	Cantilever slabs	m2	45	319.46	14,375.70
172	Cantilever slabs propped up exceed 3,5m and not exceeding 5,0m high	m2	45	396.37	17,836.65
173	Vanity slabs, cupboard slabs, cover slabs, etc	m2	45	340.67	15,330.15
174	Landings	m2	45	340.67	15,330.15
175	Landings exceeding 250mm and not exceeding 500mm thick	m2	45	340.67	15,330.15
176	Stairs and sloping soffits	m2	45	522.28	23,502.60
177	Beams	m2	45	357.91	16,105.95
178	Beams circular exceeding 1m radius	m2	45	364.54	16,404.30
179	Beams propped up exceeding 3,5m and not exceeding 5,0m high	m2	45	434.79	19,565.55
180	Beams with sloping soffits	m2	45	364.54	16,404.30
181	Beams with sloping soffits propped up exceeding 3,5m and not exceeding 5,0m high	m2	45	442.74	19,923.30
182	Isolated beams	m2	45	357.91	16,105.95
183	Isolated beams circular exceeding 1m radius	m2	45	364.54	16,404.30
184	Isolated beams propped up exceeding 3,5m and not exceeding 5,0m high	m2	45	434.79	19,565.55
	<u>Smooth formwork to circular columns</u>				
185	250mm diameter column not exceeding 3,5m high	No	45	782.10	35,194.50
186	250mm diameter column exceeding 3,5m high not exceeding 5,0m high	No	28	1,117.48	31,289.44
187	350mm diameter column not exceeding 3,5m high	No	28	913.34	25,573.52

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
188	350mm diameter column exceeding 3,5m high not exceeding 5,0m high	No	28	1,475.40	41,311.20
189	450mm diameter column not exceeding 3,5m high	No	28	1,045.90	29,285.20
190	450mm diameter column exceeding 3,5m high not exceeding 5,0m high	No	28	2,128.91	59,609.48
	<u>GROOVES, ETC</u>				
	<u>Boxing in smooth formwork to form</u>				
191	25 x 25mm chamfer along top or bottom edge	m	298	25.97	7,739.06
192	25 x 25mm chamfer along top or bottom edge circular not exceeding 1m radius	m	298	33.39	9,950.22
193	25 x 25mm vertical chamfer at corner	m	298	25.97	7,739.06
194	40 x 25mm horizontal chase or groove in side	m	298	44.53	13,271.13
195	40 x 25mm horizontal chase or groove in side circular not exceeding 1m radius	m	298	51.95	15,482.29
196	40 x 25mm raking or vertical chase or groove in side	m	298	44.53	13,271.13
	<u>Smooth formwork to form</u>				
197	Opening not exceeding 1m girth through not exceeding 300mm slab	No	243	226.67	55,080.81
198	100mm diameter opening through not exceeding 300mm slab	No	243	31.56	7,668.11
199	150mm diameter opening through not exceeding 300mm slab	No	243	35.28	8,573.04
200	100mm diameter opening through 340mm slab	No	243	35.28	8,573.04
201	150mm diameter opening through 340mm slab	No	243	40.84	9,923.63
202	Opening not exceeding 1m girth through not exceeding 300mm wall or beam	No	243	247.89	60,237.27
203	Opening not exceeding 1m girth through 350mm wall or beam	No	243	291.63	70,866.09
	<u>MOVEMENT JOINTS, ETC</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Expansion joints with bitumen impregnated softboard between vertical concrete surfaces</u>				
204	10mm joint exceeding 300mm high	m2	243	96.78	23,517.54
205	10mm joint not exceeding 300mm high	m	243	29.17	7,088.31
	<u>Expansion joints with bitumen impregnated softboard between vertical concrete and brick surfaces</u>				
206	10mm joint exceeding 300mm high	m2	243	96.78	23,517.54
207	10mm joint not exceeding 300mm high	m	243	29.17	7,088.31
	<u>Saw cut joints</u>				
208	5 x 35mm saw cut jointson top of concrete	m	243	53.02	12,883.86
	<u>Vertical toggle construction joint through concrete including thick cement slurry to one face</u>				
209	Surface bed not exceeding 300mm thick	m	243	89.38	21,719.34
210	Slabs not exceeding 300mm thick	m	243	89.38	21,719.34
211	Slabs 350mm thick	m	243	112.13	27,247.59
212	Walls not exceeding 300mm thick	m	243	89.38	21,719.34
213	Walls 350mm thick	m	243	112.13	27,247.59
	<u>REINFORCEMENT</u>				
	<u>Mild steel reinforcement to structural concrete work</u>				
214	8mm Diameter bars	t	2	13,500.00	27,000.00
215	10mm Diameter bars	t	2	13,500.00	27,000.00
216	12mm Diameter bar	t	2	13,500.00	27,000.00
217	16mm Diameter bars	t	2	13,500.00	27,000.00
	<u>High tensile steel reinforcement to structural concrete work</u>				
218	10mm Diameter bars	t	2	13,500.00	27,000.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
219	12mm Diameter bars	t	2	13,500.00	27,000.00
220	16mm Diameter bars	t	2	13,500.00	27,000.00
221	20mm Diameter bars	t	2	13,500.00	27,000.00
222	25mm Diameter bars	t	2	13,500.00	27,000.00
223	32mm Diameter bars	t	2	13,500.00	27,000.00
	<u>High tensile steel dowel bars</u>				
224	16mm diameter dowel bar 700mm long with one end embedded 350mm deep in side of concrete at expansion joint and other end greased and wrapped in polythene sheeting including hole through formwork	No	257	38.45	9,881.65 0.00
	<u>Fabric reinforcement</u>				
225	Type Ref. 100 in concrete surface beds, slabs, etc	m2	115	63.63	7,317.45
226	Type Ref. 193 in concrete surface beds, slabs, etc	m2	115	70.26	8,079.90
227	Type Ref. 245 in concrete surface beds, slabs, etc	m2	115	78.22	8,995.30
228	Type Ref. 311 in concrete surface beds, slabs, etc	m2	115	84.83	9,755.45
229	Type Ref. 395 in concrete surface beds, slabs, etc	m2	115	91.47	10,519.05
	<u>CONCRETE FLOOR POLISHING</u>				
	<u>Grinding and polishing of existing concrete floor</u>				
230	Areas not exceeding 500m2	m2	21	689.32	14,475.72
231	Areas exceeding 500m2 and not exceeding 1000m2	m2	21	499.76	10,494.96
232	Areas exceeding 1000m2 and not exceeding 2000m2	m2	21	482.52	10,132.92
233	Areas exceeding 2000m2 and not exceeding 5000m2	m2	21	465.29	9,771.09
234	Areas exceeding 5000m2 and not exceeding 10000m2	m2	21	448.05	9,409.05
235	Areas exceeding 10000m2 and not exceeding 20000m2	m2	21	430.83	9,047.43
	<u>Grinding and polishing of existing concrete floor in confined areas</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
236	Areas not exceeding 500m2	m2	35	742.34	25,981.90
237	Areas exceeding 500m2 and not exceeding 1000m2	m2	35	552.78	19,347.30
238	Areas exceeding 1000m2 and not exceeding 2000m2	m2	35	535.54	18,743.90
239	Areas exceeding 2000m2 and not exceeding 5000m2	m2	35	518.31	18,140.85
240	Areas exceeding 5000m2 and not exceeding 10000m2	m2	35	501.07	17,537.45
241	Areas exceeding 1000m2 and not exceeding 20000m2	m2	35	483.86	16,935.10
	<u>POLISH, SEALERS, ETC</u>				
	<u>Stain resistance sealing</u>				
242	Single coat seal to flooring	m2	265	83.54	22,137.57
	<u>Deep Clean Restoration</u>				
243	To linoleum, vinyl, etc	m2	200	55.00	11,000.00
244	To power floated concrete floors	m2	200	35.00	7,000.00
245	To granite	m2	200	35.00	7,000.00
246	To marble	m2	200	35.00	7,000.00
247	To terrazzo	m2	200	55.00	11,000.00
	<u>Cementations overlay</u>				
248	Supply and placement	m2	35	1,541.69	53,959.15
	<u>Sundries</u>				
249	Raising of doors	m2	40	292.95	11,718.00
					9,818,201.66

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	SUB-TOTAL <i>(Carried To Summary)</i>				27,921,723.41
	BILL NO. 5				
	MASONRY				
	PREAMBLES				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	SUPPLEMENTARY PREAMBLES				
	BRICKWORK				
	Sizes in descriptions				
	Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick.				
	Hollow walls, etc				
	Description of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole				
	Bagged and sealed walls				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats bitumen emulsion waterproofing coating <u>Face bricks</u> Bricks shall be ordered timeously to obtain uniformity in size and colour <u>Pointing</u> Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc. <u>BLOCKWORK</u> <u>Concrete masonry units</u> Blocks are to be either solid or hollow modular dense concrete masonry units having a compressive strength of 14MPa <u>Wall ties for blockwork</u> Wall ties shall be polypropylene ties complying with BS76377. Ties for hollow walls shall be of sufficient length to allow not less than 75mm of each end to be built into the blockwork. Ties are to be spaced at intervals of not more than 1m in the horizontal direction and not more than 400mm staggered in the vertical direction except at openings, vertical joints or ends of walls where they are to be placed vertically above each other <u>Blockwork</u> Blockwork shall comply with SANS 10145 "Concrete Masonry Construction" Surfaces to be plastered shall have joints raked out to a depth of at least 10mm to provide a key. Cavities of hollow walls shall be kept free of mortar droppings or other undesirable matter. Every second perpend of the bottom course of the external skin of hollow walls shall be left open as a weep hole				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	Standard complementary blocks Descriptions of blockwork shall be deemed to include standard complementary blocks such as corner, three-quarter, half and quarter blocks required in the construction of corners, reveals, jambs, ends, etc to solid and hollow walls and for bonding as necessary				
	<u>DECORATIVE BLOCKS</u>				
	Blocks shall be of approved manufacture, sound, well burnt or cured and uniform and true in size, shape and colour				
	<u>BRICKWORK</u>				
	<u>FOUNDATIONS (PROVISIONAL)</u>				
	<u>Brickwork of NFX bricks (14MPa nominal compressive strength) in class I mortar</u>				
1	Piers	m2	7	2,656.61	18,596.27
2	L-shaped piers	m2	7	2,698.24	18,887.68
3	H-shaped piers	m2	7	2,739.85	19,178.95
4	One brick walls	m2	7	525.35	3,677.45
5	One brick walls circular on plan	m2	7	550.04	3,850.28
6	One and a half brick walls	m2	7	775.01	5,425.07
7	One and a half brick wall circular on plan	m2	7	803.61	5,625.27
8	One brick cavity walls	m2	7	550.04	3,850.28
9	Two brick walls	m2	7	1,006.47	7,045.29
10	Two brick walls circular on plan	m2	7	1,033.78	7,236.46
	<u>Brickwork of concrete bricks (14MPa nominal compressive strength) in class I mortar</u>				
11	Piers	m2	7	2,656.61	18,596.27
12	L-shaped piers	m2	7	2,698.24	18,887.68
13	H-shaped piers	m2	7	2,739.85	19,178.95

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
14	One brick walls	m2	7	525.35	3,677.45
15	One brick walls circular on plan	m2	7	550.04	3,850.28
16	One and a half brick walls	m2	7	775.01	5,425.07
17	One and a half brick wall circular on plan	m2	7	803.61	5,625.27
18	Two brick walls	m2	7	1,006.47	7,045.29
19	Two brick walls circular on plan	m2	7	1,033.78	7,236.46
<u>BRICKWORK IN SUPERSTRUCTURE</u>					
<u>Brickwork of NFX bricks (14MPa nominal compressive strength) in class</u>					
<u>II mortar</u>					
20	Piers	m2	7	2,656.61	18,596.27
21	L-shaped piers	m2	7	2,698.24	18,887.68
22	H-shaped piers	m2	7	2,739.85	19,178.95
23	50mm cut lining to concrete	m2	7	195.06	1,365.42
24	50mm cut lining to concrete circular on plan	m2	7	200.26	1,401.82
25	Brick-on-edge walls	m2	7	195.06	1,365.42
26	Half brick walls	m2	7	263.98	1,847.86
27	Half brick walls circular on plan	m2	7	276.97	1,938.79
28	Half brick walls against existing surfaces	m2	7	263.98	1,847.86
29	Half brick walls in beamfilling	m2	7	276.97	1,938.79
30	Half brick walls in beamfilling circular on plan	m2	7	284.78	1,993.46
31	Half brick lining to concrete columns	m2	7	263.98	1,847.86
32	Half brick lining to concrete columns circular on plan	m2	7	276.97	1,938.79
33	One brick walls	m2	7	525.35	3,677.45
34	One brick walls circular on plan	m2	7	550.04	3,850.28

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
35	One brick walls against existing surfaces	m2	7	525.35	3,677.45
36	One brick walls in beamfilling	m2	7	550.04	3,850.28
37	One brick walls in beamfilling circular on plan	m2	7	566.94	3,968.58
38	280mm hollow walls of two half brick skins including wire ties	m2	7	559.15	3,914.05
39	280mm hollow walls of two half brick skins including wire ties circular on plan	m2	7	574.75	4,023.25
40	One and a half brick wall	m2	7	775.01	5,425.07
41	One and a half brick wall circular on plan	m2	7	803.61	5,625.27
42	390mm hollow walls of one half brick and one one brick skins including wire ties	m2	7	811.42	5,679.94
43	390mm hollow walls of one half brick and one one brick skins including wire ties on circular plan	m2	7	832.23	5,825.61
44	Two brick walls	m2	7	1,006.47	7,045.29
45	Two brick walls circular on plan	m2	7	1,033.78	7,236.46
46	Half brick kerb 170mm high	m	7	45.51	318.57
47	Half brick kerb 170mm high circular on plan	m	7	48.11	336.77
48	One brick kerb 170mm high	m	7	89.72	628.04
49	One brick kerb 170mm high circular on plan	m	7	96.23	673.61
	<u>Brickwork of concrete bricks (14MPa nominal compressive strength in class II mortar</u>				
50	Piers	m2	7	2,656.61	18,596.27
51	L-shaped piers	m2	7	2,698.24	18,887.68
52	H-shaped piers	m2	7	2,739.85	19,178.95
53	50mm cut lining to concrete	m2	7	195.06	1,365.42
54	50mm cut lining to concrete circular on plan	m2	7	200.26	1,401.82
55	Brick-on-edge walls	m2	7	195.06	1,365.42

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
56	Half brick walls	m2	7	263.98	1,847.86
57	Half brick walls circular on plan	m2	7	276.97	1,938.79
58	Half brick walls against existing surfaces	m2	7	263.98	1,847.86
59	Half brick walls in beamfilling	m2	7	276.97	1,938.79
60	Half brick walls in beamfilling circular on plan	m2	7	284.78	1,993.46
61	Half brick lining to concrete columns	m2	7	263.98	1,847.86
62	Half brick lining to concrete columns circular on plan	m2	7	276.97	1,938.79
63	One brick walls	m2	7	525.35	3,677.45
64	One brick walls circular on plan	m2	7	550.04	3,850.28
65	One brick walls against existing surfaces	m2	7	525.35	3,677.45
66	One brick walls in beamfilling	m2	7	550.04	3,850.28
67	One brick walls in beamfilling circular on plan	m2	7	566.94	3,968.58
68	280mm hollow walls of two half brick skins including wire ties	m2	7	559.15	3,914.05
69	280mm hollow walls of two half brick skins including wire ties circular on plan	m2	7	574.75	4,023.25
70	One and a half brick wall	m2	7	775.01	5,425.07
71	One and a half brick wall circular on plan	m2	7	803.61	5,625.27
72	390mm hollow walls of one half brick and one one brick skins including wire ties	m2	7	811.42	5,679.94
73	390mm hollow walls of one half brick and one one brick skins including wire ties on circular plan	m2	7	832.23	5,825.61
74	Two brick walls	m2	7	1,006.47	7,045.29
75	Two brick walls circular on plan	m2	7	1,033.78	7,236.46
76	Half brick kerb 170mm high	m	7	45.51	318.57
77	Half brick kerb 170mm high circular on plan	m	7	48.11	336.77

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
78	One brick kerb 170mm high	m	7	89.72	628.04
79	One brick kerb 170mm high circular on plan	m	7	96.23	673.61
	<u>BRICKWORK SUNDRIES</u>				
	<u>Brickwork sundries</u>				
80	Cutting toothings and bonding new brickwork to existing	m2	7	28.61	200.27
81	Extra for building brickwork to battered face with each course set back 55mm	m2	7	41.62	291.34
82	Extra for building brickwork to battered face with sloping joints	m2	7	41.62	291.34
83	Extra for building brickwork to oversail face with each course projecting 55mm	m2	7	44.21	309.47
84	Splayed mortar fillet one course high in 50mm cavity	m	7	14.30	100.10
85	Splayed mortar fillet two course high in 50mm cavity	m	7	23.40	163.80
86	Closing 50mm cavity of hollow wall vertically with brickwork half brick wide	m	7	26.01	182.07
87	Closing 50mm cavity of hollow wall horizontally with one course of brickwork	m	7	26.01	182.07
88	Closing 50mm cavity of hollow wall horizontally with two course of brickwork	m	7	41.62	291.34
89	Closing 50mm cavity at raking top of hollow wall with two course of brickwork	m	7	41.62	291.34
	<u>Reinforcing and stabilising brickwork</u>				
90	Cutting out and removing one course half brickwall and building in 1 x 110 x 75mm lintels in lengths not exceeding 3m	m	7	105.34	737.38
91	Cutting out and removing one course one brickwall and building in 2 x 110 x 75mm lintels in lengths not exceeding 3m	m	7	210.65	1,474.55
	<u>Fair face to brickwork on horizontal stretcher bond pointed with flush horizontal and vertical joints</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
92	Extra for fair face	m2	7	135.00	945.00
93	Half brick walls pointed both sides	m2	7	369.57	2,587.00
	<u>Fair face to brickwork on horizontal stretcher bond pointed with recessed horizontal and flush vertical joints</u>				
94	Extra for fair face	m2	7	135.00	945.00
95	Half brick walls pointed both sides	m2	7	369.57	2,587.00
	<u>Fair face to brickwork on horizontal stretcher bond pointed with recessed horizontal and vertical joints</u>		7		0.00
96	Extra for fair face	m2	7	135.00	945.00
97	Half brick walls pointed both sides	m2	7	369.57	2,587.00
	<u>Bagging of 1:3 cement and sand mixture</u>				
98	On brick surfaces	m2	7	46.90	328.30
99	On concrete surfaces including fins, irregularities	m2	7	46.90	328.30
	<u>Cement wash of 1:3 liquid cement and sand mixture applied with a brush</u>				
100	On brick surfaces	m2	7	46.90	328.30
101	On concrete surfaces including fins, irregularities	m2	7	46.90	328.30
	<u>Joint forming material in movement joints</u>				
102	10mm Fibre board built in vertically between brick skins	m2	7	91.03	637.21
103	10mm Fibre board built in vertically through brick walls	m2	7	91.03	637.21
104	10mm Bitumen impregnated fibre board built in vertically between brick skins	m2	7	150.85	1,055.95
105	10mm Bitumen impregnated fibre board built in vertically through brick walls	m2	7	150.85	1,055.95
	<u>Steel bar reinforcement</u>				
106	8mm diameter mild steel bar built in horizontally (0.395 kg/m)	kg	7	13.50	94.50

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
107	10mm diameter high tensile steel bar built in horizontally (0.617 kg/m)	kg	7	13.50	94.50
	<u>Reinforcement to brickwork</u>				
108	75mm wide brick force built in horizontally	m	7	4.00	28.00
109	150mm wide brick force built in horizontally	m	7	4.00	28.00
110	230mm wide brick force built in horizontally	m	7	4.00	28.00
	<u>Prestressed fabricated lintels</u>				
111	110 x 75mm lintels in lengths not exceeding 3m	m	7	83.73	586.14
112	110 x 75mm lintels in lengths exceeding 3m and not exceeding 4,5m	m	7	83.73	586.14
113	150 x 75mm lintels in lengths not exceeding 3m	m	7	83.73	586.14
114	150 x 75mm lintels in lengths exceeding 3m and not exceeding 4,5m	m	7	83.73	586.14
	<u>Galvanised wire ties etc</u>				
115	4mm diameter roof tie 2m girth bent double with one end fixed to timber and other end built into brickwork	No	7	15.00	105.00
116	4mm diameter roof tie 2m girth bent double with one end fixed to timber and other end cast into concrete	No	7	15.00	105.00
117	4mm diameter butterfly ties fixed to brickwork	m	7	15.00	105.00
	<u>Galvanised hoop iron cramps, ties, etc</u>				
118	40 x 1,6mm "Tibond" wall tie strips shot pinned to concrete and with tie bent out and built into brickwork	No	7	26.01	182.07
119	30 x 1,6mm cramp 300mm long with two ends fixed to brickwork	No	7	30.00	210.00
120	30 x 1,6mm cramp 500mm long with one end fixed to wood and other end built into brickwork	No	7	35.00	245.00
121	30 x 1,6mm wall tie 500mm long with one end cast into concrete and other end built into brickwork	No	7	35.00	245.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
122	30 x 1,6mm wall tie 500mm long with one end shot pinned to concrete and other end built into brickwork	No	7	35.00	245.00
123	30 x 1,6mm roof tie 1,5m long with one fixed to timber and other end built into brickwork	No	7	35.00	245.00
124	30 x 1,6mm roof tie 1,5m long with one fixed to timber and other end cast into concrete	No	7	35.00	245.00
125	30 x 1,6mm ceiling hanger 1m long with one fixed to timber and other end shot pinned to concrete	No	7	35.00	245.00
	<u>Air bricks etc</u>				
126	230 x 76mm clay vermin proof air brick	No	7	48.11	336.77
127	230 x 150mm clay vermin proof air brick	No	7	48.11	336.77
128	230 x 160mm cement air brick	No	7	11.71	81.97
	<u>FACE BRICKWORK</u>				
	<u>Face brick pointed with recessed horizontal and vertical joints. (Allow P.C. amount of R6,000.00 per 1000 for supply and delivery)</u>				
129	Extra over ordinary brickwork for face brickwork in foundations	m2	7	166.45	1,165.15
130	Extra over ordinary brickwork for face brickwork in foundations circular on plan	m2	7	172.95	1,210.65
131	Extra over ordinary brickwork for face brickwork	m2	7	166.45	1,165.15
132	Extra over ordinary brickwork for face brickwork circular on plan	m2	7	172.95	1,210.65
133	Extra over ordinary brickwork for face brickwork in soldier courses	m2	7	166.45	1,165.15
134	Extra over ordinary brickwork for face brickwork in soldier courses circular on plan	m2	7	172.95	1,210.65
135	50mm cut lining to concrete	m2	7	243.42	1,703.94
136	50mm cut lining to concrete circular on plan	m2	7	257.72	1,804.04
137	Half brick wall pointed both sides	m2	7	457.72	3,204.04

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
138	One brick walls in English bond pointed both sides	m2	7	884.24	6,189.68
139	Extra over brickwork for brick-on-flat header course band	m	7	82.05	574.38
140	Extra over brickwork for brick-on-edge header course band	m	7	119.50	836.50
141	Extra over brickwork for brick-on-end soldier course band	m	7	139.01	973.07
142	Extra over brickwork for brick-on-edge header course lintel	m	7	119.50	836.50
143	Extra over brickwork for brick-on-edge header course window sill set sloping	m	7	119.50	836.50
144	Extra over brickwork for brick-on-edge header course lintel pointed one side and 110mm soffit	m	7	119.50	836.50
145	Extra over brickwork for brick-on-end soldier course lintel	m	7	139.01	973.07
146	Extra over brickwork for brick-on-edge soldier course lintel pointed one side and 110mm soffit	m	7	139.01	973.07
147	Fair raking cutting	m	7	24.70	172.90
148	Fair splay cutting	m	7	24.70	172.90
149	Fair stepped cutting and fitting over treads and risers	m	7	24.70	172.90
150	Fair circular cutting	m	7	24.70	172.90
151	Fair cutting at squint quoin or birdsmouth angle	m	7	24.70	172.90
152	Fair cutting to both sides at mitred squint quoin or birdsmouth angle	m	7	24.70	172.90
153	Cutting toothings and bonding new face brickwork to existing	m	7	24.70	172.90
154	Fair cutting and fitting around pipes not exceeding 100mm diameter	No	7	48.11	336.77
155	Fair cutting and fitting around pipes exceeding 100mm diameter and not exceeding 200mm diameter	No	7	54.62	382.34
<u>SUNDRIES</u>					
<u>Cleaning of face brick walls</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
156	Cleaning of Face Brick walls sugar soap or equally approved detergent	m2	7	62.53	437.71
157	Steam cleaning of Face Brick walls	m2	7	63.16	442.12
	<u>HERITAGE BUILDINGS ONLY - "Restore Old face brick in poor condition</u>				
158	Patching and sealing of old face brick wall in bad condition	m2	7	77.28	540.96
	<u>Brick-on-edge header course copings, sills etc. of face brick as described</u>				
159	Coping on top of half brick wall	m	7	152.01	1,064.07
160	Coping on top of one brick wall	m	7	104.02	728.14
161	Coping on top of one and a half brick wall	m	7	154.74	1,083.18
162	Coping on racking top of one brick wall	m	7	174.02	1,218.14
163	Coping on top of one brick wall circular on plan	m	7	186.63	1,306.41
164	230mm wide sills set level and slightly projecting	m	7	184.02	1,288.14
165	230mm wide sills set sloping and slightly projecting	m	7	184.02	1,288.14
	<u>Fair arches, recesses, etc of face brick as described</u>				
166	Extra over brickwork for segmental arch in half brick wall 900mm span and 340mm high formed of brick-on-edge header course ring pointed on soffit and one side including centre	No	7	224.70	1,572.90
167	Extra over brickwork for segmental arch in one brick wall 900mm span and 340mm high formed of brick-on-edge header course rings pointed on soffit and both sides including centre	No	7	266.31	1,864.17
168	Extra over brickwork for 900mm diameter semi-circular arch in one brick wall formed of 2 brick-on-edge header course rings pointed on soffit and both sides including centre	No	7	252.13	1,764.91
	<u>QUARRY TILES</u>				
	<u>150 x 150 x 25mm quarry tiles on brickwork with continuous joints in both directions and pointed on all exposed surfaces</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
169	150mm wide sill of one row of tiles set flat or sloping and slightly projecting	m	7	91.03	637.21
170	150mm wide bullnosed edge sill of one row of tiles set flat or sloping and slightly projecting	m	7	101.43	710.01
	<u>300 x 300 x 10mm quarry tiles with continuous joints in both directions flush pointed on all exposed surfaces</u>				
171	Paving on 25mm thick mortar bed	m2	7	486.33	3,404.31
172	Paving on average 50mm thick mortar bed to falls	m2	7	507.14	3,549.98
173	Extra for 150mm wide band, margin, etc. in contrasting colour	m	7	89.72	628.04
174	Fair circular cutting	m	7	5.20	36.40
175	300mm wide treads on 25mm thick mortar bed	m	7	170.35	1,192.45
176	330mm wide treads with bullnosed edge on 25mm thick mortar bed	m	7	180.75	1,265.25
177	170mm high risers on 25mm mortar bed	m	7	101.43	710.01
	<u>NUTEC-CEMENT / FIBRE-CEMENT WINDOW SILLS</u>				
	<u>Natural grey sills in single lengths bedded in class I mortar including metal fixing lugs etc</u>				
178	15 x 150mm wide sills set flat and slightly projecting	m	7	146.94	1,028.58
179	15 x 200mm wide sills set sloping and slightly projecting	m	7	169.05	1,183.35
	<u>DECORATIVE BLOCKS</u>				
	<u>400 x 400 x 100mm Concrete grille blocks in class II mortar pointed with flush joints pointed on both sides</u>				
180	In walls	m2	7	295.18	2,066.26
	<u>GLASS BRICK WALLS</u>				
	<u>190 x 190 x 80mm "Ezylay System - Solaris Samba" or equal and approved glass blocks bedded and jointed in slow-setting class I mortar with continuous joints in both directions pointed in tinted mortar both sides with flush horizontal and vertical joints</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
181	80mm walls	m2	7	993.47	6,954.29
182	80mm walls circular on plan	m2	7	1,002.58	7,018.06
	<u>190 x 190 x 80mm "Ezylay System - Solaris Light Diffusing" or equal and approved glass blocks bedded and jointed in slow- setting class I mortar with continuous joints in both directions pointed in tinted mortar both sides with recessed horizontal and</u>				
183	80mm walls	m2	7	1,130.00	7,910.00
184	80mm walls circular on plan	m2	7	1,139.12	7,973.84
	<u>Sundries in glass block walls</u>				
185	Two layers Type FV damp proof course horizontal slip joint below glass blocks	m2	7	41.62	291.34
186	10mm expanded polystyrene (density 33kg per m ³) horizontal between top of glass blocks and structure	m2	7	76.73	537.11
187	10mm expanded polystyrene (density 33kg per m ³) vertically between glass blocks and structure	m2	7	76.73	537.11
188	8mm diameter galvanised mild steel bar reinforcement horizontally and vertically	kg	7	22.10	154.70
	<u>Vanity Slabs to tops</u>				
189	Granite slab 600mm wide	m	7	1,515.03	10,605.21
190	Granite slab 900mm wide	m	7	1,744.44	12,211.08
191	Open ended dog-leg shaped vanity basin 600mm wide at a 15deg angel with a 50 x 50 mm waste chanel, mounted on concealed steel angle brackets @ 7000mm centres. Including a 600mm high splashback all made of granite	No	7	2,725.83	19,080.81
192	Extra over for cutting and opening of granite slab for stoves	No	7	273.08	1,911.56
193	Extra over for cutting and opening of tap holes	No	7	97.53	682.71
					623,743.09
					28,545,466.51

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	SUB-TOTAL <i>(Carried To Summary)</i>				
	<u>BILL NO. 6</u>				
	<u>WATERPROOFING</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	<u>Waterproofing</u>				
	Waterproofing of roofs, basements, etc. shall be laid under a ten year guarantee. Waterproofing to roofs shall be laid to even falls to outlets etc with necessary ridges, hips and valleys. Descriptions of sheet or membrane waterproofing shall be deemed to include additional labour to turn-ups and turn-downs.				
	<u>DAMP PROOFING OF WALLS AND FLOORS</u>				
	<u>One layer of 375 micron "Gundle plastic Brikgrip DPC" embossed damp proof course</u>				
1	In walls	m2	18	34.33	617.94
	<u>One layer of 250 micron "Gundle Plastic USB Green" waterproofing sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u>				
2	Under surface beds	m2	18	24.23	436.14
3	Vertically between walls	m2	18	24.23	436.14
	<u>One layer of 250 micron "Gundle Plastic Hyperelastic Orange" or equally approved waterproofing sheeting sealed at laps with "Superstik" tape carried out strictly in accordance with the</u>				
4	Under surface beds	m2	18	56.56	1,018.08

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
5	Vertically between walls	m2	18	56.56	1,018.08
	<u>Two coats "Brickseal" or equally approved bitumen emulsion waterproof coating</u>				
6	On concrete floors	m2	18	26.26	472.68
7	On concrete walls, columns and beams	m2	18	26.26	472.68
8	On concrete walls, columns and beams in foundations	m2	18	26.26	472.68
9	On brick walls	m2	18	26.26	472.68
10	On brick bagged walls	m2	18	26.26	472.68
	<u>Primer and two coats "Durabit" or equally approved rubber bitumen emulsion waterproof coating</u>				
11	On IBR, corrugated, etc. roof sheeting	m2	18	195.00	3,510.00
12	On concrete floors	m2	18	195.00	3,510.00
13	On concrete walls, columns and beams	m2	18	195.00	3,510.00
14	On concrete walls, columns and beams in foundations	m2	18	195.00	3,510.00
15	On brick walls	m2	18	195.00	3,510.00
16	On brick bagged walls	m2	18	195.00	3,510.00
	<u>Primer and three coats "Durabit" or equally approved rubber bitumen emulsion waterproof coating and one coat "Silvershield" aluminium coating</u>				
17	On concrete floors	m2	18	245.63	4,421.34
18	On concrete walls, columns and beams	m2	18	245.63	4,421.34
19	On concrete walls, columns and beams in foundations	m2	18	245.63	4,421.34
20	On brick walls	m2	18	245.63	4,421.34
21	On brick bagged walls	m2	18	245.63	4,421.34

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>4mm "Derbigum SP4" or equal and approved fully bonded waterproofing system carried out strictly in accordance with the manufacturer's instructions and under a Ten Year Insurance Backed Guarantee on materials and workmanship (On Concrete)</u>				
22	On flat floors	m2	18	225.63	4,061.34
23	On sloping floors	m2	18	225.63	4,061.34
24	On flat roofs	m2	18	225.63	4,061.34
25	On flat wooden panels,roofs, etc	m2	18	225.63	4,061.34
26	On sloping roofs	m2	18	225.63	4,061.34
27	On parapet walls	m2	18	225.63	4,061.34
28	On tops and sides of invert beams	m2	18	225.63	4,061.34
29	On bottom and sides of floor ducts, channels, etc	m2	18	225.63	4,061.34
30	On bottom and sides of box gutters	m2	18	225.63	4,061.34
31	On bottom and sides of planter boxes	m2	18	225.63	4,061.34
32	On internal surfaces of 450 x 450 x 450mm deep sump, catchpit, etc	m2	18	225.63	4,061.34
33	Sealing edge to brickwork or concrete	m	18	64.64	1,163.52
34	Sealing edge to brickwork or concrete including trowelled mastic bead	m	18	98.98	1,781.64
35	Flashing strip 200mm girth a turn-ups including sealing top edge into groove with mastic	m	18	98.98	1,781.64
36	Additional membrane 200mm girth at internal and external angles	m	18	64.64	1,163.52
37	Additional membrane 200mm girth at internal and external angles circular on plan including darts as necessary	m	18	64.64	1,163.52
38	Additional membrane 200mm girth a turn-ups including flashing strip 200mm girth and sealing top edge into groove with mastic	m	18	98.98	1,781.64

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
39	Type 40 bituminous fibreglass felt protection layer with coarse building sand blinding loose laid over horizontal waterproofing with 50mm wide side and end laps sealed with cold bituminous	m2	18	276.73	4,981.14
40	30 x 30mm softwood timber triangular fillet	m	18	20.20	363.60
41	50 x 50mm softwood timber triangular fillet	m	18	30.31	545.58
	<u>PROTECTIVE STONE DRESSING</u>				
	<u>20mm crusher stone dressing evenly spread with larger stones around outlets</u>				
42	50mm thick on waterproofing to flat roofs	m2	18	70.70	1,272.60
	<u>PROTECTIVE ROOFING PAINT</u>				
	<u>Two coats bituminous aluminium paint</u>				
43	On waterproofing to roofs	m2	18	74.54	1,341.72
44	On waterproofing to box gutters	m2	18	74.54	1,341.72
	<u>JOINT SEALANTS, ETC</u>				
	<u>Silicone sealing compound including backing cord, bond breaker, primer, etc</u>				
45	6 x 12mm. in saw cut joints in concrete surface beds	m	18	54.54	981.72
46	10 x 12mm. in expansion joints between concrete surface beds and brickwork including raking out joint filler as necessary	m	18	86.87	1,563.66
47	10 x 12mm. in vertical expansion joints between brickwork or concrete surfaces including raking out joint filler as necessary	m	18	86.87	1,563.66
48	10 x 12mm. in expansion joints in soffits raking out joint filler as necessary	m	18	86.87	1,563.66
49	10 x 12mm. in expansion joints in soffits raking out joint filler as necessary	m	18	86.87	1,563.66
	<u>Clear silicon sealant</u>				
50	Between glazed tiles and sanitary fittings	m	18	18.18	327.24

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
51	The Works or equivalent wet surface sealant	m	18	109.06	1,963.08
	<u>EPOXY</u>				
	<u>EPOXY 319/20 epoxy floor and wall coating applied in strict accordance with the manufacturer's instructions</u>				
52	On screeded floors	m2	18	131.29	2,363.22
53	On screeded seating slabs	m2	18	131.29	2,363.22
54	On plastered walls	m2	18	131.29	2,363.22
	<u>Primer and two coats "Rubberising" bitumen emulsion waterproof coating</u>				
55	On concrete floors	m2	18	331.05	5,958.90
56	On concrete walls, columns and beams	m2	18	331.05	5,958.90
57	On concrete walls, columns and beams in foundations	m2	18	331.05	5,958.90
58	On brick walls	m2	18	331.05	5,958.90
59	On brick bagged walls	m2	18	331.05	5,958.90
	<u>Fibre Flex membrane free "Flash Harry" or equally approved waterproofing</u>				
60	On flat roofs	m2	18	135.91	2,446.38
61	On flat wooden panels, roofs, etc	m2	18	135.91	2,446.38
62	On sloping roofs	m2	18	135.91	2,446.38
63	On sloping IBR roof sheeting	m2	18	135.91	2,446.38
64	On walls	m2	18	135.91	2,446.38
65	On tops and sides of invert beams	m2	18	135.91	2,446.38
	<u>Bituminised heat-laminated layer of aluminium foil "Slatex 2000" or equivalent waterproofing to slate roofs</u>				
66	On flat roofs	m2	18	211.94	3,814.92
67	On sloping roofs	m2	18	211.94	3,814.92

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	<u>Straight cutting</u>				
	Description of all roof coverings are deemed to include for all straight cutting				
	<u>TILES</u>				
	<u>Marley Mendip or equal and approved profile M22 factory- coated through colour concrete roof tiles, size 420 x 332mm manufactured in accordance with SABS 542, of approved colour with matching fittings nailed and/or fixed with suitable non-corrosive clips as required to and including 38 x 50mm sawn softwood battens at 320mm centres on an underlay of SABS approved "Gundle" white 250 micron plastic sheeting laid horizontally over trusses, with minimum overlap of 150mm and secured with non-corrosive clout nails to the trusses</u>				
1	Roof covering with pitch not exceeding 50 degrees	m2	14	235.37	3,295.18
2	Side cladding at gable ends	m2	14	235.37	3,295.18
3	Circular cutting	m	14	6.51	91.14
4	Taper ridge tiles edge bedded and pointed in 1:3 cement/sand mortar tinted to match tile colour over 150mm wide DPC	m	14	187.25	2,621.50
5	Taper hip tiles edge bedded and pointed in 1:3 cement/sand mortar tinted to match tile colour over 150mm wide DPC	m	14	187.25	2,621.50
6	Verge capping tiles to match roofing tiles fixed with non-corrosive fixing accessories	m	14	271.77	3,804.78
7	Purpose made tile to end ridge bedded and pointed in 1:3 cement mortar tinted to match existing colour	No	14	146.94	2,057.16
8	Open cut valley including cutting of tiles and waste to both sides forming a neat open channel of at least 100mm	m	14	159.94	2,239.16

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
9	Purpose made tile to two-way intersection of ridge with hips bedded and pointed in 1:3 cement mortar tinted to match existing colour	No	14	15.60	218.40
10	Cutting and waste at abutments, parapets and verges	m	14	15.60	218.40
	<u>SUNDRIES</u>				
11	Making good and sealing loose tiles to roof <u>Harveytile 1675 x 397mm "Tufftile" Zincalume coated mild steel tile with stonecoat finish on one side fixed with serrated galvanized clout nails to and including 38 x 38mm sawn softwood batten at 369mm centres on an underlay of SABS approved "Gundle" white 250 micron plastic sheeting with 150mm lapped and sealed joints laid horizontally over and secured with non-corrosive clout nails to the trusses</u>	m	14	46.62	652.68
12	Roof covering with pitch not exceeding 50 degrees	m2	14	258.91	3,624.74
13	Side cladding to gables, etc	m2	14	258.91	3,624.74
14	Circular cutting	m	14	6.51	91.14
15	Square ridge tapered capping to match roofing tile	m	14	187.25	2,621.50
16	Angle ridge tapered capping to match roofing tile	m	14	187.25	2,621.50
17	Square hip tapered capping to match roofing tile	m	14	187.25	2,621.50
18	Angle hip tapered capping to match roofing tile	m	14	186.59	2,612.26
19	Gable tapered trim to match roofing tile	m	14	271.77	3,804.78
20	Bargeboard serrated cover to match roofing tile	m	14	146.94	2,057.16
21	Sidewall serrated flashing to match roofing tile	m	14	161.63	2,262.82
22	Headwall flashing to match roofing tile	m	14	161.63	2,262.82
23	Cover flashing to match roofing tile	m	14	161.63	2,262.82
24	Hip end cap	No	14	146.94	2,057.16
25	Ridge end cap	No	14	146.94	2,057.16
26	Junction of ridge with two hip capping	No	14	159.94	2,239.16

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
27	Junction of ridge with one ridge capping	No	14	146.94	2,057.16
28	Cutting and waste including bending edge of tiles up or down at abutments, parapets and verges	m	14	15.60	218.40
29	Cut valley including cutting of tiles and waste to both sides including bending edge of tiles down forming a neat 75mm open channel	m	14	15.60	218.40
30	Cut valley including cutting of tiles and waste to both sides including bending edge of tiles down forming a neat closed channel	m	14	15.60	218.40
31	Cut hip including cutting of tiles and waste to both sides including bending edge of tiles up forming a snug tapered fit	m	14	15.60	218.40
<u>SUNDRIES</u>					
32	Making good and sealing loose tiles to roof	m	14	46.62	652.68
<u>THATCH</u>					
<u>SUPPLEMENTARY PREAMBLES</u>					
Grass in the Gauteng area suitable for thatch is the hyparrhenia species and is obtainable in lengths varying from 760 to 1020mm					
The minimum density to which the above-mentioned grass should be compacted is 30kg/m2/150mm thickness					
The fibre blanket usually consists of an interlay or an underlay of multilayered fire -retarded reinforced double-sided aluminium foil sheeting					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>150mm Thick thatch of hand cut grass of the hyparrhenia hirta species in lengths varying from 760 to 1020mm laid in bundles of suitable size, compacted to a minimum density of 30kg/m2/150mm thickness and fixed by means of suitable fixing rods interlaced through and over the bundles at not exceeding 600mm centres and secured with tarred twine to and including eucalyptus battens CCa treated in accordance with SANS 457-2, varying in diameter from 20 to 40mm, spaced at maximum 300mm centres generally and at closer centres nearer to eaves, including a fire-retardant interlay of multilayered reinforced double-sided aluminium foil sheeting in accordance with SANS 1381-4 with mass of not less than 272g/m2 and a Class I fire rating in accordance with SANS 0177-3</u>				
33	Covering to general roof slopes	m2	14	301.69	4,223.66
34	Covering to general roof slopes including a spreadlayer to exposed soffit	m2	14	301.69	4,223.66
35	Coverings to dormers, turrets, etc	m2	14	301.69	4,223.66
36	Ridges formed by extending covering above ridge level on the one roof slope, bending over and down on the opposite slope and fixing and securing as described for roof covering and repeating the process on the other roof slope including covering with galvanised wire bird netting 900mm girth and necessary additional fixing rods	m	14	187.25	2,621.50
37	Purpose made continuous glass fibre ridge capping of not less than 1,5mm thick material 1300mm girth and in suitable lengths, securely fixed to thatch with 75mm wire lapped and sealed heading joints including grass filling under	m	14	231.46	3,240.44
38	Extra over ridge capping for purpose made angle piece	No	14	249.67	3,495.38
39	Extra over ridge capping for purpose made curved returned end piece	No	14	249.67	3,495.38
	<u>PROFILED FIBRE-CEMENT SHEETING AND ACCESSORIES</u>				
	<u>Nutec Bigsix sheeting or equally approved fixed to timber/steel purlins or rails</u>				
40	Roof covering with pitch not exceeding 50 degrees with side and end laps sealed with 12 x 25mm closed cell impregnated polyurethane foam strips	m2	14	253.56	3,549.84

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
41	Side cladding	m2	14	224.95	3,149.30
42	Extra over roof covering for soaker flange sheet suitable for ventilator with throat size 850 x 460mm	No	14	604.67	8,465.38
43	Circular cutting	m	14	6.51	91.14
44	Side apron flashing	m	14	154.74	2,166.36
45	End apron flashing	m	14	221.07	3,094.98
46	Plain fixed angle ridge/hip capping flashing	m	14	245.76	3,440.64
47	Plain adjustable ridge/hip capping flashing	m	14	330.30	4,624.20
48	Fixed angle wide profile ridge sheets	m	14	245.76	3,440.64
49	Close fitting adjustable ridge capping	m	14	262.67	3,677.38
50	Fixed angle sawtooth ridge capping	m	14	245.76	3,440.64
51	Adjustable sawtooth ridge capping	m	14	301.69	4,223.66
52	Birdproofing	m	14	84.52	1,183.28
53	Eaves fillers	m	14	166.45	2,330.30
54	Straight sill flashing	m	14	161.24	2,257.36
55	U-flashing	m	14	163.84	2,293.76
56	Hip and end cap	No	14	109.22	1,529.08
57	Ridge end cap	No	14	109.22	1,529.08
58	Junction of ridge with two hip cappings	m	14	219.75	3,076.50
59	Junction of ridge with two hip cappings	No	1		
<u>PROFILED METAL SHEETING AND ACCESSORIES</u>					
<u>0,58mm corrugated profile roll-formed Z275 spelter galvanised steel sheeting, in single lengths, fixed to timber/steel purlins or rails and</u> <u>0,58mm galvanised sheet steel accessories</u>					
60	Roof covering with pitch not exceeding 50 degrees	m2	14	288.68	4,041.52

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
61	Roof covering with pitch not exceeding 50 degrees side laps seam stitched	m2	14	295.18	4,132.52
62	Roof covering with pitch not exceeding 50 degrees side laps seal with 6 x 20mm closed cell impregnated polyurethane strips and seam stitched	m2	14	310.79	4,351.06
63	Side cladding	m2	14	288.68	4,041.52
64	Side cladding circular on plan to 3,0m radius	m2	14	288.68	4,041.52
65	Roof covering and side cladding to dormers, turrets, etc	m2	14	288.68	4,041.52
66	Extra over roof covering /side cladding for 1,25mm semi-opaque 90% light transmission "Modek - Polycarbonate" translucent panel	m2	14	72.82	1,019.48
67	Circular cutting	m	14	6.51	91.14
68	Extra over roof covering for 20 degree crank to form ridge	m	14	59.81	837.34
69	Extra over roof covering for 110 degrees bullnose to form 450mm radius at edge	m	14	180.75	2,530.50
70	Ridge capping 462mm girth	m	14	111.06	1,554.87
71	Hip capping 462mm girth	m	14	111.06	1,554.87
72	Side wall flashing 308mm girth	m	14	111.06	1,554.87
73	Head wall flashing 308mm girth	m	14	111.06	1,554.87
74	Cover flashing 154mm girth	m	14	111.06	1,554.87
75	Gable trim 308mm girth	m	14	111.06	1,554.87
76	Apex flashing 462mm girth	m	14	111.06	1,554.87
77	Corner trim 462mm girth	m	14	111.06	1,554.87
78	Apron flashing 462mm girth	m	14	111.06	1,554.87
79	Drip flashing 154mm girth	m	14	111.06	1,554.87
80	Sill flashing 308mm girth	m	14	111.06	1,554.87

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
81	Jamb flashing 308mm girth	m	14	111.06	1,554.87
82	Narrow and broad flute closers	m	14	30.94	433.16
83	Narrow and broad flute closers raking at valleys or hips	m	14	30.94	433.16
84	Moulded narrow and broad rib polyethylene filler blocks	m	14	30.94	433.16
85	Moulded narrow and broad rib polyethylene filler blocks raking at valleys and hips	m	14	30.94	433.16
	<u>SUNDRIES</u>				
86	Making good roof sheeting by screwing and sealing of loose or missing screws /nails. Sealing using waterproofing	m2	14	39.88	558.32
	<u>0,58mm corrugated profile roll-formed Z275 spelter galvanised steel sheeting with "Global-Sil" finish on one side, in single lengths fixed to timber/steel purlins or rails and 0,58mm galvanised sheet steel accessories with "Global-Sil" finish on one side</u>				
87	Roof covering with pitch not exceeding 50 degrees	m2	14	331.59	4,642.26
88	Roof covering with pitch not exceeding 50 degrees with side laps seam stitched	m2	14	338.09	4,733.26
89	Roof covering with pitch not exceeding 50 degrees side laps seal with 6 x 20mm closed cell impregnated polyurethane strips and seam stitched	m2	14	353.70	4,951.80
90	Side cladding	m2	14	331.59	4,642.26
91	Side cladding circular on plan to 3,0m radius	m2	14	331.59	4,642.26
92	Roof covering and side cladding to dormers, turrets, etc	m2	14	331.59	4,642.26
93	Extra over roof covering /side cladding for 1,25mm semi-opaque 90% light transmission "Modek - Polycarbonate" translucent panel	m2	14		0.00
94	Circular cutting	m	14	6.51	91.14
95	Extra over roof covering for 20 degree crank to form ridge	m	14	59.81	837.34
96	Extra over roof covering for 110 degrees bullnose to form 450mm radius at edge	m	14	180.75	2,530.50

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
97	Ridge capping 462mm girth	m	14	111.06	1,554.87
98	Hip capping 462mm girth	m	14	111.06	1,554.87
99	Side wall flashing 308mm girth	m	14	111.06	1,554.87
100	Head wall flashing 308mm girth	m	14	111.06	1,554.87
101	Cover flashing 154mm girth	m	14	111.06	1,554.87
102	Gable trim 308mm girth	m	14	111.06	1,554.87
103	Apex flashing 462mm girth	m	14	111.06	1,554.87
104	Corner trim 462mm girth	m	14	111.06	1,554.87
105	Apron flashing 462mm girth	m	14	111.06	1,554.87
106	Drip flashing 154mm girth	m	14	111.06	1,554.87
107	Sill flashing 308mm girth	m	14	111.06	1,554.87
108	Jamb flashing 308mm girth	m	14	111.06	1,554.87
109	Narrow and broad flute closers	m	14	30.94	433.16
110	Narrow and broad flute closers raking at valleys or hips	m	14	30.94	433.16
111	Moulded narrow and broad rib polyethylene filler blocks	m	14	30.94	433.16
112	Moulded narrow and broad rib polyethylene filler blocks raking at valleys and hips	m	14	39.88	558.32
<u>SUNDRIES</u>					
113	Making good roof sheeting by screwing and sealing of loose or missing screws /nails. Sealing using waterproofing	m2	14	42.93	601.02
	<u>0,58mm IBR profile Z275 spelter galvanised steel troughed sheeting, in single lengths fixed to timber/steel purlins or rails and 0,58mm galvanised sheet steel accessories</u>				
114	Roof covering with pitch not exceeding 50 degrees	m2	14	284.78	3,986.92
115	Roof covering with pitch not exceeding 50 degrees side laps seam stitched	m2	14	292.58	4,096.12

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
116	Roof covering with pitch not exceeding 50 degrees side laps seal with 6 x 20mm closed cell impregnated polyurethane strips and seam stitched	m2	14	306.88	4,296.32
117	Side cladding	m2	14	284.78	3,986.92
118	Side cladding circular on plan to 3,0m radius	m2	14	284.78	3,986.92
119	Roof covering and side cladding to dormers, turrets, etc	m2	14	284.78	3,986.92
120	Extra over roof covering /side cladding for 1,25mm semi-opaque 90% light transmission "Modek - Polycarbonate" translucent panel	m2	14	72.82	1,019.48
121	Circular cutting	m	14	6.51	91.14
122	Extra over roof covering for 20 degree crank to form ridge	m	14	59.81	837.34
123	Extra over roof covering for 110 degrees bullnose to form 450mm radius at edge	m	14	180.75	2,530.50
124	Ridge capping 462mm girth	m	14	111.06	1,554.87
125	Hip capping 462mm girth	m	14	111.06	1,554.87
126	Side wall flashing 308mm girth	m	14	111.06	1,554.87
127	Head wall flashing 308mm girth	m	14	111.06	1,554.87
128	Cover flashing 154mm girth	m	14	111.06	1,554.87
129	Gable trim 308mm girth	m	14	111.06	1,554.87
130	Apex flashing 462mm girth	m	14	111.06	1,554.87
131	Corner trim 462mm girth	m	14	111.06	1,554.87
132	Apron flashing 462mm girth	m	14	111.06	1,554.87
133	Drip flashing 154mm girth	m	14	111.06	1,554.87
134	Sill flashing 308mm girth	m	14	111.06	1,554.87
135	Jamb flashing 308mm girth	m	14	111.06	1,554.87
136	Narrow and broad flute closers	m	14	111.06	1,554.87

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
137	Narrow and broad flute closers raking at valleys or hips	m	14	41.87	586.24
138	Moulded narrow and broad rib polyethylene filler blocks	m	14	41.87	586.24
139	Moulded narrow and broad rib polyethylene filler blocks raking at valleys and hips	m	14	41.87	586.24
	<u>SUNDRIES</u>				
140	Making good roof sheeting by screwing and sealing of loose or missing screws /nails. Sealing using waterproofing	m2	14	42.93	601.02
	<u>0,58mm. IBR profile Z275 spelter galvanised steel troughed sheeting with "Global-Sil" finish on one side, in single lengths fixed to steel purlins or rails and 0,58mm galvanised sheet steel accessories with "Global-Sil" finish on one side</u>				
141	Roof covering with pitch not exceeding 50 degrees	m2	14	327.69	4,587.66
142	Roof covering with pitch not exceeding 50 degrees side laps seam stitched	m2	14	332.89	4,660.46
143	Roof covering with pitch not exceeding 50 degrees side laps seal with 6 x 20mm closed cell impregnated polyurethane strips and seam stitched	m2	14	332.89	4,660.46
144	Side cladding	m2	14	327.69	4,587.66
145	Side cladding circular on plan to 3,0m radius	m2	14	327.69	4,587.66
146	Roof covering and side cladding to dormers, turrets, etc	m2	14	327.69	4,587.66
147	Circular cutting	m	14	6.51	91.14
148	Extra over roof covering for 20 degree crank to form ridge	m	14	59.81	837.34
149	Extra over roof covering for 110 degrees bullnose to form 450mm radius at edge	m	14	180.75	2,530.50
150	Ridge capping 462mm girth	m	14	111.06	1,554.87
151	Hip capping 462mm girth	m	14	111.06	1,554.87
152	Side wall flashing 308mm girth	m	14	111.06	1,554.87
153	Head wall flashing 308mm girth	m	14	111.06	1,554.87

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
154	Cover flashing 154mm girth	m	14	111.06	1,554.87
155	Gable trim 308mm girth	m	14	111.06	1,554.87
156	Apex flashing 462mm girth	m	14	111.06	1,554.87
157	Corner trim 462mm girth	m	14	111.06	1,554.87
158	Apron flashing 462mm girth	m	14	111.06	1,554.87
159	Drip flashing 154mm girth	m	14	111.06	1,554.87
160	Sill flashing 308mm girth	m	14	111.06	1,554.87
161	Jamb flashing 308mm girth	m	14	111.06	1,554.87
162	Narrow and broad flute closers	m	14	41.87	586.24
163	Narrow and broad flute closers raking at valleys or hips	m	14	41.87	586.24
164	Moulded narrow and broad rib polyethylene filler blocks	m	14	41.87	586.24
165	Moulded narrow and broad rib polyethylene filler blocks raking at valleys and hips	m	14	41.87	586.24
	<u>SUNDRIES</u>				
166	Making good roof sheeting by screwing and sealing of loose or missing screws /nails. Sealing using waterproofing	m2	14	42.93	601.02
	<u>0,6mm "Klip-lok 700" Z275 spelter galvanised ribbed sheet steel in single lengths fixed to timber/steel purlins or rails and 0,58mm galvanised sheet steel accessories</u>				
167	Roof covering with pitch not exceeding 50 degrees	m2	14	365.40	5,115.60
168	Roof covering with pitch not exceeding 50 degrees side laps seam stitched	m2	14	365.40	5,115.60
169	Roof covering with pitch not exceeding 50 degrees side laps seal with 6 x 20mm closed cell impregnated polyurethane strips and seam stitched	m2	14	365.40	5,115.60
170	Side cladding	m2	14	373.20	5,224.80
171	Side cladding circular on plan to 3,0m radius	m2	14		

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
172	Roof covering and side cladding to dormers, turrets, etc	m2	14	387.50	5,425.00
173	Extra over roof covering /side cladding for 1,25mm semi-opaque 90% light transmission "Modek - Polycarbonate" translucent panel	m2	14	79.33	1,110.62
174	Circular cutting	m	14	6.51	91.14
175	Extra over roof covering for 20 degree crank to form ridge	m	14	59.81	837.34
176	Extra over roof covering for 110 degrees bullnose to form 450mm radius at edge	m	14	180.75	2,530.50
177	Ridge capping 462mm girth	m	14	101.43	1,420.02
178	Hip capping 462mm girth	m	14	101.43	1,420.02
179	Side wall flashing 308mm girth	m	14	101.43	1,420.02
180	Head wall flashing 308mm girth	m	14	101.43	1,420.02
181	Cover flashing 154mm girth	m	14	101.43	1,420.02
182	Gable trim 308mm girth	m	14	101.43	1,420.02
183	Apex flashing 462mm girth	m	14	101.43	1,420.02
184	Corner trim 462mm girth	m	14	101.43	1,420.02
185	Apron flashing 462mm girth	m	14	101.43	1,420.02
186	Drip flashing 154mm girth	m	14	101.43	1,420.02
187	Sill flashing 308mm girth	m	14	101.43	1,420.02
188	Jamb flashing 308mm girth	m	14	101.43	1,420.02
	<u>0,6mm "Klip-lok 700" Z275 spelter galvanised ribbed sheet steel with "Global-Sil" finish on one side, in single lengths fixed to timber/steel purlins or rails and 0,58mm galvanised sheet steel accessories with "Global-Sil" finish on one side</u>				
189	Roof covering with pitch not exceeding 50 degrees	m2	14	321.31	4,498.34
190	Roof covering with pitch not exceeding 50 degrees side laps seam stitched	m2	14	321.31	4,498.34

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
191	Roof covering with pitch not exceeding 50 degrees side laps seal with 6 x 20mm closed cell impregnated polyurethane strips and seam stitched	m2	14	321.31	4,498.34
192	Side cladding	m2	14	321.31	4,498.34
193	Side cladding circular on plan to 3,0m radius	m2	14	421.31	5,898.34
194	Roof covering and side cladding to dormers, turrets, etc	m2	14	443.42	6,207.88
195	Circular cutting	m	14	6.51	91.14
196	Extra over roof covering for 20 degree crank to form ridge	m	14	59.81	837.34
197	Extra over roof covering for 110 degrees bullnose to form 450mm radius at edge	m	14	180.75	2,530.50
198	Ridge capping 462mm girth	m	14	102.74	1,438.36
199	Hip capping 462mm girth	m	14	102.74	1,438.36
200	Side wall flashing 308mm girth	m	14	101.43	1,420.02
201	Head wall flashing 308mm girth	m	14	101.43	1,420.02
202	Cover flashing 154mm girth	m	14	101.43	1,420.02
203	Gable trim 308mm girth	m	14	102.74	1,438.36
204	Apex flashing 462mm girth	m	14	102.74	1,438.36
205	Corner trim 462mm girth	m	14	111.82	1,565.48
206	Apron flashing 462mm girth	m	14	111.82	1,565.48
207	Drip flashing 154mm girth	m	14	111.82	1,565.48
208	Sill flashing 308mm girth	m	14	111.82	1,565.48
209	Jamb flashing 308mm girth	m	14	111.82	1,565.48
<u>ROOF VENTILATORS</u>					
<u>Everite</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
210	Nutec Ventair Product No. 760-270 fibre-cement ventilator fixed on soaker flange sheet (soaker flange sheet elsewhere) including sealing strips, fixing accessories, etc	m	14	3,791.82	53,085.48
	<u>ROOF AND WALL INSULATION</u>				
	<u>Sisalation RSA 420 heavy industrial grade aluminium foil based insulation</u>				
211	Insulation laid taut over purlins (at approximately 1800mm centres) and fixed concurrent with roof covering including galvanised steel straining wires	m2	14	59.53	833.39
	<u>Sisalation RSA 410 residential grade glass fibre reinforced aluminium foil bonded insulation</u>				
212	Insulation laid taut over rafters (at approximately 1200mm centres) and fixed concurrent with tiling battens, purlins, etc	m2	14	59.53	833.39
	<u>SHEET METAL FLASHINGS, LININGS, COPINGS, ETC.</u>				
	<u>0,58mm. galvanised sheet iron</u>				
213	Flashings	m2	14	167.75	2,348.50
214	Stepped cover flashings	m2	14	167.75	2,348.50
215	Stepped cover flashings to roof pitches exceeding 50 degrees	m2	14	167.75	2,348.50
216	Soakers	m2	14	167.75	2,348.50
217	Lining to valleys with riveted and soldered joints	m2	14	167.75	2,348.50
218	Lining to box gutters with riveted and soldered joints	m2	14	167.75	2,348.50
219	Copings with riveted and soldered joints attached with suitable clips at 500mm centres along both edges, riveted to coping and plugged to brickwork or concrete	m2	14	202.85	2,839.90
220	Antguards	m2	14	141.74	1,984.36
221	Circular cutting	m	14	6.51	91.14
	<u>0,58mm. galvanised sheet iron with "Global-Sil" finish on one side</u>				
222	Flashings	m2	14	183.35	2,566.90

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
223	Stepped cover flashings	m2	14	183.35	2,566.90
224	Stepped cover flashings to roof pitches exceeding 50 degrees	m2	14	183.35	2,566.90
225	Soakers	m2	14	183.35	2,566.90
226	Lining to valleys with riveted and soldered joints	m2	14	183.35	2,566.90
227	Lining to box gutters with riveted and soldered joints	m2	14	183.35	2,566.90
228	Copings with riveted and soldered joints attached with suitable clips at 500mm centres along both edges, riveted to coping and plugged to brickwork or concrete	m2	14	218.47	3,058.58
229	Antguards	m2	14	183.35	2,566.90
230	Circular cutting	m	14	6.51	91.14
	<u>SLATES</u>				
	<u>420 X 330mm "Marley Eternit" slates or equally approved laid in single thickness with a headlap of 90mm on underlay of bituminous roofing felt in accordance with SANS 92 Type 60 faced with 0.1mm aluminium foil over half its width with 150mm head laps and with tops of slates nailed with galvanised steel clout nails to and including 38 x 25mm sawn softwood battens at 450mm centres</u>				
231	Roof covering with pitches not exceeding 25 degrees	m2	14	448.62	6,280.68
232	Roof covering with pitches not exceeding 25 degrees, circular across the fall to ?m radius	m2	14	448.62	6,280.68
	<u>Roof covering circular along the fall not exceeding 6m radius</u>				
233	Roof covering to conical shape with a 25 degree pitch and a radius as per architects specification, including cutting slates to wedge shape	m2	14	493.48	6,908.72
234	Side cladding to gables etc	m2	14	493.51	6,909.14
235	Side cladding to gables etc circular on plan to ?m radius	m2	14	493.51	6,909.14
236	Soft cladding to eaves overhangs etc	m2	14	493.51	6,909.14
237	Roof covering in side cladding to dormers, turrets, etc	m2	14	492.84	6,899.76

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
238	Circular cutting	m	14	6.51	91.14
239	Extra on roof covering for double course at eaves including fixing clips and 38 x 38mm softwood tilting fillet	m	14	96.56	1,351.84
240	Close cut and mitred ridge including soakers of bituminous roofing felt in accordance with SANS 92 Type 60 and necessary additional battens	m	14	127.95	1,791.30
241	Close cut and mitred valley including soakers of bituminous roofing felt in accordance with SANS 92 Type 60 and necessary additional battens	m	14	127.95	1,791.30
242	Close cut and mitred vertical angle including soakers of bituminous roofing felt in accordance with SANS 92 Type 60 and necessary additional battens	m	14	127.95	1,791.30
<u>SUNDRIES</u>					
243	Making good and sealing slate tiles and shingles to roof	m2	14	67.47	944.58
<u>RAINWATER DISPOSAL</u>					
<u>0,6mm Galvanised sheet iron</u>					
244	125mm Half round eaves gutter with beaded front edge including fixing brackets	m	14	115.73	1,620.22
245	Extra over 125mm half round eaves gutter for stopped end	No	14	67.62	946.68
246	Extra over 125mm half round eaves gutter for angle	No	14	100.13	1,401.82
247	Extra over 125mm half round eaves gutter for outlet for 76mm diameter pipe	No	14	84.52	1,183.28
248	76mm diameter rainwater pipes	m	14	88.41	1,237.74
249	Extra over 76mm diameter rainwater pipe for bend	No	14	53.32	746.48
250	Extra over 76mm diameter rainwater pipe for shoe	No	14	53.32	746.48
251	100 x 125mm eaves gutter with beaded front edge including fixing brackets	m	14	126.13	1,765.82
252	Extra over 100 x 125mm eaves gutter for stopped end	No	14	72.82	1,019.48

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
253	Extra over 100 x 125mm eaves gutter for angle	No	14	100.13	1,401.82
254	Extra over 100 x 125mm eaves gutter for 100 x 76mm outlet	No	14	84.52	1,183.28
255	Extra over 76mm diameter rainwater pipe for outlet	No	14	84.52	1,183.28
256	100 x 76mm rainwater pipes	m	14	96.23	1,347.22
257	Extra over 100 x 76mm rainwater pipe for soldered bend	No	14	57.22	801.08
258	Extra over 100 x 76mm rainwater pipe for soldered shoe	No	14	57.22	801.08
	<u>Extruded Seamless Aluminium</u>				
259	125 x 85mm OGEE eaves gutter	m	14	131.33	1,838.62
260	125 x 85mm eaves gutter stopped end	No	14	79.33	1,110.62
261	125 x 85mm eaves gutter mitre corner	No	14	114.43	1,602.02
262	75 x 50mm eaves gutter outlet	No	14	97.53	1,365.42
263	75 x 50mm fluted rainwater pipe	No	14	101.43	1,420.02
264	75 x 50mm crimped rainwater pipe bend	No	14	63.72	892.08
265	75 x 50mm crimped rainwater pipe shoe	No	14	63.72	892.08
266	150 x 125mm OGEE eaves gutter	m	14	143.05	2,002.70
267	150 x 125mm eaves gutter stopped end	No	14	84.52	1,183.28
268	150 x 125mm eaves gutter mitre corner	No	14	114.43	1,602.02
269	100 x 75mm eaves gutter outlet	No	14	97.53	1,365.42
270	100 x 75mm fluted rainwater pipe	m	14	110.53	1,547.42
271	100 x 75mm crimped rainwater pipe bend	No	14	67.62	946.68
272	100 x 75mm crimped rainwater pipe shoe	No	14	67.62	946.68
	<u>REPLACE DAMAGED GUTTERS AND DOWNPIPES</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Carefully cut and remove gutter and / or down pipe in damaged section, replace with new including gutter brackets, pipe clips, making water tight at joints, prepare and paint to match existing and leave in good working order.</u>				
	<u>0,6mm Galvanised Sheet Iron</u>				
273	125mm Half round eaves gutter with beaded front edge	m	14	119.64	1,674.96
274	125mm half round eaves gutter stopped end	No	14	71.52	1,001.28
275	125mm half round eaves gutter angle	No	14	104.02	1,456.28
276	125mm half round eaves gutter outlet for 76mm diameter pipe	No	14	88.41	1,237.74
277	76mm diameter rainwater pipe	m	14	92.33	1,292.62
278	76mm diameter rainwater pipe bend	No	14	57.22	801.08
279	76mm diameter rainwater pipe shoe	No	14	57.22	801.08
280	100 x 125mm eaves gutter with beaded front edge	m	14	130.03	1,820.42
281	100 x 125mm eaves gutter stopped end	No	14	76.73	1,074.22
282	100 x 125mm eaves gutter angle	No	14	104.02	1,456.28
283	100 x 76mm eaves gutter outlet	No	14	88.41	1,237.74
284	100 x 76mm rainwater pipe	m	14	100.13	1,401.82
285	100 x 76mm rainwater pipe soldered bend	No	14	61.11	855.54
286	100 x 76mm rainwater pipe soldered shoe	No	14	61.11	855.54
	<u>Sundries</u>				
287	Replace or install new gutter bracket and / or pipe clip	No	14	21.37	299.18
288	Repair leaking joint to Galvanised Iron gutter and / or down pipe not exceeding 500mm girth	No	14	31.86	446.04
289	Repair leaking joint to Aluminium gutter and / or down pipe not exceeding 500mm girth	No	14	31.86	446.04
290	Repair leaking joint to Galvanised Iron down pipe not exceeding 350mm diameter	No	14	31.86	446.04

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
291	Replace or install new 80 or 100mm Full-bore cast iron outlet grating	No	14	1,997.84	27,969.76
					683,057.09
	SUB-TOTAL <i>(Carried To Summary)</i>				29,440,511.61
	<u>BILL NO. 8</u>				
	<u>CARPENTRY AND JOINERY</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	<u>Particle board</u>				
	Particle board shall comply with the following specifications: a) SABS 1300 Particle board: exterior and flooring type b) SABS 1301 Particle board: interior type				
	<u>Joinery</u>				
	Description of frames shall be deemed to include frames, transoms, mullions, rails, etc Description of hardwood joinery shall be deemed to include pelleting of bolt holes				
	<u>Fixings</u>				
	Items described as "nailed" shall be deemed to be fixed with hardened steel nails or shot pins to brickwork or concrete.				
	<u>Decorative laminated finish</u>				
	Laminated finish shall be glued under pressure. Edge strips shall be butt jointed at junctions with adjacent similar finish				
	<u>ROOFS, ETC</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Prefabricated timber roof construction complete, including battens, runners, bracing, hips, valleys, cleats, etc. designed, supplied and fixed complete</u>				
	<u>Flat roof construction for rectangular shaped</u>				
1	Flat roof construction for rectangular shaped building with a 400mm overhang projection on both sides	m2	6	634.06	3,804.36
	<u>Pitched roof construction for rectangular shaped</u>				
2	Mono pitch roof trusses for rectangular shaped building with a pitch not exceeding 270 and a 500mm eaves overhang projection on one side, erected in position complete	No	6	851.10	5,106.60
3	Double pitch roof trusses for rectangular shaped building with a pitch not exceeding 270 and a 500mm eaves overhang projection on one side, erected in position complete	No	6	932.87	5,597.22
	<u>Sawn softwood grade 4</u>				
4	38 x 38mm Battens	m	6	24.07	144.42
5	38 x 76mm Tilting battens	m	6	29.91	179.46
6	38 x 76mm wall plates	m	6	29.91	179.46
7	38 x 76mm wall plates bolted	m	6	40.31	241.86
8	50 x 76mm bracing	m	6	45.51	273.06
9	50 x 76mm hangers	m	6	45.51	273.06
10	50 x 75mm purlins	m	6	45.51	273.06
11	50 x 50mm trimmers	m	6	23.40	140.40
12	38 x 152mm sprockets	m	6	53.32	319.92
13	38 x 114mm Ceiling joists in lengths not exceeding 2,4m	m	6	46.81	280.86
14	50 x 152mm Ceiling joists in lengths exceeding 2,4m and not exceeding 3,9m	m	6	81.92	491.52
15	38 x 114mm Rafters in lengths not exceeding 2,4m	m	6	46.81	280.86

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
16	50 x 152mm Rafters in lengths exceeding 2,4m and not exceeding 3,9m	m	6	81.92	491.52
17	76 x 152mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m	6	117.03	702.18
18	38 x 114mm Bearers in lengths not exceeding 2,4mm	m	6	46.81	280.86
19	50 x 152mm Bearers in lengths exceeding 2,4mm and not exceeding 3,9mm	m	6	81.92	491.52
20	76 x 152mm Bearers in lengths exceeding 3,9m and not exceeding 6,6m	m	6	117.03	702.18
	<u>Sawn softwood grade 6</u>				
21	76 x 228mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m	6	210.65	1,263.90
22	76 x 228mm Rafters in lengths exceeding 6,6m	m	6	223.66	1,341.96
23	76 x 228mm Bearers in lengths exceeding 3,9m and not exceeding 6,6m	m	6	210.65	1,263.90
24	76 x 228mm Bearers in lengths exceeding 6,6m	m	6	223.66	1,341.96
	<u>Wrought softwood grade 6</u>				
25	76 x 228mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m	6	296.48	1,778.88
26	76 x 228mm Rafters in lengths exceeding 6,6m	m	6	310.79	1,864.74
27	76 x 228mm Bearers in lengths exceeding 3,9m and not exceeding 6,6m	m	6	296.48	1,778.88
28	76 x 228mm Bearers in lengths exceeding 6,6m	m	6	310.79	1,864.74
	<u>Sundries</u>				
29	Two coats creosote on sawn timbers	m2	6	46.81	280.86
30	2,5mm diameter galvanised wire tie 2m girth wrapped around rafter and purlin with ends tied together	No	6	14.30	85.80
31	30 x 1,6mm galvanised hoop iron roof tie 1500mm girth with each end fixed to timber	No	6	46.81	280.86

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
32	4,5mm Diameter galvanised wire tie 1500mm girth with one end fired to timber and other end built into brickwork	No	6	20.81	124.86
	<u>EAVES, VERGES, ETC</u>				
	<u>Sawn softwood</u>				
33	38 x 38mm Branders	m	6	18.21	109.26
34	38 x 114mm Bearers	m	6	31.21	187.26
35	38 x 114mm Hangers	m	6	31.21	187.26
	<u>Wrought softwood</u>				
36	Eaves soffit covering of 25 x 38mm slates at 60mm centres including galvanised wire bird mesh backing	m2	6	457.72	2,746.32
37	Verge soffit covering of 25 x 38mm slates at 60mm centres including galvanised wire bird mesh backing	m2	6	457.72	2,746.32
	<u>Wrought Meranti</u>				
38	Eaves soffit covering of 22 x 96mm tongued and grooved boarding	m2	6	408.68	2,452.08
39	38 x 38mm Branders	m	6	18.21	109.26
40	38 x 114mm Bearers	m	6	31.21	187.26
41	38 x 114mm Hangers	m	6	31.21	187.26
42	38 x 38mm Branders wrought on one surface	m	6	18.21	109.26
43	19mm Quadrant beads	m	6	15.60	93.60
44	10 x 20mm Beads	m	6	15.60	93.60
45	32mm Half round cover strips	m	6	19.50	117.00
46	10 x 32mm Cover strips	m	6	20.81	124.86
47	22 x 144mm Fascias and barge boards	m	6	45.51	273.06
	<u>Everite high density plain Pressed Nutec-cement</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
48	Eaves soffit covering of 4mm thick sheets (branders elsewhere) with H-type pressed steel jointing strips	m2	6	79.33	475.98
49	Eaves soffit covering of 4mm thick sheets with H-type pressed steel jointing strips including 38 x 38mm sawn softwood brandering along edges, along centre and at 400mm centres across sheets	m2	6	132.63	795.78
50	12 x 225mm fascias and barge boards including galvanised steel H-profile jointing strips	m	6	101.43	608.58
<u>FLOORS</u>					
<u>Sawn Softwood</u>					
51	38 x 76mm Battens wired to concrete (wire ties elsewhere)	m	6	29.91	179.46
52	50 x 150mm Floor joists in lengths not exceeding 2,4m	m	6	81.92	491.52
53	50 x 150mm Floor joists in lengths exceeding 2,4m and not exceeding 3,9m	m	6	106.51	639.06
54	50 x 150mm Floor joists in lengths exceeding 3,9m and not exceeding 6,6m	m	6	138.44	830.64
55	50 x 150mm Floor joists in lengths exceeding 6,6m	m	6	179.99	1,079.94
56	76 x 152mm Bearers in lengths exceeding 3,9m and not exceeding 6,6m	m	6	117.03	702.18
57	76 x 152mm Bearers in lengths exceeding 6,6m	m	6	152.13	912.78
<u>Wrought Softwood</u>					
58	Flooring of 22 x 96mm tounge and grooved boarding	m2	6	408.68	2,452.08
59	Raking cutting	m	6	16.13	96.78
60	Circular cutting	m	6	16.13	96.78
61	22 x 170mm Risers with rebated top edge let into and including groove in treads	m	6	76.46	458.76
62	22 x 300mm Treads with rounded front edge	m	6	135.00	810.00
<u>Wire ties</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
63	4mm Diameter galvanised wire tie 450mm girth bent double, embedded in concrete, bound around floor batten and twisted together including saw cuts	No	6	20.81	124.86
	<u>SKIRTINGS</u>				
	<u>Wrought Softwood</u>				
64	19 x 70mm skirting nailed	m	6	88.61	531.66
65	19 x 70mm skirting plugged	m	6	91.21	547.26
66	19 x 70mm skirting stepped over treads and risers nailed	m	6	99.70	598.20
67	19 x 70mm skirting stepped over treads and risers plugged	m	6	91.62	549.72
68	22 x 94mm skirting nailed	m	6	95.12	570.72
69	22 x 94mm skirting plugged	m	6	97.70	586.20
70	19mm quadrant bead nailed	m	6	21.84	131.04
71	32mm quadrant bead nailed	m	6	23.40	140.40
72	19mm Raking skirting 230mm high extreme with bottom edge stepped over treads and risers nailed	m	6	92.01	552.06
73	19mm Raking skirting 230mm high extreme with bottom edge stepped over treads and risers plugged	m	6	95.93	575.58
	<u>Wrought Meranti</u>				
74	19 x 70mm skirting nailed	m	6	124.21	745.26
75	19 x 70mm skirting plugged	m	6	126.81	760.86
76	19 x 70mm skirting stepped over treads and risers nailed	m	6	123.32	739.92
77	19 x 70mm skirting stepped over treads and risers plugged	m	6	128.51	771.06
78	22 x 94mm skirting nailed	m	6	127.22	763.32
79	22 x 94mm skirting plugged	m	6	129.81	778.86
80	19mm quadrant bead nailed	m	6	20.81	124.86
81	32mm quadrant bead nailed	m	6	35.12	210.72

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
82	19mm Raking skirting 230mm high extreme with bottom edge stepped over treads and risers nailed	m	6	96.23	577.38
83	19mm Raking skirting 230mm high extreme with bottom edge stepped over treads and risers plugged	m	6	120.13	720.78
	<u>HERITAGE SKIRTING AND ARCHITRAVES - "Making good, patching, straightening and sealing of existing skirting to Heritage Buildings" (Paintwork elsewhere)</u>				
84	70mm Skirting / Architraves / Dado Rails	m	6	61.34	368.04
85	115mm Skirting / Architraves / Dado Rails	m	6	76.67	460.02
86	150mm Skirting / Architraves / Dado Rails	m	6	95.85	575.10
87	170mm Skirting / Architraves / Dado Rails	m	6	119.81	718.86
88	225mm Skirting / Architraves / Dado Rails	m	6	149.75	898.50
	<u>DOORS, ETC</u>				
	<u>Wrought Meranti doors hung to steel frames</u>				
89	44mm Framed batten door 900 x 2032mm high of 44 x 100mm top rail and stiles, 44 x 100mm middle ledge and braces and 44 x 100mm bottom rail filled in with 70mm V- jointed one side boarding and covered on other side with 3,2mm plywood with veneer to match door let into and including rebates all round	No	6	1,436.89	8,621.34
90	44mm Framed batten door 813 x 2032mm high of 44 x 100mm top rail and stiles, 44 x 100mm middle ledge and braces and 44 x 100mm bottom rail filled in with 70mm V- jointed one side boarding and covered on other side with 3,2mm plywood with veneer to match door let into and including rebates all round	No	6	1,263.93	7,583.58
91	44mm Framed batten door 813 x 2032mm high of 44 x 100mm top rail and stiles, 44 x 150mm middle ledge and 44 x 225mm bottom ledge filled in with 22mm V-jointed one side boarding	No	6	1,436.89	8,621.34
92	44mm Framed batten door 813 x 2032mm high of 44 x 100mm top rail and stiles, 44 x 150mm middle ledge and 44 x 225mm bottom ledge filled in with 22mm V-jointed one side boarding and 3mm sheet metal fixed to other side	No	6	1,853.01	11,118.06

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
93	44mm Framed batten door 762 x 2032mm high of 44 x 100mm top rail and stiles, 44 x 100mm middle ledge and braces and 44 x 100mm bottom rail filled in with 70mm V- jointed one side boarding and covered on other side with 3,2mm plywood with veneer to match door let into and including rebates all round	No	6	1,263.93	7,583.58
94	44mm Framed batten double door 1616 x 2032mm high of 44 x 100mm top rail and stiles, 44 x 150mm middle ledge and 44 x 225mm bottom ledge filled in with 22mm V- jointed one side boarding	No	6	2,873.78	17,242.68
95	44mm Double leaf framed batten door 1510 x 2032mm high of 44 x 100mm top rail, stiles and rebated meeting stiles, 44 x 100mm middle ledge and braces and 44 x 100mm bottom rail filled in with 70mm V- jointed one side boarding and covered on other side with 3,2mm plywood with veneer to match door let into and including rebates all round	No	6	2,492.77	14,956.62
	<u>Swartland</u>				
96	44mm "Kayo 8" Panel door 813 x 2032mm high	No	6	1,690.46	10,142.76
97	44mm "Kayo 8" Panel rebated double door 1626 x 2032mm high	No	6	3,380.91	20,285.46
	<u>Semi-solid flush door with 3,2mm. hardboard covering on both sides hung to steel frames</u>				
98	40mm Door 900 x 2032mm high	No	6	1,050.00	6,300.00
99	40mm Door 813 x 2032mm high	No	6	900.33	5,401.98
100	40mm Door 762 x 2032mm high	No	6	750.22	4,501.32
101	40mm Double leaf door 1511 x 2032mm high with rebated meeting styles	No	6	1,250.00	7,500.00
102	40mm Double leaf door 1613 x 2032mm high with rebated meeting styles	No	6	2,050.00	12,300.00
103	40mm Double leaf door 1359 x 2032mm high with rebated meeting styles	No	6	1,350.00	8,100.00
104	40mm Double leaf door 1616 x 2032mm high with flush meeting styles	No	6	2,050.00	12,300.00
105	40mm Double leaf door 1511 x 2032mm high with flush meeting styles	No	6	1,250.00	7,500.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
106	40mm Double leaf door 1359 x 2032mm high with flush meeting styles	No	6	1,350.00	8,100.00
107	Extra for 300 x 450mm opening including natural anodised aluminium louvre unit	No	6	709.99	4,259.94
	<u>Semi-solid flush door with sapele veneer on both sides hung to steel frames</u>				
108	40mm Door 900 x 2032mm high	No	6	1,050.00	6,300.00
109	40mm Door 813 x 2032mm high	No	6	900.33	5,401.98
110	40mm Door 762 x 2032mm high	No	6	750.22	4,501.32
111	40mm Double leaf door 1511 x 2032mm high with rebated meeting styles	No	6	1,250.00	7,500.00
112	40mm Double leaf door 1613 x 2032mm high with rebated meeting styles	No	6	2,050.00	12,300.00
113	40mm Double leaf door 1359 x 2032mm high with rebated meeting styles	No	6	1,350.00	8,100.00
114	40mm Double leaf door 1616 x 2032mm high with flush meeting styles	No	6	2,050.00	12,300.00
115	40mm Double leaf door 1511 x 2032mm high with flush meeting styles	No	6	1,250.00	7,500.00
116	40mm Double leaf door 1359 x 2032mm high with flush meeting styles	No	6	1,350.00	8,100.00
117	Extra for 300 x 450mm opening including natural anodised aluminium louvre unit	No	6	709.99	4,259.94
	<u>Solid flush door with 3,2mm hardboard covering on both sides hung to steel frames</u>				
118	40mm Door 900 x 2032mm high	No	6	1,050.00	6,300.00
119	40mm Door 813 x 2032mm high	No	6	900.33	5,401.98
120	40mm Door 762 x 2032mm high	No	6	750.22	4,501.32

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
121	40mm Double leaf door 1511 x 2032mm high with rebated meeting styles	No	6	1,250.00	7,500.00
122	40mm Double leaf door 1613 x 2032mm high with rebated meeting styles	No	6	2,050.00	12,300.00
123	40mm Double leaf door 1359 x 2032mm high with rebated meeting styles	No	6	1,350.00	8,100.00
124	40mm Double leaf door 1616 x 2032mm high with flush meeting styles	No	6	2,050.00	12,300.00
125	40mm Double leaf door 1511 x 2032mm high with flush meeting styles	No	6	1,250.00	7,500.00
126	40mm Double leaf door 1359 x 2032mm high with flush meeting styles	No	6	1,350.00	8,100.00
127	Extra for 300 x 450mm opening including natural anodised aluminium louvre unit	No	6	709.99	4,259.94
	<u>Solid flush door with sapele veneer on both sides hung to steel frames</u>				
128	40mm Door 900 x 2032mm high	No	6	973.71	5,842.26
129	40mm Door 813 x 2032mm high	No	6	865.51	5,193.06
130	40mm Door 762 x 2032mm high	No	6	865.51	5,193.06
131	40mm Double leaf door 1511 x 2032mm high with rebated meeting styles	No	6	1,658.33	9,949.98
132	40mm Double leaf door 1613 x 2032mm high with rebated meeting styles	No	6	1,658.33	9,949.98
133	40mm Double leaf door 1359 x 2032mm high with rebated meeting styles	No	6	1,600.87	9,605.22
134	40mm Double leaf door 1616 x 2032mm high with flush meeting styles	No	6	1,658.33	9,949.98
135	40mm Double leaf door 1511 x 2032mm high with flush meeting styles	No	6	1,658.33	9,949.98
136	40mm Double leaf door 1359 x 2032mm high with flush meeting styles	No	6	1,600.87	9,605.22

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
137	Extra for 300 x 450mm opening including natural anodised aluminium louvre unit	No	6	709.99	4,259.94
	<u>JOINERY SUNDRIES</u>				
	<u>Wrought Meranti or Softwood</u>				
138	Slatted shelving, seats, etc of 22 x 96mm slats at 35mm centres	m2	6	408.68	2,452.08
139	Install 813 x 2032mm timber door including furniture (door handle)	No	6	273.08	1,638.48
140	Install door furniture (door handle)	No	6	125.48	752.88
	<u>Making good of existing doors (Patching and repairing where necessary, paintwork elsewhere)</u>				
	<u>Wrought Meranti doors hung to steel frames</u>				
141	44mm Framed batten door 900 x 2032mm high of 44 x 100mm top rail and stiles, 44 x 100mm middle ledge and braces and 44 x 100mm bottom rail filled in with 70mm V- jointed one side boarding and covered on other side with 3,2mm plywood with veneer to match door let into and including rebates all round	No	6	448.62	2,691.72
142	44mm Framed batten door 813 x 2032mm high of 44 x 100mm top rail and stiles, 44 x 100mm middle ledge and braces and 44 x 100mm bottom rail filled in with 70mm V- jointed one side boarding and covered on other side with 3,2mm plywood with veneer to match door let into and including rebates all round	No	6	448.62	2,691.72
143	44mm Framed batten door 813 x 2032mm high of 44 x 100mm top rail and stiles, 44 x 150mm middle ledge and 44 x 225mm bottom ledge filled in with 22mm V-jointed one side boarding	No	6	448.62	2,691.72
144	44mm Framed batten door 813 x 2032mm high of 44 x 100mm top rail and stiles, 44 x 150mm middle ledge and 44 x 225mm bottom ledge filled in with 22mm V-jointed one side boarding and 3mm sheet metal fixed to other side	No	6	448.62	2,691.72
145	44mm Framed batten door 762 x 2032mm high of 44 x 100mm top rail and stiles, 44 x 100mm middle ledge and braces and 44 x 100mm bottom rail filled in with 70mm V- jointed one side boarding and covered on other side with 3,2mm plywood with veneer to match door let into and including rebates all round	No	6	448.62	2,691.72

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
146	44mm Framed batten double door 1616 x 2032mm high of 44 x 100mm top rail and stiles, 44 x 150mm middle ledge and 44 x 225mm bottom ledge filled in with 22mm V- jointed one side boarding	No	6	897.24	5,383.44
147	44mm Double leaf framed batten door 1510 x 2032mm high of 44 x 100mm top rail, stiles and rebated meeting stiles, 44 x 100mm middle ledge and braces and 44 x 100mm bottom rail filled in with 70mm V- jointed one side boarding and covered on other side with 3,2mm plywood with veneer to match door let into and including rebates all round	No	6	897.24	5,383.44
	<u>ONLY IN HERITAGE BUILDINGS "Making good of existing doors (Patching and repairing where necessary, paintwork elsewhere)"</u>				
	<u>Wooden Heritage doors hung to wooden frames</u>				
148	762 x 2032mm high Single door	No	6	1,121.55	6,729.30
149	813 x 2032mm high Single door	No	6	1,121.55	6,729.30
150	900 x 2032mm high Single door	No	6	1,121.55	6,729.30
151	1200 x 2032mm high Single door	No	6	1,166.41	6,998.46
152	1510 x 2032mm high Double door	No	6	1,794.47	10,766.82
153	1616 x 2032mm high Double door	No	6	2,243.11	13,458.66
154	1810 x 2032mm high Double door	No	6	2,512.28	15,073.68
	<u>Swartland</u>				
155	44mm "Kayo 8" Panel door 813 x 2032mm high	No	6	1,448.62	8,691.72
	<u>Making good of Semi-solid flush door with 3,2mm hardboard covering on both sides hung to steel frames</u>				
156	40mm Door 900 x 2032mm high	No	6	245.76	1,474.54
157	40mm Door 813 x 2032mm high	No	6	245.76	1,474.54
158	40mm Door 762 x 2032mm high	No	6	245.76	1,474.54
159	40mm Double leaf door 1511 x 2032mm high with rebated meeting styles	No	6	491.54	2,949.24

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
160	40mm Double leaf door 1613 x 2032mm high with rebated meeting styles	No	6	491.54	2,949.24
161	40mm Double leaf door 1359 x 2032mm high with rebated meeting styles	No	6	491.54	2,949.24
162	40mm Double leaf door 1616 x 2032mm high with flush meeting styles	No	6	491.54	2,949.24
163	40mm Double leaf door 1511 x 2032mm high with flush meeting styles	No	6	491.54	2,949.24
164	40mm Double leaf door 1359 x 2032mm high with flush meeting styles	No	6	491.54	2,949.24
	<u>Making good of Semi-solid flush door with sapele veneer on both sides hung to steel frames</u>				
165	40mm Door 900 x 2032mm high	No	6	245.76	1,474.54
			6		0.00
166	40mm Door 813 x 2032mm high	No	6	245.76	1,474.54
167	40mm Door 762 x 2032mm high	No	6	245.76	1,474.54
168	40mm Double leaf door 1511 x 2032mm high with rebated meeting styles	No	6	491.54	2,949.24
169	40mm Double leaf door 1613 x 2032mm high with rebated meeting styles	No	6	491.54	2,949.24
170	40mm Double leaf door 1359 x 2032mm high with rebated meeting styles	No	6	491.54	2,949.24
171	40mm Double leaf door 1616 x 2032mm high with flush meeting styles	No	6	491.54	2,949.24
172	40mm Double leaf door 1511 x 2032mm high with flush meeting styles	No	6	491.54	2,949.24
173	40mm Double leaf door 1359 x 2032mm high with flush meeting styles	No	6	491.54	2,949.24
	<u>Making good of Solid flush door with 3,2mm hardboard covering on both sides hung to steel frames</u>				
174	40mm Door 900 x 2032mm high	No	6	245.76	1,474.54

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
175	40mm Door 813 x 2032mm high	No	6	245.76	1,474.54
176	40mm Door 762 x 2032mm high	No	6	245.76	1,474.54
177	40mm Double leaf door 1511 x 2032mm high with rebated meeting styles	No	6	491.54	2,949.24
178	40mm Double leaf door 1613 x 2032mm high with rebated meeting styles	No	6	491.54	2,949.24
179	40mm Double leaf door 1359 x 2032mm high with rebated meeting styles	No	6	491.54	2,949.24
180	40mm Double leaf door 1616 x 2032mm high with flush meeting styles	No	6	491.54	2,949.24
181	40mm Double leaf door 1511 x 2032mm high with flush meeting styles	No	6	491.54	2,949.24
182	40mm Double leaf door 1359 x 2032mm high with flush meeting styles	No	6	491.54	2,949.24
	<u>Making good of Solid flush door with sapele veneer on both sides hung to steel frames</u>				
183	40mm Door 900 x 2032mm high	No	6	245.76	1,474.54
184	40mm Door 813 x 2032mm high	No	6	245.76	1,474.54
185	40mm Door 762 x 2032mm high	No	6	245.76	1,474.54
186	40mm Double leaf door 1511 x 2032mm high with rebated meeting styles	No	6	491.54	2,949.24
187	40mm Double leaf door 1613 x 2032mm high with rebated meeting styles	No	6	491.54	2,949.24
188	40mm Double leaf door 1359 x 2032mm high with rebated meeting styles	No	6	491.54	2,949.24
189	40mm Double leaf door 1616 x 2032mm high with flush meeting styles	No	6	491.54	2,949.24
190	40mm Double leaf door 1511 x 2032mm high with flush meeting styles	No	6	491.54	2,949.24

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
191	40mm Double leaf door 1359 x 2032mm high with flush meeting styles	No	6	491.54	2,949.24
	<u>FITTINGS</u>				
	<u>General</u>				
	The following cupboards fittings have been measured as complete units i.e. the components of the units have not been separately measured. The descriptions, therefore, of such units shall be deemed to include all components, assembling, housing, notching, gluing, blocking, planting on and screwing with countersunk screws, edge strips, decorative plastic finish, glass, ironmongery, metalwork, paint or varnish finishes, etc				
	<u>Kitchen cupboards etc with approved hinges, handles and telescopic drawer sliders</u>				
192	Wall cupboard Type W300 - 300 x 300 x 720mm high with top, sides, bottom, division, shelf, back and single hinged door	No	6	736.78	4,420.67
193	Wall cupboard Type W450 - 450 x 300 x 720mm high with top, sides, bottom, division, shelf, back and single hinged door	No	6	901.67	5,410.02
194	Wall cupboard Type W600 - 600 x 300 x 720mm high with top, sides, bottom, division, shelf, back and single hinged door	No	6	1,071.24	6,427.43
195	Wall cupboard Type W750 - 750 x 300 x 720mm high with top, sides, bottom, division, shelf, back and double hinged door	No	6	1,227.98	7,367.89
196	Wall cupboard Type W900 - 900 x 300 x 720mm high with top, sides, bottom, division, shelf, back and double hinged doors	No	6	1,494.18	8,965.07
197	Wall cupboard Type W1200 - 1200 x 300 x 720mm high with top, sides, bottom, division, shelf, back and double hinged doors	No	6	1,921.81	11,530.85
198	Wall cupboard Type WCU600 (L shaped) - 600 x 300 x 720mm high with top, sides, bottom, division, shelf, back and double hinged doors	No	6	1,403.15	8,418.90
199	Wall cupboard Type WC300 (End display) - 300 x 300 x 720mm high with top, sides, bottom, division, shelf, back and double hinged doors	No	6	736.78	4,420.67
200	Floor cupboard Type F300 - (without top) - 300 x 550 x 880mm high with sides, bottom, division, shelf, and single hinged door	No	6	1,094.02	6,564.10

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
201	Floor cupboard Type F450 - (without top) - 450 x 550 x 880mm high with sides, bottom, division, shelf, and single hinged door	No	6	1,310.40	7,862.40
202	Floor cupboard Type F600 - (without top) - 600 x 550 x 880mm high with sides, bottom, division, shelf, and single hinged door	No	6	1,543.99	9,263.94
203	Floor cupboard Type F750 - (without top) - 750 x 550 x 880mm high with sides, bottom, division, shelf, and double hinged doors	No	6	1,861.71	11,170.24
204	Floor cupboard Type F900 - (without top) - 900 x 550 x 880mm high with sides, bottom, division, shelf, and double hinged doors	No	6	2,071.23	12,427.38
205	Floor cupboard Type F1200 - (without top) - 1200 x 550 x 880mm high with sides, bottom, division, shelf, and double hinged doors	No	6	2,526.36	15,158.14
206	Floor cupboard Type F450/1 - (without top) - 450 x 550 x 880mm high with sides, bottom, division, shelf, and single hinged door, dividing framework and 1 drawer	No	6	1,440.94	8,645.62
207	Floor cupboard Type F450/4 - (without top) - 450 x 550 x 880mm high with sides, bottom, dividing framework and 4 drawers	No	6	1,777.55	10,665.31
208	Floor cupboard Type F600/1 - (without top) - 600 x 550 x 880mm high with sides, bottom, division, shelf, and single hinged door, dividing framework and 1 drawer	No	6	1,671.07	10,026.41
209	Floor cupboard Type F600/4 - (without top) - 600 x 550 x 880mm high with sides, bottom, dividing framework and 4 drawers	No	6	2,425.04	14,550.23
210	Floor cupboard Type FCU900 (L shaped) - 900 x 300 x 880mm high with sides, bottom, division, shelf, back and double hinged doors	No	6	2,979.77	17,878.64
211	Floor cupboard Type BC450 - 450 x 300 x 2095mm high with top, sides, bottom, division, 2 shelves, back and single hinged door	No	6	2,864.69	17,188.16
212	Floor cupboard Type GC600 - 600 x 300 x 2095mm high with top, sides, bottom, division, 4 shelves, back and single hinged door	No	6	3,628.95	21,773.72
213	Sink cupboard Type S900 - 900 x 550 x 880mm high with sides, bottom, division, shelf, back and double hinged doors (sink elsewhere)	No	6	2,071.23	12,427.38

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
214	Sink cupboard Type S1200 - 1200 x 550 x 880mm high with sides, bottom, division, shelf, back and double hinged doors (sink elsewhere)	No	6	2,526.36	15,158.14
215	Sink cupboard Type S1500 (double bowl) - 1500 x 550 x 880mm high with sides, bottom, division, shelf, back and double hinged doors (sink elsewhere)	No	6	3,158.39	18,950.32
	<u>32mm thick post formed (on one side) top with 0,6mm Decon Laminated in Artic Granite or similar</u>				
216	600mm wide	m	6	282.15	1,692.90
217	900mm wide	m	6	395.01	2,370.06
218	Extra over for edge strip	m	6	11.05	66.30
219	Extra over for splay cutting	m	6	7.36	44.16
	<u>Laminated Pine</u>				
220	46 x 231mm Beam	m	6	139.09	834.54
221	46 x 297mm Beam	m	6	178.83	1,072.98
222	70 x 147mm Beam	m	6	134.69	808.14
223	70 x 231mm Beam	m	6	211.66	1,269.96
224	70 x 297mm Beam	m	6	272.14	1,632.84
225	70 x 363mm Beam	m	6	332.61	1,995.66
	<u>Service Counters</u>				
226	Plumtree melamine, Alpine finish, Size 750 x 1000mm high, in high impact PVC edged all round 32mm worktop including 2 x 2door lockable cupboards with two open spaces for chairs and cable outlets, 3 x open shelves, 2 x rounded corner unit with min 3 x open front display shelves	No	6	3,450.10	20,700.60
227	Four Tier open bag storage unit 450 x 1832 x 450mm deep (4 x pigeon holes per unit)	No	6	2,139.69	12,838.14
228	Library shelving unit 900 x 1200 x 300mm deep with adjustable shelves, 22mm "Plumtree" melamine	No	6	2,401.36	14,408.16

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
229	Adult - Computer/study bay 800 x 750 x 300mm deep with enclosed sides 800mm high with cable outlets	No	6	2,280.46	13,682.76
230	Water treated solid wood platform of 100 x 50mm continuous top and bottom rails, 100 x 100mm intermediate post at approximately 1200mm centres, 100 x 100mm cross-bracing, 100 x 30mm flat section floor slats, all bolted together with 100 x 10mm diameter stainless steel bolts	m2	6	3,643.44	21,860.64
	<u>CUBICLES AND SHELVES</u>				
	<u>Ekurhuleni cubicles</u>				
231	Manufacture, supply and install: Interview Cubicles with 32mm thick Melamine wood grain "Vancouver Maple" or other colour board with 32 mm work-tops, vanity, triple drawer units and edged all around in black hi-impact edging to suit. All new counters to include for plant-on black squares detail, counter holes for cables, two down lights, aluminium skirting as per drawing. (2,7m high x 1,4m wide).	No	6	38,137.95	228,827.70
232	Manufacture, supply and install new 2400 wide reception counter in 16mm thick Melamine wood grain "Vancouver Maple" or other colour melamine base unit, 32 mm work surface edged with 3 mm hi-impact polyurethane edging and includes for a single 3 drawer pedestal unit for storage, Maple vanity front and 10 mm tempered glass upper split level shelf top section on stainless steel posts.	No	6	18,401.20	110,407.20
233	Manufacture, supply and install: 32mm thick Melamine wood grain door 813 x 2032mm high for staff entrance plus 32mm panel around door 2700 high x 2000mm wide. Complete with hinges.	No	6	3,312.21	19,873.26
234	Manufacture, supply and install: 16mm thick Melamine wood grain tender box 500x500x12000mm with 32mm similar top. Complete with hinges, lock, pad lock with 450mm COJ Brushed Aluminium logo and 100x450 "Name logo's"	No	6	3,664.92	21,989.52
	<u>Libraries shelves</u>				
235	Elephant folio shelving 2000 x 900 x 650d fixed to the floor, 120mm spacing between shelves, in Mahogany. 2 - A.1.1.f.y shelving units 1800w x 1800h x 300d Addendum B Mahogany is adapted to manufacture these fixed Elephant folio shelving units.	No	6	8,082.82	48,496.92

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
236	Catalogue card storage boxes unit 1300 x 1870 x 370d fixed to the floor, 103mm spacing between shelves. 1 - A.1.1.f.y shelving unit 1800w x 1800h x 300d Addendum B Mahogany is adapted to manufacture this fixed storage unit.	No	6	8,082.82	48,496.92
237	10 - Drawer AO size map/plan filing cabinets, fixed to the floor, each unit includes the following: 1x 4 drawer metal unit, 1420w x 530h x 960d fixed on top of 1 x 6 drawer metal unit, 1420w x 740h x 960d and 1x universal metal stand, all of the above clad with Beech wood melamine, to match the existing furniture, total height per unit: 1520mm.	No	6	39,179.58	235,077.48
238	Single wall units 954w x 2000h x 466d, fixed to the floor fitted with 12x fixed shelves each, with 138mm(h) gaps between shelves, in Mahogany.13 - B.1.1.f.y Shelving units 1800 x 1500 x 300 Addendum B is adapted to manufacture these multi-shelf fixed units. (Equal angle colour matching aluminium is used to fix the shelving units to the floor.)	No	6	6,749.70	40,498.20
239	Single wall units 900 x 2000 x 300 fixed to the floor fitted with 4x adjustable shelves each, in Beechwood. 6 - A.1.1.c.y - Shelving units 900 x 1800 x 300 Addendum B Beechwood, is adapted to manufacture these fixed shelving units. (6x shelving units fixed behind the counter) (Equal angle colour matching aluminium is used to fix the shelving units to the floor.)	No	6	4,504.34	27,026.04
240	Counter 1500w x 750h x 500d single level, granite top 1500 x 500mm, Steel construction design to match the existing counters, 10mm clear polished glass panelling fitted with the vinyl logo as per existing units single level Rustenburg (colour) granite 1 - 1500 x 500 x 30mm, counter fixed to the floor.	No	6	12,067.62	72,405.72
241	Double island units 1800 x 1500 x 660 fixed to the floor fitted with 8x lockable glass doors each, in Mahogany. 10 - B.1.2.c.y Shelving units 2700 x 1400 x 600. Addendum B Mahogany, is adapted to manufacture these fixed lockable shelving units.	No	6	16,344.84	98,069.04
242	Double island units 900 x 1500 x 660 fixed to the floor fitted with 4x lockable glass doors each, in Mahogany. 10 - B.1.1.j.y Shelving units 2700 x 1500 x 300 Addendum B Mahogany, is adapted to manufacture these fixed lockable shelving units. (10 Rows of 2700mm(w) lockable shelving units)(Equal angle colour matching aluminium is used to the shelving units to the floor)fix	No	6	9,595.14	57,570.84

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
243	Single wall units 450w x 2500h x 450d, fixed to the floor fitted with 10x fixed shelves each, with 450mm(h) gaps between shelves, in Melamine wood colour to match existing furniture. with 2mm PVC edging. (Equal angle colour matching aluminium is used to fix the shelving units to the floor.)	No	6	5,604.91	33,629.46
244	Drawing pigeon hole 450w x 1100h x 800b, fixed to the floor in 16mm Melamine wood colour to match existing furniture	No	6	1,751.81	10,510.84
<u>ROLL-UP, RETRACTABLE SCREENS AND BLINDS</u>					
<u>Windovert or equivalent blinds</u>					
Supply and install complete with colour co-ordinated ladder lace, cord, head and bottom rails, tilters, cord locks and installation brackets					
245	25mm Plain slatted venetian wooden window	m2	6	599.88	3,599.28
246	25mm Perforated venetian wooden window blinds	m2	6	843.59	5,061.54
247	50mm Plaswood venetian wooden window screen	m2	6	1,723.58	10,341.48
248	2300 x 1600mm high double leaf hinged bamboo screen with 100 x 35mm meranti frame	No	6	3,312.21	19,873.26
249	63mm blade width vertical fabric venetian blinds	m2	6	447.16	2,682.96
250	90mm blade width vertical fabric venetian blinds	m2	6	514.23	3,085.38
251	127mm blade width vertical fabric venetian blinds	m2	6	581.29	3,487.74
252	16mm blade width aluminium venetian blinds	m2	6	509.25	3,055.50
253	25mm blade width aluminium venetian blinds	m2	6	585.64	3,513.84
254	50mm blade width aluminium venetian blinds	m2	6	662.02	3,972.12
<u>Fabric Screens</u>					
255	Fabric Duke/Black Suede regis lined-in workwear 100% cotton with nine racer single tracks c/w cording sets	m2	6	706.88	4,241.28
256	Fabric York Velvet regis lined-in workwear 100% cotton with nine racer single tracks c/w cording sets	m2	6	1,257.32	7,543.92
<u>Stage Screens</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
257	Fabric Duke/Black Suede one valance plus two stage screws ,lined-in workwear 100% cotton glorius track with winch	m2	6	732.89	4,397.34
258	Fabric York Velvet one valance plus two stage screws ,lined-in workwear 100% cotton glorius track with winch	m2	6	1,071.27	6,427.62
	<u>Sundries</u>				
	<u>Making good wooden floors</u>				
259	Cleaning, sanding and sealing ordinary floors	m2	6	226.95	1,361.70
260	Replacing parquet floors	m2	6	306.69	1,840.14
261	Cleaning, sanding and sealing parquet floors	m2	6	1,073.41	6,440.46
					2,180,921.26
	SUB-TOTAL (Carried To Summary)				31,621,432.87
	<u>BILL NO. 9</u>				
	<u>CEILINGS, PARTITIONS AND ACCESS FLOORING</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	<u>Descriptions</u>				
	Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins or shot pinned to brickwork or concrete Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres, and where described as "bolted" the bolts have been given elsewhere				
	<u>CEILINGS ETC</u>				
	<u>Isotherm insulation or equally approved</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	50mm insulation closely fitted and laid on top of branderling between roof trusses	m2	17	67.70	1,150.90
	<u>NAILED UP CEILINGS</u>				
	<u>6,4mm "Rhino" gypsum plasterboard or equally approved with 32mm wrought softwood half round cover strip over joints</u>				
2	Ceilings including 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	164.49	2,796.40
3	Sloping ceilings including 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	171.64	2,917.95
4	Vertical ceilings including 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	171.64	2,917.95
5	Horizontal bulkhead including 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	193.09	3,282.60
6	Sloping bulkhead including 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	200.24	3,404.15
7	Vertical bulkhead including 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	200.24	3,404.15
8	Circular cutting	m	17	15.20	258.40
9	Opening for sprinkler head	No	17	17.80	302.60
10	Extra over ceiling for opening for 75mm diameter downlighter	No	17	17.80	302.60
11	Extra over ceiling for opening for 180mm diameter downlighter	No	17	20.40	346.80
12	Extra over ceiling for opening for 300 x 1200mm light fitting	No	17	111.21	1,890.57
13	Extra over ceiling for opening for 600 x 1200mm light fitting	No	17	111.62	1,897.54
14	Extra over ceiling for 600 x 600mm opening for ventilation/air conditioning diffuser	No	17	92.01	1,564.17
15	Extra over ceiling for 600 x 600mm trap door of 38 x 50mm wrought softwood rebated framing with one 38 x 38mm sawn softwood cross brander covered with ceiling board and fitted flush in opening on 20 x 20mm pressed steel angle	No	17	403.12	6,853.04

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
16	Ceilings excluding 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	110.53	1,879.01
17	Sloping ceilings excluding 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	117.03	1,989.51
18	Vertical ceilings excluding 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	121.57	2,066.69
	<u>6,4mm "Rhino" gypsum plasterboard or equally approved with H-type pressed metal jointing strips</u>				
19	Ceilings including 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	164.49	2,796.40
20	Sloping ceilings including 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	171.64	2,917.95
21	Vertical ceilings including 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	171.64	2,917.95
22	Horizontal bulkhead including 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	193.09	3,282.60
23	Sloping bulkhead including 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	200.24	3,404.15
24	Vertical bulkhead including 38 x 50mm sawn softwood branderling at 400mm centres	m2	17	200.24	3,404.15
25	Circular cutting	m	17	15.20	258.40
26	Opening for sprinkler head	No	17	17.80	302.60
27	Extra over ceiling for opening for 75mm diameter downlighter	No	17	17.80	302.60
28	Extra over ceiling for opening for 180mm diameter downlighter	No	17	20.40	346.80
29	Extra over ceiling for opening for 300 x 1200mm light fitting	No	17	111.21	1,890.57
30	Extra over ceiling for opening for 600 x 1200mm light fitting	No	17	111.62	1,897.54
31	Extra over ceiling for 600 x 600mm opening for ventilation/air conditioning diffuser	No	17	92.01	1,564.17

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
32	Extra over ceiling for 600 x 600mm trap door of 38 x 50mm wrought softwood rebated framing with one 38 x 38mm sawn softwood cross brander covered with ceiling board and fitted flush in opening on 20 x 20mm pressed steel angle	No	17	403.12	6,853.04
33	Ceilings excluding 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	110.53	1,879.01
34	Sloping ceilings excluding 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	117.03	1,989.51
35	Vertical ceilings excluding 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	121.57	2,066.69
	<u>6,4mm "Rhino" gypsum plasterboard or equally approved with 63mm wide strips of mesh scrim fixed over joints and finished with gypsum skim plaster trowelled and sanded to a smooth polished surface</u>				
36	Ceilings including 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	201.55	3,426.35
37	Sloping ceilings including 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	208.06	3,537.02
38	Vertical ceilings including 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	208.06	3,537.02
39	Horizontal bulkhead including 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	214.57	3,647.69
40	Sloping bulkhead including 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	214.57	3,647.69
41	Vertical bulkhead including 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	214.57	3,647.69
42	Circular cutting	m	17	15.20	258.40
43	Opening for sprinkler head	No	17	17.80	302.60
44	Extra over ceiling for opening for 75mm diameter downlighter	No	17	17.80	302.60
45	Extra over ceiling for opening for 180mm diameter downlighter	No	17	20.40	346.80
46	Extra over ceiling for opening for 300 x 1200mm light fitting	No	17	111.21	1,890.57

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
47	Extra over ceiling for opening for 600 x 1200mm light fitting	No	17	111.62	1,897.54
48	Extra over ceiling for 600 x 600mm opening for ventilation/air conditioning diffuser	No	17	92.01	1,564.17
49	Extra over ceiling for 600 x 600mm trap door of 38 x 50mm wrought softwood rebated framing with one 38 x 38mm sawn softwood cross brander covered with ceiling board and fitted flush in opening on 20 x 20mm pressed steel angle	No	17	403.12	6,853.04
50	Ceilings excluding 38 x 50mm sawn softwood brander at 400mm centres	m2	17	110.53	1,879.01
51	Sloping ceilings excluding 38 x 50mm sawn softwood brander at 400mm centres	m2	17	117.03	1,989.51
52	Vertical ceilings excluding 38 x 50mm sawn softwood brander at 400mm centres	m2	17	121.57	2,066.69
	<u>4mm "Everite Cladit" high density plain Pressed Nutec-cement boards or equally approved with 32 x 10mm wrought softwood cover strip over joints</u>				
53	Ceilings including 38 x 50mm sawn softwood brander at 400mm centres	m2	17	149.54	2,542.18
54	Sloping ceilings including 38 x 50mm sawn softwood brander at 400mm centres	m2	17	156.04	2,652.68
55	Vertical ceilings including 38 x 50mm sawn softwood brander at 400mm centres	m2	17	156.04	2,652.68
56	Horizontal bulkhead including 38 x 50mm sawn softwood brander at 400mm centres	m2	17	175.54	2,984.18
57	Sloping bulkhead including 38 x 50mm sawn softwood brander at 400mm centres	m2	17	182.04	3,094.68
58	Vertical bulkhead including 38 x 50mm sawn softwood brander at 400mm centres	m2	17	182.04	3,094.68
59	Circular cutting	m	17	15.20	258.40
60	Opening for sprinkler head	No	17	17.80	302.60
61	Extra over ceiling for opening for 75mm diameter downlighter	No	17	17.80	302.60

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
62	Extra over ceiling for opening for 180mm diameter downlighter	No	17	20.40	346.80
63	Extra over ceiling for opening for 300 x 1200mm light fitting	No	17	111.21	1,890.57
64	Extra over ceiling for opening for 600 x 1200mm light fitting	No	17	111.62	1,897.54
65	Extra over ceiling for 600 x 600mm opening for ventilation/air conditioning diffuser	No	17	92.01	1,564.17
66	Extra over ceiling for 600 x 600mm trap door of 38 x 50mm wrought softwood rebated framing with one 38 x 38mm sawn softwood cross brander covered with ceiling board and fitted flush in opening on 20 x 20mm pressed steel angle	No	17	403.12	6,853.04
67	Ceilings excluding 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	110.53	1,879.01
68	Sloping ceilings excluding 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	117.03	1,989.51
69	Vertical ceilings excluding 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	121.57	2,066.69
	<u>4mm "Everite Cladit" high density plain Pressed Nutec-cement boards or equally approved with H-type pressed steel jointing strips</u>				
70	Ceilings including 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	149.54	2,542.18
71	Sloping ceilings including 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	156.04	2,652.68
72	Vertical ceilings including 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	156.04	2,652.68
73	Horizontal bulkhead including 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	175.54	2,984.18
74	Sloping bulkhead including 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	182.04	3,094.68
75	Vertical bulkhead including 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	182.04	3,094.68

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
76	Circular cutting	m	17	15.20	258.40
77	Opening for sprinkler head	No	17	17.80	302.60
78	Extra over ceiling for opening for 75mm diameter downlighter	No	17	17.80	302.60
79	Extra over ceiling for opening for 180mm diameter downlighter	No	17	20.40	346.80
80	Extra over ceiling for opening for 300 x 1200mm light fitting	No	17	111.21	1,890.57
81	Extra over ceiling for opening for 600 x 1200mm light fitting	No	17	111.62	1,897.54
82	Extra over ceiling for 600 x 600mm opening for ventilation/air conditioning diffuser	No	17	92.01	1,564.17
83	Extra over ceiling for 600 x 600mm trap door of 38 x 50mm wrought softwood rebated framing with one 38 x 38mm sawn softwood cross brander covered with ceiling board and fitted flush in opening on 20 x 20mm pressed steel angle	No	17	403.12	6,853.04
84	Ceilings excluding 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	110.53	1,879.01
85	Sloping ceilings excluding 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	117.03	1,989.51
86	Vertical ceilings excluding 38 x 50mm sawn softwood brandering at 400mm centres	m2	17	121.57	2,066.69
<u>Book Detection System Partition (Oak Melamine)</u>					
87	Partition 1200 x 1800mm with wood	m2	17	327.70	5,570.83
88	Partition 1200 x 1800mm with glazing (Glazing measured else where)	m2	17	382.31	6,499.30
<u>CORNICES, MOULDINGS AND ROSES</u>					
<u>Rhino gypsum plasterboard cornice</u>					
89	75mm standard coved cornice	m	17	54.70	929.90
90	125mm standard coved cornice	m	17	61.62	1,047.54
<u>Rhino gypsum plasterboard decorative mouldings</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
91	75mm standard coved cornice	m	17	57.07	970.19
92	125mm standard coved cornice	m	17	62.41	1,060.97
93	155mm standard coved cornice	m	17	74.90	1,273.30
94	225mm standard coved cornice	m	17	89.89	1,528.13
	<u>Polystyrene, Expanded Polystyrene (EPS) and Polyurethane decorative mouldings</u>				
95	75mm standard coved cornice	m	17	29.50	501.50
96	125mm standard coved cornice	m	17	35.12	597.04
97	155mm standard coved cornice	m	17	42.12	716.04
98	225mm standard coved cornice	m	17	50.56	859.52
	<u>Wrought softwood</u>				
99	20 x 65mm cornice	m	17	32.52	552.84
	<u>HERITAGE CORNICE AND MOULDINGS - "Making good, patching, straightening and sealing of existing Cornice, Mouldings and soffits of verges to Heritage Buildings" (Paintwork elsewhere)</u>				
100	75mm Heritage Moulding cornice	m	17	27.60	469.20
101	125mm Heritage Moulding cornice	m	17	44.16	750.72
102	155mm Heritage Moulding cornice	m	17	56.32	957.44
103	225mm Heritage Moulding cornice	m	17	82.81	1,407.77
104	Not exceeding 225mm girth Moulding cornice External with special bonding liquid	m	17	134.95	2,294.15
105	Exceeding 225mm and not exceeding 600mm girth Moulding cornice External with special bonding liquid	m	17	175.43	2,982.31
106	Restoring soffits of verges including mouldings	m2	17	390.72	6,642.24
	<u>SUSPENDED CEILINGS</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	Electrical light fittings, diffusers, panels, etc generally are "lay in" units of the same dimensions as the suspension grid described and allowance must be made accordingly for their support inclusive of any flexibility in setting out that may be required (ceiling panels have not been deducted and pricing is to take cognisance thereof)				
	<u>BPB Gypsum DonnCeil Gyprex White vinyl finished gypsum ceiling tiles or equally approved size 1200 x 600mm x 12,5mm thick laid on and including SQ/T38 galvanised main tees, cross tees, hold-down clips, wedges, etc., all suspended with galvanised hangers at hanger centres not exceeding 1200mm</u>				
107	Ceiling suspended not exceeding 1m below concrete soffits.	m2	17	276.97	4,708.49
			17		0.00
108	Ceiling suspended exceeding 1m and not exceeding 2m below concrete soffits	m2	17	280.88	4,774.96
109	Sloping ceiling suspended not exceeding 1m below concrete soffits	m2	17	276.97	4,708.49
110	Sloping ceiling suspended exceeding 1m and not exceeding 2m below concrete soffits	m2	17	280.88	4,774.96
111	Ceiling suspended not exceeding 1m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	276.97	4,708.49
112	Ceiling suspended exceeding 1m and not exceeding 2m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	280.88	4,774.96
113	Sloping ceiling suspended not exceeding 1m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	276.97	4,708.49
114	Sloping ceiling suspended exceeding 1m and not exceeding 2m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	280.88	4,774.96
115	Ceilings suspended not exceeding 1m below steel purlins at 1,8m centres (trusses at 6,0m centres)	m2	17	276.97	4,708.49
116	Ceilings suspended exceeding 1m and not exceeding 2m below steel purlins at 1,8m centres (trusses at 6,0m centres)	m2	17	280.88	4,774.96
117	Sloping ceilings suspended not exceeding 1m below steel purlins at 1,8m centres (trusses at 6,0m centres)	m2	17	276.97	4,708.49

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
118	Sloping ceilings suspended exceeding 1m and not exceeding 2m below steel purlins at 1,8m centres (trusses at 6,0m centres)	m2	17	280.88	4,774.96
119	Horizontal bulkheads suspended not exceeding 1m below concrete soffits	m2	17	276.97	4,708.49
120	Horizontal bulkheads suspended exceeding 1m and not exceeding 2m below concrete soffits	m2	17	280.88	4,774.96
121	Horizontal bulkhead suspended not exceeding 1m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	276.97	4,708.49
122	Horizontal bulkhead suspended exceeding 1m and not exceeding 2m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	280.88	4,774.96
123	Sloping bulkheads suspended exceeding 1m and not exceeding 2m below concrete soffits	m2	17	276.97	4,708.49
124	Sloping bulkhead suspended exceeding 1m and not exceeding 2m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	280.88	4,774.96
125	Circular cutting	m	17	15.20	258.40
126	Opening for sprinkler head	No	17	17.80	302.60
127	Extra over ceiling for opening for 75mm diameter downlighter	No	17	17.80	302.60
128	Extra over ceiling for opening for 180mm diameter downlighter	No	17	20.40	346.80
129	Extra over ceiling for opening for 600 x 1200mm light fitting	No	17	66.51	1,130.67
130	Extra over ceiling for 600 x 600mm opening for ventilation/air conditioning diffuser	No	17	66.51	1,130.67
	<u>Sundries</u>				
131	Install 600 x 1200mm acoustic tile in existing suspended ceiling frame	m2	17	138.50	2,354.50

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Everite Nutec vinyl finished ceiling tiles or equally approved size 1200 x 600mm x 6mm thick laid on and including SQ/T38 galvanised main tees, cross tees, hold-down clips, wedges, etc., all suspended with galvanised hangers at hanger centres not exceeding 1200mm</u>				
132	Ceiling suspended not exceeding 1m below concrete soffits.	m2	17	276.07	4,693.14
133	Ceiling suspended exceeding 1m and not exceeding 2m below concrete soffits	m2	17	280.36	4,766.07
134	Sloping ceiling suspended not exceeding 1m below concrete soffits	m2	17	276.07	4,693.14
135	Sloping ceiling suspended exceeding 1m and not exceeding 2m below concrete soffits	m2	17	280.36	4,766.07
136	Ceiling suspended not exceeding 1m. below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	276.07	4,693.14
137	Ceiling suspended exceeding 1m and not exceeding 2m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	280.36	4,766.07
138	Sloping ceiling suspended not exceeding 1m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	276.07	4,693.14
139	Sloping ceiling suspended exceeding 1m and not exceeding 2m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	280.36	4,766.07
140	Ceilings suspended not exceeding 1m below steel purlins at 1,8m centres (trusses at 6,0m centres)	m2	17	276.07	4,693.14
141	Ceilings suspended exceeding 1m and not exceeding 2m below steel purlins at 1,8m centres (trusses at 6,0m centres)	m2	17	280.36	4,766.07
142	Sloping ceilings suspended not exceeding 1m below steel purlins at 1,8m centres (trusses at 6,0m centres)	m2	17	276.07	4,693.14
143	Sloping ceilings suspended exceeding 1m and not exceeding 2m below steel purlins at 1,8m centres (trusses at 6,0m centres)	m2	17	280.36	4,766.07
144	Horizontal bulkheads suspended not exceeding 1m below concrete soffits	m2	17	276.07	4,693.14

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
145	Horizontal bulkheads suspended exceeding 1m and not exceeding 2m below concrete soffits	m2	17	280.36	4,766.07
146	Horizontal bulkhead suspended not exceeding 1m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	276.07	4,693.14
147	Horizontal bulkhead suspended exceeding 1m and not exceeding 2m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	280.36	4,766.07
148	Sloping bulkheads suspended exceeding 1m and not exceeding 2m below concrete soffits	m2	17	276.07	4,693.14
149	Sloping bulkhead suspended exceeding 1m and not exceeding 2m below timber/steel purlins at 1,4m centres (trusses at 1,0m centres)	m2	17	280.36	4,766.07
150	Circular cutting	m	17	15.20	258.40
151	Opening for sprinkler head	No	17	17.80	302.60
152	Extra over ceiling for opening for 75mm diameter downlighter	No	17	17.80	302.60
153	Extra over ceiling for opening for 180mm diameter downlighter	No	17	10.40	176.80
154	Extra over ceiling for opening for 600 x 1200mm light fitting	No	17	66.51	1,130.67
155	Extra over ceiling for 600 x 600mm opening for ventilation/air conditioning diffuser	No	17	66.51	1,130.67
	<u>Donn cornices to suspended ceilings</u>				
156	47 x 35mm 'SM25' recessed shadowline cornice plugged (code LSM 25).	m	17	101.21	1,720.57
157	47 x 35mm 'SM25' recessed shadowline cornice plugged (code LSM 25) circular on plan	m	17	126.90	2,157.30
	<u>Sundries</u>				
158	Install 600 x 1200mm acoustic tile in existing suspended ceiling frame	No	17	175.47	2,982.99
159	Vacuum cleaning of ceiling voids	m2	17	7.80	132.60

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>CEILING TILES TO Rhino / Gypsum Board ceiling or equally approved</u>				
160	500 x 500 Polystyrene Tile with wood finish	m2	17	149.54	2,542.18
161	500 x 500 Polystyrene Tile with Laminated finish	m2	17	149.54	2,542.18
	<u>PARTITIONS ETC.</u>				
	<u>Rhino-Drywall partition systems</u>				
	<u>BPB Gypsum GypRoc Standard - 40 db (½ hour fire rating) Ultrasteel Stud Drywall consisting of stud and track system with 51mm Drywall Ultrasteel studs positioned at 600mm centres fixed into 51mm wide top and bottom track clad on both sides with 12,5mm thick taper edged Rhinoboard fixed with 25mm Drywall screws at 220mm centres and all corners fixed with Drywall Corner beads and all joints to be taped and jointed as per manufacture's specifications.</u>				
162	Partitioning 2100mm high with bottom track plugged and free top track	m	17	733.66	12,472.15
163	Partitioning 3000mm high with bottom track plugged and top track fixed to suspended ceiling tees	m	17	1,072.26	18,228.42
164	Partitioning 3000mm high with bottom track plugged and top track fixed to suspended ceiling tees circular on plan	m	17	1,072.26	18,228.42
165	Partitioning 3600mm high with bottom track plugged and top track fixed to suspended ceiling tees	m	17	1,298.01	22,066.17
166	Partitioning 3600mm high with bottom track plugged and top track fixed to suspended ceiling tees circular on plan	m	17	1,298.01	22,066.17
167	Partition 3000mm high with top and bottom tracks plugged and glazing in lieu of boarding 1,1m high at 1,0m above floor level framed all round with "Drywall" aluminium glazing sections and divided into panels with aluminium mullions at 1,2m centres with each panel glazed with 4mm clear float glass including neoprene glazing gaskets (glass elsewhere)	m	17	1,788.60	30,406.20
168	Extra over partition 2100mm high for vertical abutment	No	17	104.85	1,782.43
169	Extra over partition 2100mm high for corner	No	17	104.85	1,782.43
170	Extra over partition 2100mm high for T - intersection	No	17	104.85	1,782.43

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
171	Extra over partition 2100mm high for fair end	No	17	158.64	2,696.88
172	Extra over partition 3000mm high for vertical abutment	No	17	104.85	1,782.43
173	Extra over partition 3000mm high for corner	No	17	118.33	2,011.58
174	Extra over partition 3000mm high for T - intersection	No	17	118.33	2,011.58
175	Extra over partition 3000mm high for fair end	No	17	222.36	3,780.12
176	Extra over partition 3600mm high for vertical abutment	m2	17	136.54	2,321.21
177	Extra over partition 3600mm high for corner	No	17	136.54	2,321.21
178	Extra over partition 3600mm high for T - intersection	No	17	136.54	2,321.21
179	Extra over partition 3600mm high for fair end	No	17	263.98	4,487.66
180	75mm Aluminium skirting	m	17	87.20	1,482.40
181	Removal and rifitting of double sided partition with new aluminium top and bottom railtracks (Paint work elsewhere)	m	17	234.06	3,979.02
182	Extra over aluminium frame into drywall partition for glass partition	m	17	123.53	2,100.01
183	Opening of existing partition for doors, windows, etc	m2	17	67.47	1,146.99
	<u>Doors</u>				
184	Extra over partition for 40mm semi-solid flush door 762 x 2032mm high with commercial veneer on both sides and hardwood edge strips to vertical edges hung to and including standard natural anodised aluminium door frame with one pair of 100mm nylon washered	No	4	1,022.07	4,088.28
185	Extra over partition for 40mm semi-solid flush door 813 x 2032mm high with commercial veneer on both sides and hardwood edge strips to vertical edges hung to and including standard natural anodised aluminium door frame with one pair of 100mm nylon washered aluminium hinges and additional studding, trimming, etc	No	4	1,022.07	4,088.28

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
186	Extra over partition for 40mm semi-solid flush double door 1510 x 2032mm high with commercial veneer on both sides and hardwood edge strips to vertical edges hung to and including standard natural anodised aluminium door frame with three pair of 100mm nylon washered aluminium hinges and additional studding, trimming, etc	No	4	1,594.23	6,376.92
187	Extra over partition for 40mm semi-solid flush door 813 x 2032mm high with commercial veneer on both sides and hardwood edge strips to vertical edges hung to and including standard natural anodised aluminium door frame with one pair of 100mm nylon washered aluminium hinges and additional studding, trimming, etc	No	4	1,059.79	4,239.16
188	Extra over partition for 40mm semi-solid flush double door 1510 x 2032mm high with commercial veneer on both sides and hardwood edge strips to vertical edges hung to and including standard natural anodised aluminium door frame with three pair of 100mm nylon washered aluminium hinges and additional studding, trimming, etc	No	5	1,672.25	8,361.25
	<u>Insulation</u>				
189	75mm Thick "Isotherm" thermal insulation blanket in cavity of partitioning	m2	56	74.62	4,178.72

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>TOILET PARTITIONS</u>				
	All toilet partitions are to be manufactured in a one-piece construction. No horizontal or vertical joints will be permitted				
	<u>Vitraflex toilet partitioning with 20mm thick vitreous enamelled steel sheet faced particle board bonded panels and natural anodised aluminium edging and top rails including fixing components and standard ironmongery comprising of indicator bolts, coat</u>				
190	Partition 800 X 2000mm high	No	3	2,340.63	7,021.89
191	Partition 900 X 2000mm high	No	3	2,598.11	7,794.33
192	Partition 1200 X 2000mm high	No	3	2,986.90	8,960.70
193	Partition 1800 X 2000mm high	No	3	3,734.61	11,203.83
194	Full stile 200 X 2000mm high	No	3	215.86	647.58
195	Wall stile 105mm wide x 2000mm high	No	3	165.15	495.45
196	End stile 140mm wide x 2000mm high	No	3	183.35	550.05
197	Door 794 x 1800mm high	No	3	2,340.63	7,021.89
					656,423.66

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	SUB-TOTAL <i>(Carried To Summary)</i>				32,277,856.53
	<u>BILL NO. 10</u>				
	<u>FLOOR COVERINGS, WALL LININGS, ETC.</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	<u>FLOOR COVERINGS</u>				
	<u>Laminated wooden floor</u>				
	<u>8mm Brown Rhodesian teak mosaic wood floor boards or equally approved</u>				
1	On floors	m2	18	504.54	9,081.72
2	On dished (sunken) floors	m2	18	504.54	9,081.72
3	On treads and risers of stepped floors	m2	18	485.02	8,730.36
4	On treads and risers of stairs	m2	18	485.02	8,730.36
5	On treads and risers of winding stairs	m2	18	485.02	8,730.36
6	Margins and borders not exceeding 500mm wide	m	18	243.17	4,377.06
7	Inserts 500mm wide of differing colour	m	18	243.17	4,377.06
8	Circular cutting	m	18	10.40	187.20
	<u>8mm Brown Rhodesian teak mosaic wood blocks or equally approved</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
9	On floors	m2	18	504.54	9,081.72
10	On dished (sunken) floors	m2	18	504.54	9,081.72
11	On treads and risers of stepped floors	m2	18	485.02	8,730.36
12	On treads and risers of stairs	m2	18	485.02	8,730.36
13	On treads and risers of winding stairs	m2	18	485.02	8,730.36
14	Margins and borders not exceeding 500mm wide	m	18	243.17	4,377.06
15	Turn-ups over coves and up against walls not exceeding 500mm girth	m	18	243.17	4,377.06
16	Inserts 500mm wide of differing colour	m	18	243.17	4,377.06
17	Circular cutting	m	18	10.40	187.20
	<u>Sundries</u>				
18	Sanding and sealing to floors	m2	18	234.06	4,213.08
	<u>220 x 73 x 19mm Brown Rhodesian teak mosaic wood blocks in herringbone pattern or equally approved</u>				
19	On floors	m2	18	825.72	14,862.96
20	On dished (sunken) floors	m2	18	825.72	14,862.96
21	On treads and risers of stepped floors	m2	18	825.72	14,862.96
22	On treads and risers of stairs	m2	18	825.72	14,862.96
23	On treads and risers of winding stairs	m2	18	825.72	14,862.96
24	Margins and borders not exceeding 500mm wide	m	18	416.11	7,489.98
25	Turn-ups over coves and up against walls not exceeding 500mm girth	m	18	416.11	7,489.98
26	Inserts 500mm wide of differing colour	m	18	416.11	7,489.98
27	Circular cutting	m	18	10.40	187.20
	<u>300 x 300 x 2,0mm "Floorflex" semi-flexible vinyl tiles or equally approved</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
28	On floors	m2	18	233.94	4,210.92
29	On dished (sunken) floors	m2	18	233.94	4,210.92
30	On treads and risers of stepped floors	m2	18	233.94	4,210.92
31	On treads and risers of stairs	m2	18	233.94	4,210.92
32	Margins and borders not exceeding 500mm wide	m	18	68.92	1,240.56
33	Turn-ups over coves and up against walls not exceeding 500mm girth	m	18	68.92	1,240.56
34	Inserts 500mm wide of differing colour	m	18	24.70	444.60
35	Circular cutting	m	18	2.60	46.80
36	75mm Skirting	m	18	16.07	289.26
	<u>300 x 300 x 2,5mm "Floorflex" semi-flexible vinyl tiles or equally approved</u>				
37	On floors	m2	18	254.74	4,585.32
38	On dished (sunken) floors	m2	18	254.74	4,585.32
39	On treads and risers of stepped floors	m2	18	254.74	4,585.32
40	On treads and risers of stairs	m2	18	254.74	4,585.32
41	On treads and risers of winding stairs	m2	18		0.00
42	Margins and borders not exceeding 500mm wide	m	18	79.33	1,427.94
43	Turn-ups over coves and up against walls not exceeding 500mm girth	m	18	79.33	1,427.94
44	Inserts 500mm wide of differing colour	m	18	27.32	491.76
45	Circular cutting	m	18	2.60	46.80
46	75mm Skirting	m	18	18.57	334.26
	<u>300 x 300 x 2,0mm "Superflex" fully-flexible vinyl tiles or equally approved</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
47	On floors	m2	18	254.57	4,582.26
48	On dished (sunken) floors	m2	18	254.57	4,582.26
49	On treads and risers of stepped floors	m2	18	254.57	4,582.26
50	On treads and risers of stairs	m2	18	254.57	4,582.26
51	On treads and risers of winding stairs	m2	18		0.00
52	Margins and borders not exceeding 500mm wide	m	18	107.93	1,942.74
53	Turn-ups over coves and up against walls not exceeding 500mm girth	m	18	107.93	1,942.74
54	Inserts 500mm wide of differing colour	m	18	36.40	655.20
55	Circular cutting	m	18	2.60	46.80
56	75mm Skirting	m	18	25.76	463.68
	<u>300 x 300 x 2,5mm "Superflex" fully-flexible vinyl tiles or equally approved</u>				
57	On floors	m2	18	266.58	4,798.44
58	On dished (sunken) floors	m2	18	266.58	4,798.44
59	On treads and risers of stepped floors	m2	18	266.58	4,798.44
60	On treads and risers of stairs	m2	18	266.58	4,798.44
61	On treads and risers of winding stairs	m2	18		0.00
62	Margins and borders not exceeding 500mm wide	m	18	135.23	2,434.14
63	Turn-ups over coves and up against walls not exceeding 500mm girth	m	18	135.23	2,434.14
64	Inserts 500mm wide of differing colour	m	18	44.21	795.78
65	Circular cutting	m	18	2.60	46.80
66	75mm Skirting	m	18	31.99	575.82
	<u>2,0mm "Superflex" fully flexible vinyl sheeting with welded joints or equally approved</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
67	On floors	m2	18	446.68	8,040.17
68	On dished (sunken) floors	m2	18	464.00	8,352.07
69	On treads and risers of stepped floors	m2	18	464.00	8,352.07
70	On treads and risers of stairs	m2	18	464.00	8,352.07
71	Margins and borders not exceeding 500mm wide	m	18	193.33	3,479.94
72	Turn-ups over coves and up against walls not exceeding 500mm girth	m	18	193.33	3,479.94
73	Inserts 500mm wide of differing colour	m	18	77.34	1,392.12
74	Circular cutting	m	18	2.60	46.80
75	75mm Skirting	m	18	44.63	803.34
	<u>2,5mm "Superflex" fully flexible vinyl sheeting with welded joints or equally approved</u>				
76	On floors	m2	18	470.87	8,475.59
77	On dished (sunken) floors	m2	18	486.61	8,758.93
78	On treads and risers of stepped floors	m2	18	486.61	8,758.93
79	On treads and risers of stairs	m2	18	486.61	8,758.93
80	Margins and borders not exceeding 500mm wide	m	18	221.19	3,981.42
81	Turn-ups over coves and up against walls not exceeding 500mm girth	m	18	221.19	3,981.42
82	Inserts 500mm wide of differing colour	m	18	88.47	1,592.46
83	Circular cutting	m	18	2.60	46.80
84	75mm Skirting	m	18	51.34	924.12
	<u>3,5mm "Industrial Floor" flexible vinyl sheeting with welded joints or equally approved</u>				
85	On floors	m2	18	508.73	9,157.14

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
86	On dished (sunken) floors	m2	18	523.03	9,414.54
87	On treads and risers of stepped floors	m2	18	537.32	9,671.76
88	On treads and risers of stairs	m2	18	537.32	9,671.76
89	Margins and borders not exceeding 500mm wide	m	18	268.67	4,836.06
90	Turn-ups over coves and up against walls not exceeding 500mm girth	m	18	268.67	4,836.06
91	Inserts 500mm wide of differing colour	m	18	107.46	1,934.28
92	Circular cutting	m	18	2.60	46.80
93	75mm Skirting	m	18	61.01	1,098.18
	<u>3,5mm "Industrial Floor" non - slip flexible vinyl sheeting with welded joints or equally approved</u>				
94	On floors	m2	18	524.33	9,437.94
	<u>450 x 450 x 6.3mm stud pattern Eco range (Colour : dark grey) "Tuff Seal" interlocking heavy duty vinyl tiles or equally approved laid in accordance with manufactures instructions</u>				
95	On floors	m2	18	500.63	9,011.34
96	On dished (sunken) floors	m2	18	500.63	9,011.34
97	On treads and risers of steps	m2	18	500.63	9,011.34
98	On treads and risers of stairs	m2	18	500.63	9,011.34
99	Margins and borders not exceeding 450mm wide	m	18	150.85	2,715.30
100	Circular cutting	m	18	10.40	187.20
101	75mm Skirting	m	18	60.08	1,081.44
	<u>Belgotex Berber Point polypropylene needlepunch carpeting or equally approved laid in accordance with SABS 0186-2000 fitting code of practice</u>				
102	On floors	m2	18	458.95	8,261.14
103	On dished (sunken) floors	m2	18	481.88	8,673.91

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
104	On treads and risers of steps	m2	18	481.88	8,673.91
105	On treads and risers of stairs	m2	18	481.88	8,673.91
106	Margins and borders not exceeding 500mm wide	m	18	176.52	3,177.36
107	Circular cutting	m	18	2.60	46.80
	<u>Belgotex Berber Point 920 Nexus 500 x 500mm carpet tiles or equally approved laid in accordance with SABS 0186-2000 fitting code of practice</u>				
108	On floors	m2	18	458.95	8,261.14
109	On dished (sunken) floors	m2	18	481.88	8,673.91
110	On treads and risers of steps	m2	18	481.88	8,673.91
111	On treads and risers of stairs	m2	18	481.88	8,673.91
112	Margins and borders not exceeding 500mm wide	m	18	176.52	3,177.36
113	Circular cutting	m	18	2.60	46.80
114	75mm Skirting	m	18	42.29	761.22
	<u>Sundries</u>				
115	Blue underfelt	m2	18	117.58	2,116.44
116	Self-levelling screed	m2	18	84.52	1,521.36
117	Aluminium metal door strips	m2	18	63.07	1,135.26
118	Steam cleaning to carpets	m2	18	84.52	1,521.36
	<u>WALL LININGS</u>				
	<u>1,25mm. "Superflex" fully flexible vinyl sheeting with welded joints or equally approved</u>				
119	On walls	m2	18	209.36	3,768.41
120	On circular walls	m2	18	209.36	3,768.41
121	Circular cutting	m	18	12.60	226.80

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Belgotex Berber Heritage tufted carpeting glued on or equally approved</u>				
122	On walls	m2	18	481.88	8,673.91
123	On circular walls	m2	18	481.88	8,673.91
124	Circular cutting	m	18	12.60	226.80
	<u>Architect approved sheet carpet (Cost Price R280.00/m², delivered on site, fixed with adhesive)</u>				
125	On walls	m2	18	481.88	8,673.91
126	On circular walls	m2	18	481.88	8,673.91
127	Circular cutting	m	18	2.60	46.80
	<u>SKIRTINGS, NOSINGS, ETC</u>				
	<u>Floorworx Extruda or equally approved</u>				
128	25mm MES25 edge strip	m	18	38.21	687.78
129	25 x 2.5mm MPT25 edge trim	m	18	38.21	687.78
130	70 x 10mm MCB70 vinyl skirting	m	18	44.70	804.60
131	100 x 14mm MCB100 vinyl skirting	m	18	60.31	1,085.58
132	100 x 50mm MFE5 vinyl hospital skirting	m	18	67.22	1,209.96
133	35 x 14mm MCF54 vinyl coved fillet	m	18	60.71	1,092.78
134	75 x 10mm MSN100 vinyl stairnosing	m	18	62.41	1,123.38
	<u>Floorworx Protrim Mouldings</u>		18		0.00
135	82 x 11mm PTS082 skirting	m	18	67.62	1,217.16
136	16 x 16mm PTQ016 quarter round	m	18	40.31	725.58
137	66 x 17mm PTC066 chair rail	m	18	68.92	1,240.56
	<u>Floorworx Intrad Wall and Corner Protection All to be installed strictly in accordance to manufacturer's instructions</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
138	Wall protector of 200 x 29mm TR200 high impact resistant uPVC extruded lip channel profile complete with 25mm wide uPVC brackets TRP200 at 400mm max. centres plugged to wall and uPVC joining blocks TRJ200 as required	m	18	250.97	4,517.46
139	Extra over lip channel for uPVC external corner TRE200	No	18	135.23	2,434.14
140	Extra over lip channel for uPVC stop end TRS200	No	18	79.33	1,427.94
141	Corner protector of 70 x 70 x 1.2mm thick CP1200 high impact resistant uPVC extruded angular profile	m	18	120.94	2,176.92
<u>HANDRAILS</u>					
<u>Floorworx Extruda vinyl handrails or equally approved</u>					
142	MHR1 handrail fitted over 40 x 6mm core rail	m	18	65.02	1,170.36
143	MHR2 handrail fitted over 40 x 10mm core rail	m	18	76.73	1,381.14
144	MHR3 handrail fitted over 50 x 6mm core rail	m	18	83.22	1,497.96
145	MHR4 handrail fitted over 50 x 10mm core rail	m	18	97.53	1,755.54
<u>POLISH, SEALERS, ETC.</u>					
<u>Polish, Sealers, etc</u>					
146	2 coats wax polish on vinyl flooring	m2	18	29.11	523.98
147	Strip and seal on vinyl flooring	m2	18	23.40	421.20
<u>EXPANSION JOINTS</u>					
<u>Floorworx Intrad Wall and Corner Protection All to be installed strictly in accordance to manufacturers instructions</u>					
148	Floor expansion joint with aluminium extruded T-section profile complete with rubber plugged to wall, floors,etc TRJ200 as required	m	18	250.97	4,517.46
<u>WALL COVERINGS (PAPERHANGING)</u>					
<u>1,25mm "Superflex" wall paper sheeting with welded joints or equally approved</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
149	On walls	m2	18	209.36	3,768.41
150	On circular walls	m2	18	149.54	2,691.72
151	Circular cutting	m	18	2.60	46.80
	<u>HERITAGE BUILDINGS ; "Rehabilitation of wooden floors, facades, and panels</u>				
152	Rehabilitation of suspended wooden floor	m2	18	312.82	5,630.76
153	Rehabilitation of wooden panels	m2	18	276.02	4,968.36
154	Rehabilitation of wooden facades	m2	18	276.02	4,968.36
					669,477.01

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	SUB-TOTAL <i>(Carried To Summary)</i>				32,947,333.54
	<u>BILL NO. 11</u>				
	<u>IRONMONGERY</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	Finishers to ironmongery Where applicable finishes to ironmongery are indicated by suffixes in accordance with the following list BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded				
	<u>HINGES, BOLTS, ETC.</u>				
	<u>Union or equal and approved fixed to timber</u>				
1	100mm steel hinge	No	11	58.88	647.68
2	100mm Falling / Rising butt Hinge	No	11	150.98	1,660.78
3	100mm brass hinge JH-BB-STD-2-SS	No	11	116.70	1,283.70
4	100 x 100mm brass parliament hinge	No	11	385.42	4,239.62

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
5	100mm brass barrel bolt	No	11	38.80	426.80
6	100mm brass barrel bolt with keep fixed to metal	No	11	49.50	544.50
7	100mm brass barrel bolt with keep let into concrete	No	11	49.50	544.50
8	100mm Chrome plated brass barrel bolt	No	11	38.80	426.80
9	100mm Chrome plated brass barrel bolt with keep fixed to metal	No	11	69.44	763.84
10	100mm Chrome plated brass barrel bolt with keep let into concrete	No	11	69.44	763.84
11	WC Anodised Silver bathroom indicator bolt Ref. AL809AS	No	11	1,309.98	14,409.78
12	WC chrome plated indicator bolt with keep fixed to metal. Ref. CZ80941CH	No	11	289.76	3,187.36
13	WC chrome plated indicator Ref SS5004-73SS	No	11	317.43	3,491.73
14	Escutcheon on Rose Bathroom indicator SS5305-73SS	No	11	259.53	2,854.83
15	Escutcheon Bathroom indicator PB5375-73CH (Chrome plated)	No	11	367.81	4,045.91
16	Lockset IW2029/IW2030/IW2031/IW2047 for indicator bolt or CZ682TR / TL with 22314 indicator Lockset	No	11	762.38	8,386.18
17	Heavy duty security door chain brass code V-WS6-EB	No	11	458.21	5,040.31
<u>CATCHES, CABIN HOOKS, ETC</u>					
18	Brass window catch to side hung sash	No	11	82.97	912.67
19	Brass window stay to side hung sash	No	11	82.97	912.67
20	Brass window combination stay and fastener size 300mm Ref IW1260	No	11	153.89	1,692.79
21	Brass window fanlight stay and fastener size 300mm Ref IW1261	No	11	153.89	1,692.79
22	Brass window sliding stays outwards size 300mm Ref IW1262	No	11	82.97	912.67
23	Brass window telescopic stays size 300mm Ref IW1263	No	11	153.89	1,692.79
24	Brass window roller stay size 300mm Ref IW1263	No	11	82.97	912.67

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
25	Brass window casement stay size 300mm Ref IW1265	No	11	82.97	912.67
26	Brass window sash hook with wooden stick Ref IW1271	No	11	288.28	3,171.08
27	32mm Diameter polished hardwood longarm 2 600mm long with brass sash hook Ref "IW 1271" on one end, two broom clips each with 20 x 100 x 100mm wrought and chamfered hardwood block twice oiled and plugged and 20 x 70 x 70mm wrought and chamfered hardwood block with sinking twice oiled and plugged	No	11	608.89	6,697.77
28	Brass window sash lifts Ref IW1272	No	11	82.97	912.67
29	Brass window spring catch Ref IW1273	No	11	82.97	912.67
30	Brass window spring catch box Ref IW1274	No	11	82.97	912.67
31	Cupboard fastener IW 1266	No	11	82.97	912.67
32	Sash fastener IW 1267	No	11	82.97	912.67
33	Casement fastener IW 1269	No	11	82.97	912.67
34	Curved casement fastener IW 1270	No	11	92.34	1,015.74
35	Casement fastener wedge plate IW 1277	No	11	92.34	1,015.74
36	Dual screw/ sash window lock	No	11	180.67	1,987.37
37	100mm Brass cabin hook and eye	No	11	88.33	971.63
38	150mm Brass cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged	No	11	124.45	1,368.95
39	150mm Chromium plated cabin hook and eye	No	11	42.83	471.13
40	150mm Chromium plated cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged	No	11	80.31	883.41
41	Brass window handle	No	11	82.97	912.67
<u>LOCKS</u>					
<u>Union or equal and approved fixed to timber</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
42	Two lever lockset (2 Keys) with striking plate fixed to metal Ref. No. CZ682-24-95CH / SC. Lockset with lock, handles and keys, complete	No	11	546.72	6,013.92
43	Three lever lockset (2 Keys) with striking plate fixed to metal Ref. CZ682-24-52CH / SC. Lockset with lock, handles and keys, complete	No	11	656.98	7,226.78
44	Four lever lockset (2 Keys) with striking plate fixed to metal Ref. CZ682-24-61CH. Lockset with lock, handles and keys, complete	No	11	797.78	8,775.58
45	Double cylinder lockset (2 Keys) with striking plate fixed to metal Ref. CZ682-05-222CH. Lockset with lock, handles and keys, complete	No	11	844.67	9,291.37
46	Combination Bishop Furniture Ref. No. AL684-24-95AS with key hole with Two lever lockset 2295-76SS (2 Keys) with striking plate fixed to metal	No	11	1,023.63	11,259.93
47	Combination Bishop Furniture Ref. No. AL684-24-95AS with key hole with Three lever lockset 2252-76SS (2 Keys) with striking plate fixed to metal	No	11	1,129.61	12,425.71
48	Combination Bishop Furniture Ref. No. AL684-24-95AS with key hole with Four lever lockset 2252-76SS (2 Keys) with striking plate fixed to metal	No	11	1,129.61	12,425.71
49	Combination Bishop Furniture Double cylinder Ref. No. AL684-05AS with key hole with Cylinder Euro lockset L-2209-78SS (2 Keys) with striking plate fixed to metal	No	11	1,361.85	14,980.35
50	Oval knob cylinder lockset (2 Keys) with striking plate fixed to metal Ref. AL684-05-222AS / IW2122	No	11	645.02	7,095.22
51	Oval half knob cylinder lockset (2 Keys) with striking plate fixed to metal Ref. AL684-05-222AS / IW2122	No	11	632.98	6,962.78
52	Cylinder deadlockset (2 Keys) with striking plate fixed to metal Ref. IW 2019	No	11	582.14	6,403.54
53	Two lever lockset 2295-76SS (2 Keys) with striking plate fixed to metal	No	11	310.89	3,419.79
54	Three lever lockset 2252-76SS (2 Keys) with striking plate fixed to metal	No	11	416.88	4,585.68

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
55	Four lever lockset 22313-7615MMCH (2 Keys) with striking plate fixed to metal	No	11	416.88	4,585.68
56	Rebated conversion set Ref No IW 2140 / UDY2900SS fixed to timber door	No	11	306.18	3,367.98
57	Cylinder rim night latch Ref No 1022G Dimple keyway	No	11	658.60	7,244.60
58	Union LX 3261 security gate lock box	No	11	612.91	6,742.01
59	Master key	No	11	160.59	1,766.49
60	Cylinder rim night latch Ref No 1022G-KB, KB502 keyway	No	11	435.26	4,787.86
61	Union EP Cylinder upright lock Ref No L-2215-78SS/SL	No	11	303.49	3,338.39
62	Union EP Knob Cylinder MKD SC Code: 2x19SCMKD	No	11	408.94	4,498.34
63	Campus lockset 72mm centres Code SS6D67L-05CAM72 LH / RH	No	11	944.25	10,386.75
64	52 Union Cylinder Cupboard lock (22/25/32/38mm), Code: 452-NP	No	11	457.00	5,027.00
65	15CB Union Cylinder Cupboard drawer lock (22/25/32/38mm), Code: 415-64L/1 or 415-64R/1	No	11	49.77	547.47
66	Union Rim Dimple key lock Code: 1x1SDD	No	11	249.90	2,748.90
67	Union Cylinder Rim Lock GMKSC Code: 1x1SCGMK	No	11	420.42	4,624.62
68	Container Double Glass door lock Code: M89100711R	No	11	1,712.93	18,842.23
69	Heavy duty Digital Rim lock with Over Keys, Code: MDL2735SC	No	11	1,369.12	15,060.32
70	Heavy duty Escutcheons Code B-3G110-SS-P300	No	11	321.17	3,532.87
71	Cam Locks 60 Series for cupboards and drawers K37/B44 KD, Code: LA1106R	No	11	58.29	641.19
72	Cam Locks 60 Series for cupboards and drawers X44 DR KD, Code: LB7130R	No	11	61.56	677.16
73	L&T locking handles 38mm Rose & 3PLD Code: LL3209R	No	11	142.38	1,566.18
74	L&T locking handles T46 Re ATD Master C/P Code: LM1806R	No	11	186.02	2,046.22

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
75	L&T locking handles K48 Lem Knob handle 3PLD, Code LN2422/R	No	11	171.30	1,884.30
76	Gate lock N201 Security lock with face plate, Code: LH4115/R	No	11	321.17	3,532.87
77	Sliding door lock N201-1, Code: LH4145/R	No	11	235.53	2,590.83
78	Gate lock N888 Security lock with Cylinder and welded lock box, Code: LH8883	No	11	515.56	5,671.16
79	Locksmith to open Mortice lock and provide one key	No	11	221.56	2,437.16
80	Locksmith to open Cylinder lock and provide one key	No	11	246.81	2,714.91
81	Locksmith to open Cupboards, etc lock and provide one key	No	11	171.07	1,881.77
82	Locksmith to open Mortice Cylinder lock and provide one key	No	11	246.81	2,714.91
83	Locksmith to open Safe lock and provide one key	No	11	468.38	5,152.18
	<u>HANDLES, ETC.</u>				
	<u>IW or equal and approved fixed to timber</u>				
84	UNION AL5D67-06AS OR "IW 1324" Dove pull handle for dead lock on 152 x 152mm backplate (One)	No	11	399.11	4,390.21
85	Set of two "IW 1320" 300mm,25mm diameter Dove pull handles fixed back to back	No	11	782.87	8,611.57
86	Set of two "IW 1320" 300mm,32mm diameter Dove pull handles fixed back to back	No	11	809.63	8,905.93
87	Set of two lever handles Ref "IW 1212/62/06" fixed back to back	No	11	782.87	8,611.57
88	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/62/06" fixed back to back	No	11	1,197.72	13,174.92
89	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/62/05" fixed back to back	No	11	1,197.72	13,174.92
90	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/62/13" fixed back to back	No	11	1,197.72	13,174.92
91	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/62/24" fixed back to back	No	11	1,197.72	13,174.92

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
92	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/63/06" fixed back to back	No	11	1,197.72	13,174.92
93	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/63/05" fixed back to back	No	11	1,197.72	13,174.92
94	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/63/13" fixed back to back	No	11	1,197.72	13,174.92
95	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/63/24" fixed back to back	No	11	1,197.72	13,174.92
96	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/66/06" fixed back to back	No	11	1,197.72	13,174.92
97	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/66/05" fixed back to back	No	11	1,197.72	13,174.92
98	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/66/13" fixed back to back	No	11	1,197.72	13,174.92
99	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/66/24" fixed back to back	No	11	1,197.72	13,174.92
100	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/67/06" fixed back to back	No	11	1,197.72	13,174.92
101	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/67/05" fixed back to back	No	11	1,197.72	13,174.92
102	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/67/13" fixed back to back	No	11	1,197.72	13,174.92
103	Set of two lever handles with 3mm aluminium backplates Ref "IW 1212/67/24" fixed back to back	No	11	1,197.72	13,174.92
104	Euro profile IW2051 double cylinder lockset comprising IW1212/63/05 furniture and IW 2006 upright lock case with striking plate	No	11	1,318.16	14,499.76
105	Rebated conversion set	No	11	129.81	1,427.91
106	Aluminium Cupboard Pull handle Code: AL5123AS	No	11	102.78	1,130.58
107	Aluminium Hospital Pull handle Code: AL5510AS (One)	No	11	1,021.18	11,232.98

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
108	Aluminium 200 Pull handle BTB Code: AL5512-200BBAS (One)	No	11	332.15	3,653.65
109	Aluminium 300 Pull handle BTB Code: AL5512-300BBAS (One)	No	11	615.07	6,765.77
110	Cedar Pull Handle Blank Code: AL5C63-06AS	No	11	316.53	3,481.83
111	Cedar Pull Handle on Back Plate LH/ RH Profile 152x152 Code: AL5C66L-05AS / AL5C66R-05AS	No	11	667.56	7,343.16
112	Cedar Pull Handle on Back Plate LH/ RH Profile 152x176 Code: AL5C67L-05AS / AL5C67R-05AS	No	11	732.27	8,054.97
113	Stainless steel Dove Pull Handle on Back Plate LH / RH Key Hole 152x152 Plate Code: SS5D66L-24SS / SS5D66R-24SS	No	11	342.58	3,768.38
114	Stainless steel Dove Pull Handle on Back Plate LH / RH Key Hole 152x176 Plate Code: SS5D67L-24SS / SS5D67R-24SS	No	11	485.58	5,341.38
115	Flush Pull Handle Square - Wooden Sliding door, Code: 99004SS	No	11	109.85	1,208.35
116	Flush Pull Handle Radius - Wooden Sliding door, Code: SS5004SS	No	11	123.49	1,358.39
<u>BOLTS</u>					
117	Esco Rim lock night latch code EDY1033G	No	11	269.44	2,963.84
<u>BATHROOM FITTINGS</u>					
<u>IW or equal and approved fixed to timber</u>					
118	Code IW7010SS surface mounted multi-roll (3) toilet roll dispenser plugged	No	11	1,002.21	11,024.31
119	Code IW7015SS wall mounted soap dispenser plugged	No	11	1,002.21	11,024.31
<u>Bristell or equally approved</u>					
120	32mm "Bristell Type BGR1" back grab rail 600mm long plugged	No	11	1,252.58	13,778.38
121	32mm "Bristell Type BGR2A" side grab rail 600mm long plugged	No	11	1,195.02	13,145.22
<u>SUNDRIES</u>					
<u>IW or equal and approved fixed to timber</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
122	Code No "IW5002SC" / Union CZ8731BP door stop plugged	No	11	77.33	850.63
123	Code No "IW5032AL" / Union "AL8253AS hat and coat hook with rubber tip	No	11	74.91	824.01
124	Code No "IW5042AL" / Union "AL8723AS hat and coat hook	No	11	36.12	397.32
125	Union code AL8254AS door stop 254/C91	No	11	220.54	2,425.94
126	Union code AL8730AS door stop with rubber	No	11	143.55	1,579.05
127	32mm Diameter polished hardwood longarm 2600mm long with brass pole hook on one end, two broom clips each with 20 x 100 x 100mm wrought and chamfered hardwood block twice oiled and plugged and 20 x 70 x 70mm wrought and chamfered hardwood block with sinking twice oiled and plugged (for opening windows)	No	11	434.92	4,784.12
	<u>PUSH PLATES</u>				
	<u>"Union" or equally approved</u>				
128	200 x 800 x 2mm thick AL5089-200W aluminium push plate	No	11	359.99	3,959.89
129	200 x 800 x 1,6mm thick SS5089-200W stainless steel push plate	No	11	493.81	5,431.91
130	400 x 800 x 2mm thick AL5089-400W aluminium kick plate	No	11	641.00	7,051.00
131	400 x 800 x 1,6mm thick SS5089-400W stainless steel kick plate	No	11	757.44	8,331.84
132	152 x 76 Aluminium Push Plate Blank, Code: AL5063-06AS	No	11	174.43	1,918.69
133	152 x 76 Aluminium Push Plate Keyhole, Code: AL5063-24AS	No	11	174.43	1,918.69
134	152 x 152 Aluminium Push Plate Blank, Code: AL5066-06AS	No	11	165.15	1,816.65
135	152 x 152 Aluminium Push Plate Keyhole, Code: AL5066-24AS	No	11	177.50	1,952.50
136	152 x 152 Aluminium Push Plate LH / RH Bathroom, Code:	No	11	626.44	6,890.84
137	152 x 176 Aluminium Push Plate LH / RH Bathroom, Code:	No	11	626.44	6,890.84
	<u>DOOR CLOSERS</u>				
	<u>"Union" or equally approved</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
138	Union Heavy duty regular arm door closer with bracket fixed to metal Ref. No DC 744 EN 1-6 RA DA Code: 744	No	11	6,861.79	75,479.69
139	Union Heavy duty regular arm door closer with bracket fixed to metal Ref. No DC 744 EN 1-6 PA DA Code: 744P	No	11	7,154.96	78,704.56
140	Heavy duty hold open arm door closer with bracket fixed to metal Ref. No DC 744 EN 1-6 HO DA, Code: 744HO	No	11	8,450.78	92,958.58
141	Regular arm door closer with bracket fixed to metal Ref. No DC 777- EN 2-4 Code: 7770	No	11	1,017.56	11,193.16
142	Parallel arm door closer with bracket fixed to metal Ref. No DC 7772 OH EN 2-4, Code: 7772	No	11	1,785.90	19,644.90
143	Heavy duty double action floor spring Ref. NoFS 762 EN 3-6 HD DA TI, Code: 762 with top centre Ref. No AC286 and bottom strap Ref. No AC278	No	11	16,181.73	177,999.03
144	Heavy duty single action floor spring Ref. No FS 764 EN 3-6 HD LH TI Code: 764 with top centre Ref. No AC286AS and bottom strap Ref. No AC278 (LH) or AC279 (RH)	No	11	16,419.94	180,619.34
145	Regular duty double action floor spring Ref. No FS 749 EN 3 DA AL, CODE: 750 with top centre Ref. No AC8 and bottom strap Ref. No AC115	No	11	8,668.66	95,355.26
146	Regular duty single action floor spring Ref. No FS 754 EN 3 RH TI Code: 754 with top centre Ref. No AC286CH and bottom strap Ref. No AC278 (RH) or AC279 (LH)	No	11	9,425.26	103,677.86
147	Union Gate Closer Ref: 720 EN 2 Code: 720	No	11	3,713.57	40,849.27
148	Regular arm door closer with bracket fixed to metal Ref. No R&P CLOSER EN 2/3/4/SIL Code: DC120	No	11	838.75	9,226.25
149	Floor Springs Cam Action FS EN 3 Non HO, Code: DC420	No	11	6,557.31	72,130.41
	<u>SLIDING GEAR</u>				
	<u>"Union" or equally approved</u>				
150	Phantom sliding gear for silent doors up to 45kg width opening 610-915mm clinic cupboards Code: 27-792961	No	11	979.45	10,773.95
151	Husky folding 25 for Folding doors up to 25kg maximum width 1200mm Kit Hf25/12 - 2 leaves	No	11	665.10	7,316.10

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
152	Husky folding 25 for Folding doors up to 25kg maximum width 2400mm Kit Hf25/24 - 4 leaves	No	11	1,022.86	11,251.46
153	Husky folding 40 for Folding doors up to 40kg maximum width 1500mm Kit Hf40/15 2 leaves	No	11	979.45	10,773.95
154	Husky folding 40 for Folding doors up to 40kg maximum width 3000mm Kit Hf40/30 4 leaves	No	11	1,652.74	18,180.14
155	Senator kit for sliding doors up to 30kg for max 900mm opening width Ref 27-791065	No	11	463.63	5,099.93
156	Marathon 55 kit for sliding doors up to 55kg for max 450-750mm opening width Ref 27-789400	No	11	659.21	7,251.31
157	Marathon 55 kit for sliding doors up to 55kg for max 750-900mm opening width Ref 27-789431	No	11	735.46	8,090.06
158	Marathon 55 kit for sliding doors up to 55kg for max 900-1050mm opening width Ref 27-789462	No	11	787.07	8,657.77
159	Marathon 55 kit for sliding doors up to 55kg for max 1050-1200mm opening width Ref 27-789493	No	11	863.32	9,496.52
160	Marathon 55 kit for sliding doors up to 55kg for max 1200-1500mm opening width Ref 27-790695	No	11	1,076.81	11,844.91
161	Loretto for Sliding cupboard doors up to 23kg - Bottom roller kit D4 - 2 leaves Max opening width 1200mm Ref 27-789280	No	11	745.36	8,198.96
162	Loretto for Sliding cupboard doors up to 23kg - Bottom roller kit D5 - 2 leaves Max opening width 1500mm Ref 27-789314	No	11	804.22	8,846.42
163	Loretto for Sliding cupboard doors up to 23kg - Bottom roller kit D6 - 2 leaves Max opening width 1800mm Ref 27-789345	No	11	870.27	9,572.97
	<u>LETTERS, NAMEPLATES, ETC.</u>				
	<u>"Union" or equally approved</u>				
164	152 x 152 x 3mm aluminium plate anodised silver with male pictogram Ref. No. AL5063E-06ASE10	No	11	273.53	3,008.85
165	152 x 152 x 3mm aluminium plate anodised silver with female pictogram Ref. No. AL5063E-06ASE11	No	11	273.53	3,008.85

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
166	152 x 152 x 3mm aluminium plate anodised silver with paraplegic pictogram Ref. No. AL5066E-06ASE14	No	11	273.53	3,008.85
167	152 x 152 x 3mm aluminium plate anodised silver with male and female pictogram Ref. No. AL5066E-06ASE12	No	11	277.28	3,050.12
168	152 x 152 x 3mm aluminium plate anodised silver with fire hydrant pictogram Ref. No. AL5066E-06ASE04	No	11	277.28	3,050.12
169	152 x 152 x 3mm aluminium plate anodised silver with fire hose reel pictogram Ref. No. AL5066E-06ASE05	No	11	277.28	3,050.12
170	152 x 152 x 3mm aluminium plate anodised silver with fire extinguisher pictogram Ref. No. AL5066E-06ASE06	No	11	277.28	3,050.12
171	152 x 152 x 3mm aluminium plate anodised silver with first aid pictogram Ref. No. IW6018	No	11	277.28	3,050.12
172	152 x 152 x 3mm aluminium plate anodised silver with shower pictogram Ref. No. IW6018	No	11	277.28	3,050.12
173	152 x 152 x 3mm aluminium plate anodised silver with shower pictogram Ref. No. IW6006	No	11	277.28	3,050.12
174	152 x 152 x 3mm aluminium plate anodised silver with tea room pictogram Ref. No. IW6006	No	11	277.28	3,050.12
175	152 x 152 x 3mm aluminium plate anodised silver with telephone pictogram Ref. No. IW6006	No	11	277.28	3,050.12
176	152 x 152 x 3mm aluminium plate anodised silver with man running left or right pictogram Ref. No. IW6012	No	11	277.28	3,050.12
177	152 x 152 x 3mm aluminium plate anodised silver with escape stair pictogram Ref. No. IW6013	No	11	277.28	3,050.12
178	152 x 152 x 3mm aluminium plate anodised silver with escape direction pictogram Ref. No. IW6014	No	11	277.28	3,050.12
179	152 x 152 x 3mm aluminium plate anodised silver with bucket and broom pictogram Ref. No. IW6011	No	11	277.28	3,050.12
180	152 x 152 x 3mm aluminium plate anodised silver with baby pictogram Ref. No. IW6004	No	11	277.28	3,050.12
181	COJ Logo: Brushed aluminium 1000 x 800mm deep plugged with aluminium bolts with engraved letters	No	11	2,676.45	29,440.95

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
182	COJ Logo: Brushed aluminium 500 x 300mm deep plugged with aluminium bolts with engraved letters	No	11	1,605.87	17,664.57
183	1000 x 152 x 3mm brushed aluminium plate with engraved letters	No	11	1,338.23	14,720.53
184	100 x 450 x 3mm aluminium plate anodised silver with Name Tags not exceeding 20 letters	No	11	385.42	4,239.62
<u>PELMETS AND CERTAIN TRACKS</u>					
<u>Kirsch or equally approved</u>					
185	Cheney pressed steel pelmet 120mm high with 150mm projection including double track with 12 rollers per meter, brackets, returned ends, etc. plugged	m	11	116.43	1,280.73
186	Regular duty C-profile double curtain steel track for face fixing with 100mm projection including 14 rollers per meter, brackets, stopped ends, etc. plugged	m	11	131.81	1,449.91
187	Heavy duty extruded aluminium double curtain steel track for face fixing with 125mm projection including 14 rollers per meter, brackets, stopped ends, etc. plugged	No	11	147.21	1,619.31
188	Forwin hospital cubicle track 1.0m below soffit including 12 gliders per meter, hangers, brackets, stopped ends, etc. plugged	No	11	224.83	2,473.13
189	Extra for end plugged	No	11	77.61	853.71
190	Extra for bend	No	11	77.61	853.71
191	Extra for joint at bend	No	11	77.61	853.71
<u>BATHROOM FITTINGS</u>					
<u>Halcast or equally approved</u>					
192	20mm Diameter chromium plated curtain or hanging rail 900mm long including end flange brackets Ref 374CH plugged	No	11	260.96	2,870.56
193	20mm Diameter chromium plated towel rail 600mm long including end brackets Ref 261CH plugged	No	11	227.50	2,502.50

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
194	20mm Diameter chromium plated towel rail 900mm long including end brackets Ref 261CH plugged	No	11	343.94	3,783.34
195	Towel ring chromium plated Ref 165CH plugged	No	11	180.67	1,987.37
196	Toilet roll holder chromium plated theft proof Ref 366SCH plugged	No	11	941.37	10,355.07
197	Basket type soap dish chromium plated Ref 377CH	No	11	314.48	3,459.28
	<u>Kwakuhle Hygiene of equal and approved</u>				
198	Lockable and vandal resistant white powder coated metal roll holder Ref TR3W	No	11	941.37	10,355.07
199	Lockable and vandal resistant white powder coated metal roll holder Ref TR2W	No	11	916.32	10,079.52
200	Lockable and vandal resistant white powder coated metal roll holder Ref TR3CH	No	11	963.15	10,594.65
201	Lockable and vandal resistant white powder coated metal roll holder Ref TR2CH	No	11	941.37	10,355.07
202	ABS construction lockable Roll Control Paper Dispenser with viewing window in colour white	No	11	1,104.04	12,144.44
203	ABS construction lockable Reflex Paper Dispenser with viewing window in colour white	No	11	1,104.04	12,144.44
204	ABS construction Wastecare 40litre Multiliner Disposer wall mounted waste bin in colour white	No	11	961.68	10,578.48
205	ABS construction 950ml Soap Dispenser in colour white	No	11	948.68	10,435.48
206	Stainless steel 950ml vandal and theft resistant Soap Dispenser	No	11	1,050.51	11,555.61
	<u>Chairman Industries or equally approved</u>				
207	32mm diameter stainless steel flush valve back rail Ref. No. SR1	No	11	952.81	10,480.91
208	32mm diameter stainless steel cistern back rail Ref. No. SR2	No	11	1,138.82	12,527.02
209	20mm diameter stainless steel door rail 300mm long Ref. No. SR3	No	11	588.81	6,476.91

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
210	32mm diameter stainless steel dog leg side rail Ref. No. DL2	No	11	1,195.02	13,145.22
211	32mm diameter stainless steel dog leg with centre flange side rail Ref. No. DL3	No	11	1,252.58	13,778.38
212	19mm Diameter chromium plated towel rail 500mm long including end brackets plugged	No	11	321.17	3,532.87
213	Bobrick B-4388 Surface mounted lockable multi-roll toilet tissue dispenser plugged	No	11	1,324.84	14,573.24
214	Wall mounted stainless steel dispenser Ref "IW 7015"	No	11	608.89	6,697.79
<u>PADLOCKS</u>					
215	30mm Brass Padlocks with 15mm Hardened Steel Shackle KD, Code: UN333000000000	No	11	179.42	1,973.62
216	30mm Brass Padlocks with 32mm SS Long Shackle KD, Code: UN333002003200	No	11	187.44	2,061.84
217	40mm Brass Padlocks with 20mm Hardened Steel Shackle KD, Code: UN334000000000	No	11	198.16	2,179.76
218	40mm Brass Padlocks with 63mm SS Long Shackle KD, Code: UN334002006300	No	11	238.34	2,621.74
219	50mm Brass Padlocks with 28mm Hardened Steel Shackle KD, Code: UN335000000000	No	11	314.19	3,456.09
220	50mm Brass Padlocks with 63mm SS Long Shackle KD, Code: UN335002006300	No	11	348.11	3,829.21
221	Discus Padlock KD, Code: 400KATD	No	11	153.87	1,692.57
222	78mm Brass Padlocks Concealed Hardened Steel Shackle KD Code: UN337800000000	No	11	712.30	7,835.30
223	Padlock safety lockout device 6 Hole	No	11	99.98	1,099.78
224	Gate Hasp Lock Classic Code: MCHBT-COM	No	11	5,618.68	61,805.48
225	Hercules Padlock3 Keys, B-1K57A	No	11	5,584.42	61,428.62
<u>ESCAPE HARDWARE "EMERGENCY"</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
226	Emergency exit lockset (2 Keys) with striking plate fixed to metal Ref. IW 2032	No	11	702.57	7,728.27
227	Emergency exit lockset (2 Keys) with striking plate fixed to metal Ref. IW 2033	No	11	702.57	7,728.27
228	Panic Latch push bar 900mm Code: J-881-SIL	No	11	3,045.83	33,504.13
229	Panic Latch push bar 1200mm Code: J-881-W-SIL	No	11	3,153.37	34,687.07
230	Panic Latch Touch Bar 900mm Code: J-881T-SIL	No	11	4,549.72	50,046.92
231	Panic Latch push bar 1200mm Code: J-881T-W-SIL	No	11	5,010.32	55,113.52
232	Double panic bolt with pullman Latch Green 1940908NV	No	11	8,258.20	90,840.20
233	Double panic bolt Push bar 900mm Code: J-883-SIL	No	11	8,006.48	88,071.28
234	Double panic bolt Push bar 1200mm Code: J-883-W-SIL	No	11	8,637.59	95,013.49
235	Audible Panic latch alarm exit device Code: 8420RED	No	11	15,189.54	167,084.94
236	Outside access device (OAD) for J-series & Tesa panic devices Lever handle Code: MMPS2SCPL	No	11	1,199.06	13,189.66
237	Outside access device (OAD) for J-series panic devices Lever handle Code: J-885-SIL	No	11	1,301.53	14,316.83
<u>KITCHEN CUPBOARDS</u>					
<u>Duracraft kitchen cupboards or equally approved plugged</u>					
238	Wall cupboard Type WHU300 - 300 x 300 x 800mm high with top, sides, bottom, division, shelf, back and single hinged door	No	11	950.66	10,457.30
239	Wall cupboard Type WHU450 - 450 x 300 x 800mm high with top, sides, bottom, division, shelf, back and single hinged door	No	11	1,032.58	11,358.34
240	Wall cupboard Type WHU525 - 525 x 300 x 800mm high with top, sides, bottom, division, shelf, back and single hinged door	No	11	1,188.34	13,071.70
241	Wall cupboard Type WHU900 - 900 x 300 x 800mm high with top, sides, bottom, division, shelf, back and double hinged doors	No	11	1,690.98	18,600.78

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
242	Wall cupboard Type WHU1200 - 1200 x 300 x 800mm high with top, sides, bottom, division, shelf, back and double hinged doors	No	11	2,063.56	22,699.12
243	Wall cupboard Type WCU525 (corner unit) - 525 x 300 x 800mm high with top, sides, bottom, division, shelf, back and single hinged door	No	11	1,560.91	17,170.03
244	Floor cupboard Type BU300 - 300 x 530 x 875mm high with sides, bottom, division, shelf, and single hinged door (top elsewhere)	No	11	1,411.55	15,527.03
245	Floor cupboard Type BU450 - 450 x 530 x 875mm high with sides, bottom, division, shelf, and single hinged door (top elsewhere)	No	11	1,503.10	16,534.06
246	Floor cupboard Type BU525 - 525 x 530 x 875mm high with sides, bottom, division, shelf, and single hinged door (top elsewhere)	No	11	1,617.12	17,788.32
247	Floor cupboard Type BU900 - 900 x 530 x 875mm high with sides, bottom, division, shelf, and double hinged doors (top elsewhere)	No	11	2,380.70	26,187.70
248	Floor cupboard Type BU1200 - 1200 x 530 x 875mm high with sides, bottom, division, shelf, and double hinged doors (top elsewhere)	No	11	2,857.11	31,428.21
249	Floor cupboard Type BU450/1 - 450 x 530 x 875mm high with sides, bottom, division, shelf, and single hinged door, dividing framework and 1 drawer (top elsewhere)	No	11	1,473.38	16,207.18
250	Floor cupboard Type BU450/4 - 450 x 530 x 875mm high with sides, bottom, division framework and 4 drawer (top elsewhere)	No	11	2,447.60	26,923.60
251	Floor cupboard Type BCU825 (corner unit) - 825 x 530 x 875mm high with sides, bottom, division, shelf, back and double hinged doors	No	11	3,500.80	38,508.80
252	Floor cupboard Type BB450 - 450 x 530 x 2160mm high with top, sides, bottom, division, 2 shelves, back and single hinged door	No	11	3,359.30	36,952.30
253	Sink cupboard Type HSU900 - 900 x 530 x 875mm high with sides, bottom, division, shelf, back and double hinged doors (sink elsewhere)	No	11	3,679.14	40,470.54

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
254	Sink cupboard Type HSU1200 - 1200 x 530 x 875mm high with sides, bottom, division, shelf, back and double hinged doors (sink elsewhere)	No	11	3,478.05	38,258.55
255	Sink cupboard Type HSU1500 (double bowl) - 1500 x 530 x 875mm high with sides, bottom, division, shelf, back and double hinged doors (sink elsewhere)	No	11	5,649.99	62,149.89
256	Extra over kitchen cupboards for Top "T" joints	No	11	82.97	912.67
			11		0.00
257	Extra over kitchen cupboards for filler piece	No	11	80.31	883.41
	<u>Sundries</u>				
258	Sliding drawer rail 600mm long	m	11	83.64	920.04
259	Steel drawer handle	No	11	80.31	883.41
260	PVC drawer handle	No	11	64.90	713.90
261	PVC drawer handle	No	11	64.90	713.90
262	Cast Zinc Cupboard Pull Handle Code: CZ5105CH	No	11	107.06	1,177.66
263	Cast Zinc Cupboard Push Button Catch Code: CZ51741CH	No	11	212.00	2,332.00
264	Cast Zinc Locking Cupboard Catch Code: CZ5174CHKA	No	11	310.86	3,419.46
	<u>Turnstile and Locking Exit Gate</u>				
265	Stainless steel one-way supermarket entrance turnstile	No	11	8,154.30	89,697.30
266	Single locking exit gate for M3501	No	11	17,770.03	195,470.33
267	Service and make good stainless steel one-way supermarket entrance turnstile	No	11	1,284.30	14,127.34
	<u>Infra-red beam system</u>				
268	Infra-red beam system	No	11	13,276.76	146,044.36
	<u>TOILET BINS</u>				
	<u>Stainless steel</u>				
	<u>FRANKE or equally approved</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
269	Half moon wall mounted bin size 330 x 450 x 180mm	No	11	1,915.77	21,073.47
270	Wall mounted 430 grade brushed one piece with internal steel frame inside for disposable liner bin size 415 x 450 x 200mm	No	11	1,225.52	13,480.72
271	Wall mounted 430 grade brushed one piece with internal steel frame inside for disposable liner bin size 310 x 300 x 200mm	No	11	901.54	9,916.94
	Epoxy coated				
	FRANKE or equally approved				
272	Wall mounted mild steel one piece with internal steel frame inside for disposable liner bin size 415 x 450 x 200mm	No	11	1,232.34	13,555.74
273	Wall mounted mild steel one piece with internal steel frame inside for disposable liner bin size 310 x 300 x 200mm	No	11	1,233.89	13,572.79
					3,968,636.80
	SUB-TOTAL (Carried To Summary)				36,915,970.34
	BILL NO. 12				
	METALWORK				
	PREAMBLES				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>SUPPLEMENTARY PREAMBLES</u>				
	<u>Descriptions</u>				
	Descriptions of bolts shall be deemed to include nuts and washers Descriptions of expansion anchors and bolts an chemical anchors and bolts shall be deemed to include nuts, washers and mortises in brickwork or concrete Metalwork described as "holed for bolts(s)" shall be deemed to exclude the bolts unless otherwise described				
	<u>STEEL HANDRAILS, BALUSTRADES, ETC</u>				
	<u>Welded handrail to mild steel</u>				
1	80 x 40 x 2,0mm hollow section continuous rails with flat closed ends welded to bracket, formed of 25mm diameter bar 100mm girth once bent to 50mm internal radius, at approximately 1200mm centres each with 80mm diameter by 6mm thick plate twice holed for bolts	m	2	715.19	1,430.38
2	Extra over 80 x 40 x 2mm hollow section for mitred L-intersection	No	2	33.81	67.62
3	38 x 38 x 2,0mm hollow section continuous rails with flat closed ends welded to bracket, formed of 25mm diameter bar 100mm girth once bent to 50mm internal radius, at approximately 1200mm centres each with 80mm diameter by 6mm thick plate twice holed for bolts	m	2	598.16	1,196.32
4	Extra over 38 x 38 x 2mm hollow section for mitred L-intersection	No	2	27.32	54.64
5	76mm diameter 2,0mm hollow section continuous rails with flat closed ends welded to bracket, formed of 25mm diameter bar 100mm girth once bent to 50mm internal radius, at approximately 1200mm centres each with 80mm diameter by 6mm thick plate twice holed for bolts	m	2	663.18	1,326.36
6	Extra over 76mm pipe rail for bend to 200mm Internal radius	No	2	33.81	67.62
7	38mm diameter 2,0mm hollow section continuous rails with flat closed ends welded to bracket, formed of 25mm diameter bar 100mm girth once bent to 50mm internal radius, at approximately 1200mm centres each with 80mm diameter by 6mm thick plate twice holed for bolts	m	2	598.16	1,196.32

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
8	Extra over 38mm pipe rail for bend to 200mm Internal radius	No	2	27.32	54.64
9	6mm expansion bolt	No	2	14.30	28.60
10	8mm expansion bolt	No	2	16.26	32.52
11	10mm expansion bolt	No	2	18.21	36.42
12	6mm expansion anchor with loose bolt	No	2	18.21	36.42
13	8mm expansion anchor with loose bolt	No	2	20.16	40.32
14	10mm expansion anchor with loose bolt	No	2	22.10	44.20
15	12mm expansion anchor with loose bolt	No	2	24.84	49.68
	<u>Welded balustrading to mild steel</u>				
16	Raking balustrading to staircase or ramp of 80 x 40 x 2mm hollow section continuous top rail, 40 x 10mm flat section continuous bottom rail, 12mm square bar section intermediate balusters at 125mm centres between to and bottom rails and 38 x 38 x 2mm hollow section post at approximately 1200mm centres each with 120 x 50 x 8mm flat section base plate twice holed for bolts	m	2	785.42	1,570.84
			2		0.00
17	Extra over 80 x 40 x 2mm hollow section for mitred L-intersection	No	2	33.81	67.62
18	Raking balustrading to staircase or ramp of 50 x 10mm flat section continuous top rail, 40 x 10mm flat section continuous bottom rail, 12mm square bar section intermediate balusters at 125mm centres between to and bottom rails and 38 x 38 x 2mm hollow section post at approximately 1200mm centres each with 120 x 50 x 8mm flat section base plate twice holed for bolts	m	2	681.39	1,362.78
19	Balustrading of 50 x 10mm flat section continuous top rail, 40 x 10mm flat section continuous bottom rail, 12mm square bar section intermediate balusters at 125mm centres between to and bottom rails and 38 x 38 x 2mm hollow section post at approximately 1200mm centres each with 120 x 50 x 8mm flat section base plate twice holed for bolts	m	2	726.91	1,453.82
20	Extra over 50 x 10mm flat section for mitred L-intersection	No	2	23.40	46.80

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
21	M14mm expansion anchor bolt	No	2	33.81	67.62
22	Vastrap Sheet 3mm	m2	2	950.99	1,901.98
23	Channel 200 x 75mm	m	2	734.50	1,469.00
	<u>SUNDRY STEELWORK</u>				
	<u>Bolts</u>				
24	Bolts(Provisional)	kg	2	136.54	273.08
	<u>Welded balustrading to stainless steel</u>				
	<u>Welded brick (lintel) bearers and framing</u>				
25	Two 80 x 80 x 6mm angle section welded back-to-back with ends build into brickwork	kg	2	2.27	4.54
26	25 x 25 x 2mm Hollow section framing	m	2	60.47	120.94
27	Extra over 25 x 25mm hollow section for mitred L-section	No	2	15.60	31.20
28	76 x 76 x 3.5mm hollow section post with top welded to bearers and bottom welded to and including 150 x 150 x 6mm foot plate four times holed for bolts	m	2	105.34	210.68
	<u>Bearers to brick linings, lintels, etc</u>				
29	100 x 75 x 8mm angle section bearers and holed at 500mm centres for bolting to concrete	m	2	239.26	478.52
30	100 x 75 x 8mm angle section bearers with 130 x 50 x 8mm flat section brackets welded on at 500mm centres and once holed for bolting to concrete	m	2	267.86	535.72
31	M12/60L expansion bolt	m	2	33.81	67.62
	<u>Corner protectors</u>				
32	60 x 60 x 6mm angle section corner protectors in varying lengths twice screwed to brickwork of concrete a 500mm centres	m	2	124.84	249.68
33	40 x 40 x 2mm angle section corner protectors in varying lengths twice screwed to brickwork of concrete a 500mm centres	m	2	99.86	199.72

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Welded guard, bump rails, etc</u>				
34	80 x 40 x 2,0mm hollow section continuous rails with flat closed ends welded to bracket, formed of 25mm diameter bar 100mm girth once bent to 50mm internal radius, at approximately 1200mm centres each with 80mm diameter by 6mm thick plate twice holed for bolts	m	2	304.28	608.56
35	Extra over 80 x 40 x 2mm hollow section for mitred L-intersection	No	2	33.81	67.62
	<u>Sundries</u>				
36	Repair chromium plated lifesaver's chair	No	2	1,748.33	3,496.66
	<u>Welded bearers to benches, spectators seating, etc</u>				
37	80 x 40 x 2,0mm hollow section continuous rails with flat closed ends welded to bracket, formed of 25mm diameter bar 100mm girth once bent to 50mm internal radius, at approximately 1200mm centres each with 80mm diameter by 6mm thick plate twice holed for bolts	m	2	304.28	608.56
38	Extra over 80 x 40 x 2mm hollow section for mitred L-intersection	No	2	33.81	67.62
39	70 x 70 x6mm Angle section cleat three times holed and bolted to brickwork or concrete at 300mm centres	m	2	105.34	210.68
40	Extra over 80 x 40 x 2mm hollow section for mitred L-intersection	No	2	33.81	67.62
41	70 x 70 x6mm Angle section cleat three times holed and bolted to brickwork or concrete at 300mm centres	m	2	105.34	210.68
	<u>Welded framing to benches, spectators seating, etc</u>				
42	70 x 70 x6mm Angle section cleat three times holed and bolted to brickwork or concrete at 300mm centres	m	2	105.34	210.68
	<u>Welded bracing etc with flat section connecting plates bolted to steel</u>				
43	80 x 40 x 2,0 hollow section continuous bracing with flat section connecting plate 100 x 100 x 2,0 mm bolted to steel	m	2	304.28	608.56

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>WELDED SCREENS, GATES, ETC</u>				
	<u>Screens and gates to doors</u>				
44	50 x 76 x 3.5mm Hollow section framing	m	2	105.34	210.68
45	Extra over 50 x 76mm hollow section for mitred and welded L-intersection	m	2	105.34	210.68
46	Hole through 50 x 76mm hollow section	No	2	5.84	11.68
47	100mm M10 expansion bolt in brickwork	No	2	33.81	67.62
48	Single gate 810 x 2066mm high of 50 x 50 x 2,5mm hollow section frame and two 50 x 50 x 2,5mm hollow section horizontal middle rails filled in with 20mm diameter solid vertical round bars at 89mm centres framed through middle rails and into framing and fitted with three suitable hinges welded to post and a "Union" LX 3261 security gate lock box between middle rails	No	2	2,353.63	4,707.26
49	Double gate with two single leaves 1620 x 2066mm high of 50 x 50 x 2,5mm hollow section frame and two 50 x 50 x 2,5mm hollow section horizontal middle rails filled in with 20mm diameter solid vertical round bars at 89mm centres framed through middle rails and into framing and fitted with six suitable hinges welded to posts and a "Union" LX 3261 security gate lock box between middle rails including conversion set.	No	2	4,707.28	9,414.56
50	Steel wire expanded mesh burglar proofing not exceeding 1,0m ² bolted to brickwork	No	2	1,534.41	3,068.82
51	Steel wire expanded mesh burglar proofing exceeding 1,0m ² and not exceeding 2,0m ² bolted to brickwork	No	2	1,885.52	3,771.04
52	Steel wire mesh burglar proofing exceeding 2,0m ² and not exceeding 3,0m ² bolted to brickwork	No	2	2,353.63	4,707.26
53	Steel round, square, etc burglar proofing not exceeding 1,0m ² bolted to brickwork	No	2	1,534.41	3,068.82
54	Steel round, square, etc burglar proofing exceeding 1,0m ² and not exceeding 2,0m ² bolted to brickwork	No	2	1,885.52	3,771.04
55	Steel round, square, etc burglar proofing exceeding 2,0m ² and not exceeding 3,0m ² bolted to brickwork	No	2	2,353.63	4,707.26

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
56	Steel round, square, etc burglar proofing not exceeding 1,0m ² welded to brickwork	No	2	1,534.41	3,068.82
57	Steel round, square, etc burglar proofing exceeding 1,0m ² and not exceeding 2,0m ² welded to brickwork	No	2	1,885.52	3,771.04
58	Steel round, square, etc burglar proofing exceeding 2,0m ² and not exceeding 3,0m ² welded to brickwork	No	2	2,353.63	4,707.26
59	Steel round, square, etc burglar proofing, perimeter fencing, 1800mm high welded to steel	No	2	1,722.98	3,445.96
60	Steel round, square, etc burglar proofing, perimeter fencing, 2100mm high welded to steel	No	2	1,895.27	3,790.54
<u>RETRACTABLE SECURITY GATES AND SCREENS</u>					
<u>TRELLIDOR or equally approved installed by a Trellidor installer for a 5-year warranty on workmanship and hardware</u>					
61	Security "slam lock" gate size 900 x 2032mm high	No	2	5,560.96	11,121.92
62	Security "slam lock" gate size 1150 x 2032mm high	No	2	7,278.53	14,557.06
63	Security "slam lock" gate size 1300 x 2032mm high	No	2	7,725.08	15,450.16
64	Security screen to openings not exceeding 5m ²	No	2	3,196.23	6,392.46
65	Security screen to openings exceeding 5m ² not exceeding 10m ²	m ²	2	3,392.32	6,784.64
<u>Making good screens and gates to doors, etc.</u>					
66	Single gate 810 x 2066mm high of 50 x 50 x 2,5mm hollow section frame and two 50 x 50 x 2,5mm hollow section horizontal middle rails filled in with 20mm diameter solid vertical round bars at 89mm centres framed through middle rails and into framing and fitted with three suitable hinges welded to post and a "Union" LX 3261 security gate lock box between middle rails	No	2	588.41	1,176.82

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
67	Double gate with two single leaves 1620 x 2066mm high of 50 x 50 x2,5mm hollow section frame and two 50 x 50 x 2,5mm hollow section horizontal middle rails filled in with 20mm diameter solid vertical round bars at 89mm centres framed through middle rails and into framing and fitted with six suitable hinges welded to posts and a "Union" LX 3261 security gate lock box between middle rails including conversion set.	No	2	1,176.81	2,353.62
68	Burglar proofing 2066mm high of 50 x 50 x2,5mm hollow section frame and two 50 x 50 x 2,5mm hollow section horizontal middle rails filled in with 20mm diameter solid vertical round/square bars at 89mm centres framed through middle rails and into framing and bolted to brickwork, concrete, etc.	No	2	588.41	1,176.82
69	Steel wire mesh burglar proofing	m2	2	367.76	735.52
	<u>PRESSED STEEL DOOR FRAMES</u>				
	<u>1,2mm Rebated frame suitable for half brick wall</u>				
70	Frame for door size 762 x 2032mm high	No	2	507.14	1,014.28
71	Frame for door size 813 x 2032mm high	No	2	507.14	1,014.28
72	Frame for door size 900 x 2032mm high	No	2	561.76	1,123.52
73	Frame for double door size 1359 x 2032mm high	No	2	573.45	1,146.90
74	Frame for double door size 1511 x 2032mm high	No	2	585.16	1,170.32
75	Frame for double door size 1613 x 2032mm high	No	2	585.16	1,170.32
	<u>1,2mm Rebated frame suitable one brick wall</u>				
76	Frame for door size 762 x 2032mm high	No	2	722.99	1,445.98
77	Frame for door size 813 x 2032mm high	No	2	722.99	1,445.98
78	Frame for door size 900 x 2032mm high	No	2	798.42	1,596.84
79	Frame for double door size 1359 x 2032mm high	No	2	814.03	1,628.06
80	Frame for double door size 1511 x 2032mm high	No	2	830.92	1,661.84
81	Frame for double door size 1613 x 2032mm high	No	2	830.92	1,661.84

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>PRESSED STEEL CUPBOARD DOOR FRAMES</u>				
	<u>Standard cupboard door frame</u>				
82	Frame for door size 762 x 2032mm high	No	2	470.72	941.44
83	Frame for door size 1511 x 2032mm high	No	2	543.55	1,087.10
	<u>STEEL WINDOWS, DOORS, ETC.</u>				
	<u>Standard residential windows with 10mm diameter mild steel burglar bars to opening sashes</u>				
84	Window type NE1 size 533 x 654mm high	No	2	464.23	928.46
85	Window type NE2 size 1022 x 654mm high	No	2	634.58	1,269.16
86	Window type NE4 size 1511 x 654mm high	No	2	1,020.77	2,041.54
87	Window type NE11 size 2000 x 654mm high	No	2	1,101.39	2,202.78
88	Window type E1H size 533 x 654mm high	No	2	491.53	983.06
89	Window type E2H size 1022 x 654mm high	No	2	686.58	1,373.16
90	Window type E4H size 1511 x 654mm high	No	2	1,097.50	2,195.00
91	Window type E22 size 2000 x 654mm high	No	2	1,235.33	2,470.66
92	Window type NC1 size 533 x 949mm high	No	2	603.37	1,206.74
93	Window type NC2 size 1022 x 949mm high	No	2	821.83	1,643.66
94	Window type NC4 size 1511 x 949mm high	No	2	1,345.86	2,691.72
95	Window type NC11 size 2000 x 949mm high	No	2	1,431.68	2,863.36
96	Window type C1H size 533 x 949mm high	No	2	656.68	1,313.36
97	Window type C2H size 1022 x 949mm high	No	2	923.25	1,846.50
98	Window type C4H size 1511 x 949mm high	No	2	1,499.31	2,998.62
99	Window type ND1 size 533 x 1245mm high	No	2	690.49	1,380.98
100	Window type ND2 size 1022 x 1245mm high	No	2	955.76	1,911.52

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
101	Window type ND4 size 1511 x 1245mm high	No	2	1,555.22	3,110.44
102	Window type ND11 size 2000 x 1245mm high	No	2	1,659.25	3,318.50
103	Window type D1H size 533 x 1245mm high	No	2	765.90	1,531.80
104	Window type D2H size 1022 x 1245mm high	No	2	1,110.50	2,221.00
105	Window type D4H size 1511 x 1245mm high	No	2	1,790.58	3,581.16
106	Window type NCT1S size 533 x 949mm high	No	2	948.74	1,897.48
107	Window type NCTX7S size 1022 x 949mm high	No	2	1,236.00	2,472.00
108	Window type NCTX7S5 size 1511 x 949mm high	No	2	1,236.00	2,472.00
109	Window type TD7 size 1022 x 1245mm high	No	2	1,136.50	2,273.00
110	Window type TD75 size 1511 x 1245mm high	No	2	1,420.00	2,840.00
111	Window type TD57S8 size 2000 x 1559mm high	No	2	1,655.35	3,310.70
	<u>Standard medium universal doors, sidelights, etc</u>		2		0.00
112	Sidelight Type NSDAS, 800 x 2134mm high	No	2	985.65	1,971.30
113	Door Type NDAS, 800 x 2134mm high	No	2	2,864.67	5,729.34
114	Double door Type NDDA, 1524 x 2134mm high	No	2	4,596.73	9,193.46
115	Sidelight Type SDASH, 800 x 2134mm high	No	2	1,167.73	2,335.46
116	Door Type DASH, 800 x 2134mm high	No	2	3,153.36	6,306.72
117	Double door Type DDAH, 1524 x 2134mm high	No	2	4,800.91	9,601.82
	<u>Combination doors and frames</u>				
118	Door and frame size 813 x 2032mm. high	No	2	2,418.67	4,837.34
119	Door and frame size 1626 x 2032mm. high	No	2	4,362.10	8,724.20
	<u>ALUMINIUM SHOPFRONTS COMPLETE WITH GLAZING, HANDLES AND ALL ACCESSORIES</u>				
	<u>SLIDING FOLDING DOORS</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
120	4500-4800 x 2100mm Aluminium Folding door (Toughened Safety Glass) - 5 Panel	No	2	24,187.98	48,375.96
121	4500-4800 x 2700mm Aluminium Folding door (Toughened Safety Glass) - 5 Panel	No	2	26,616.77	53,233.54
122	5400-5700 x 2100mm Aluminium Folding door (Toughened Safety Glass) - 5 Panel	No	2	28,962.76	57,925.52
123	5400-5700 x 2700mm Aluminium Folding door (Toughened Safety Glass) - 5 Panel	No	2	30,851.37	61,702.74
124	5400-5700 x 2100mm Aluminium Folding door (Toughened Safety Glass) - 5 Panel	No	2	31,650.17	63,300.34
125	5400-5700 x 2700mm Aluminium Folding door (Toughened Safety Glass) - 5 Panel	No	2	33,805.52	67,611.04
126	6300-6600 x 2100mm Aluminium Folding door (Toughened Safety Glass) - 5 Panel	No	2	35,402.81	70,805.62
127	6300-6600 x 2700mm Aluminium Folding door (Toughened Safety Glass) - 5 Panel	No	2	37,014.76	74,029.52
<u>ALUMINIUM SLIDING DOORS</u>					
128	1800 x 2100 Aluminium sliding door (Standard 5mm glass) - Double Leaf	No	2	8,459.43	16,918.86
129	2400 x 2100 Aluminium sliding door (Standard 5mm glass) - Double Leaf	No	2	10,002.31	20,004.62
130	3000 x 2100 Aluminium sliding door (Standard 5mm glass) - Double Leaf	No	2	12,300.03	24,600.06
131	1800 x 2400 Aluminium sliding door (Safety glass) - Double Leaf	No	2	14,884.48	29,768.96
132	2400 x 2400 Aluminium sliding door (Safety glass) - Double Leaf	No	2	17,656.18	35,312.36
133	3000 x 2400 Aluminium sliding door (Safety glass) - Double leaf	No	2	20,420.06	40,840.12
134	3600 x 2400 Aluminium sliding door (Safety glass) - Four Leaf	No	2	29,357.38	58,714.76
135	4200 x 2400 Aluminium sliding door (Safety glass) - Four Leaf	No	2	32,105.67	64,211.34
136	6000 x 2400 Aluminium sliding door (Safety glass) - Four leaf	No	2	40,565.12	81,130.24

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
<u>ALUMINIUM PANE DOORS</u>					
137	900 x 2100 Aluminium Single Door (Safety Glass) - Single leaf	No	2	10,491.18	20,982.36
138	1800 x 2100 Aluminium Double Door (Safety Glass) - Double leaf	No	2	19,472.12	38,944.24
139	900 x 2400 Aluminium Single Door (Safety Glass) - Single leaf	No	2	10,764.15	21,528.30
140	1800 x 2400 Aluminium Double Door (Safety Glass) - Double leaf	No	2	20,650.58	41,301.16
<u>ALUMINIUM HINGE DOORS WITH MIDRAIL</u>					
141	900 x 2100 Aluminium Hinge Door (Safety Glass) - Single leaf	No	2	10,491.18	20,982.36
142	1800 x 2100 Aluminium Hinge Double Door (Safety Glass) - Double leaf	No	2	19,472.12	38,944.24
143	900 x 2400 Aluminium Hinge Door (Safety Glass) - Single leaf	No	2	10,764.15	21,528.30
144	1800 x 2400 Aluminium Hinge Double Door (Safety Glass) - Double leaf	No	2	20,650.58	41,301.16
<u>ALUMINIUM SIDELIGHTS</u>					
145	600 x 2100 Aluminium Sidelight (Safety Glass) - Large Pane	No	2	7,404.20	14,808.40
146	900 x 2100 Aluminium Sidelight (Safety Glass) - Large Pane	No	2	7,975.71	15,951.42
147	600 x 2400 Aluminium Sidelight (Safety Glass) - Large Pane	No	2	8,461.39	16,922.78
148	900 x 2400 Aluminium Sidelight (Safety Glass) - Large Pane	No	2	9,116.76	18,233.52
149	600 x 2100 Aluminium Sidelight (Safety Glass) - With Midrail	No	2	8,406.78	16,813.56
150	900 x 2100 Aluminium Sidelight (Safety Glass) - With Midrail	No	2	9,333.26	18,666.52
151	600 x 2400 Aluminium Sidelight (Safety Glass) - With Midrail	No	2	16,261.53	32,523.06
152	900 x 2400 Aluminium Sidelight (Safety Glass) - With Midrail	No	2	17,699.09	35,398.18
153	600 x 2100 Aluminium Sidelight (Safety Glass) - With Vents	No	2	9,766.29	19,532.58
154	900 x 2100 Aluminium Sidelight (Safety Glass) - With Vents	No	2	10,704.49	21,408.98
155	600 x 2400 Aluminium Sidelight (Safety Glass) - With Vents	No	2	11,147.27	22,294.54

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
156	900 x 2400 Aluminium Sidelight (Safety Glass) - With Vents	No	2	12,118.62	24,237.24
	<u>ALUMINIUM WINDOWS</u>				
157	600 x 600 Aluminium Window, Code: PT66(A3) - Top Hung Casement window	No	2	2,421.25	4,842.50
158	900 x 600 Aluminium Window, Code: PT96(A3) - Top Hung Casement window	No	2	2,961.94	5,923.88
159	1200 x 600 Aluminium Window, Code: PT126(A3) - Top Hung Casement window	No	2	3,517.20	7,034.40
160	600 x 900 Aluminium Window, Code: PT69(A3) - Top Hung Casement window	No	2	3,167.65	6,335.30
161	900 x 900 Aluminium Window, Code: PT99(A3) - Top Hung Casement window	No	2	3,930.43	7,860.86
162	1500 x 900 Aluminium Window, Code: PT159(A3) - Top Hung Casement window	No	2	4,957.20	9,914.40
163	1800 x 1200 Aluminium Window, Code: PTT1812(A1) - Top Hung Casement window	No	2	7,890.03	15,780.06
164	1800 x 1500 Aluminium Window, Code: PTT1815(A3) - Top Hung Casement window	No	2	8,610.92	17,221.84
165	1800 x 1800 Aluminium Window, Code: DPTT1818(A3) - Top Hung Casement window	No	2	13,828.46	27,656.92
166	2100 x 1200 Aluminium Window, Code: PTT2112(A1) - Top Hung Casement window	No	2	6,182.39	12,364.78
167	2100 x 1500 Aluminium Window, Code: PTT2115(A3) - Top Hung Casement window	No	2	7,600.55	15,201.10
168	2400 x 1500 Aluminium Window, Code: PTT2415(A3) - Top Hung Casement window	No	2	8,439.79	16,879.58
169	2400 x 1200 Aluminium Window, Code: DPTT2412(A1) - Top Hung Casement window	No	2	8,645.52	17,291.04
170	1200 x 900 Aluminium Window, Code: SH129 - Side Hung Casement window	No	2	3,517.20	7,034.40

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
171	1500 x 900 Aluminium Window, Code: SH159 - Side Hung Casement window	No	2	3,857.63	7,715.26
172	1800 x 1200 Aluminium, Code: SH1812 - Side Hung Casement window	No	2	5,011.82	10,023.64
173	2100 x 1200 Aluminium, Code: SHH2112 - Side Hung Casement window	No	2	7,129.04	14,258.08
174	1200 x 600 Aluminium, Code: HS126 - Horizontal Sliding window	No	2	3,549.96	7,099.92
175	1200 x 900 Aluminium, Code: HS129 - Horizontal Sliding window	No	2	4,052.42	8,104.84
176	1200 x 1200 Aluminium, Code: HS1212 - Horizontal Sliding window	No	2	4,562.16	9,124.32
177	1800 x 600 Aluminium, Code: HS186 - Horizontal Sliding window	No	2	4,516.65	9,033.30
178	1800 x 900 Aluminium, Code: HS189 - Horizontal Sliding window	No	2	5,091.92	10,183.84
179	1800 x 1200 Aluminium, Code: HS1812 - Horizontal Sliding window	No	2	5,665.37	11,330.74
180	2400 x 900 Aluminium, Code: HS249X - Horizontal Sliding window	No	2	7,560.50	15,121.00
181	2400 x 1200 Aluminium, Code: HS2412X - Horizontal Sliding window	No	2	8,501.70	17,003.40
182	900 x 900 Aluminium, Code: VS99 - Vertical Sliding window	No	2	4,802.46	9,604.92
183	900 x 1200 Aluminium, Code: VS912 - Vertical Sliding window	No	2	5,294.00	10,588.00
184	900 x 1500 Aluminium, Code: VS915 - Vertical Sliding window	No	2	5,854.70	11,709.40
185	900 x 1800 Aluminium, Code: VS918 - Vertical Sliding window	No	2	6,770.41	13,540.82
186	1200 x 1200 Aluminium, Code: VS1212 - Vertical Sliding window	No	2	6,073.16	12,146.32
187	1200 x 1800 Aluminium, Code: VS1218 - Vertical Sliding window	No	2	7,793.52	15,587.04
188	900 x 2100 Aluminium, Code: VS912S9 - Vertical Sliding window	No	2	7,919.13	15,838.26

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
189	1200 x 2100 Aluminium, Code: VS1212S9 - Vertical Sliding window	No	2	9,186.19	18,372.38
	<u>STEEL ROLLER SHUTTERS ETC</u>				
	<u>Galvanised roller shutters fixed to brickwork or concrete</u>				
190	Manual pushup 76mm slatted roller shutter for 2440 x 2135mm high opening	No	2	4,652.66	9,305.32
191	Manual pushup 76mm slatted roller shutter for 3000 x 2440mm high opening	No	2	6,154.56	12,309.12
	<u>Galvanized chain operated industrial roller shutter door with 75mm slats</u>				
192	2750 x 2500mm High door	No	2	16,063.24	32,126.48
	<u>Pre-painted Chromadek roller shutters fixed to brickwork or concrete</u>				
193	Manual push-up 76mm slatted roller shutter for 2440 x 2135mm high opening	No	2	5,402.97	10,805.94
194	Manual pushup 76mm slatted roller shutter for 3000 x 2440mm high opening	No	2	7,205.24	14,410.48
195	Extra over manual pushup roller shutter for electrically operated complete with one transmitter and battery back-up	No	2	3,885.45	7,770.90
	<u>GRILLES</u>				
	<u>Aluminium grilles</u>				
196	Grille size 400 x 300mm high	No	2	552.65	1,105.30
	<u>Mild Steel grilles</u>				
197	Grille size 400 x 300mm high	No	2	552.65	1,105.30
198	Grille size 600 x500mm high	No	2	837.43	1,674.86
	<u>Gratings</u>				
	<u>Galvanised steel</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
199	Open Ended System Mentis rectagrid grating size 3000x1000mm cut out where required to permit pipes, etc to pass through and bolted to concrete where required to permit pipes, etc to pass through and bolted to concrete surface bed	No	2	5,055.11	10,110.22
	<u>Swimming Pool Ladder</u>				
	<u>Stainless Steel</u>				
200	48mm Diameter, 500mm long stub pipe cast in concrete base, flush with paving for pool ladder stability	No	2	143.05	286.10
201	50mm Diameter dog-leg hollow chromium plated tube, 2.5mm thick three steps ladder with 132mm diameter, 5mm thick solid flange, twice holed and welded to top end of ladder.	No	2	10,335.63	20,671.26
	<u>STARTING BLOCKS</u>				
	<u>Stainless Steel</u>				
202	Stainless steel "Grade 316" starting block	No	2	18,886.77	37,773.54
	<u>Fibreglass</u>				
203	Fibreglass starting block	No	2	2,106.57	4,213.14
	<u>Nameboards</u>				
204	2500 x 1800 x 8mm Chromadek nameboard mounted to 50 x 50mm welded frame mounted on 2 x 75 x 3mm diameter hollow tube, with overall height of 2500mm, 500mm bottom ends cast into and including 15MPa concrete footing in ground, including excavation, ramming, removal of spoil and leaving clean and neat.	No	2	10,792.92	21,585.84
	<u>Lifesaver's Chair</u>				
	<u>Stainless Steel</u>				
205	38mm Diameter tubular framework 2900mm overall height with plastic seat, overhead shade, platform and treads and rubber feet for ease of movement	No	2	3,501.85	7,003.70
206	Three seater 1800 pool shade gazebo	No	2	4,096.11	8,192.22
	<u>STEEL LOCKERS</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Krost or equally approved</u>				
	<u>Epoxy coated</u>				
207	18kg Single compartment unit size 1800 x 300 x 450m	No	2	778.91	1,557.82
208	19kg Two compartment unit size 1800 x 300 x 450m	No	2	877.74	1,755.48
	<u>STRUCTURAL STEEL COMPONENTS</u>				
209	Columns, comprising channels welded to form box sections	t	2	30,428.22	60,856.44
210	In roof trusses-sop primed lattice	t	2	30,428.22	60,856.44
211	In purlins of cold formed lipped Z sections	t	2	30,428.22	60,856.44
212	In bracing	t	2	30,428.22	60,856.44
213	Tubular welded roof trusses	t	2	30,428.22	60,856.44
	<u>TABLES</u>				
	<u>Stainless Steel</u>				
214	Vulcan or equally approved	No	2		
215	Model "SWB 1650" table with splashback	No	2	5,544.18	11,088.36
216	Model "SWB 1840" table with splashback	No	2	6,375.64	12,751.28
	<u>WASHING LINES</u>				
217	4 x 8m lines Retractable or equivalent Mounted Washing Line wall mounted both sides	No	2	1,545.70	3,091.40
218	Compact Wall Mounted Washing line	No	2	2,649.78	5,299.56
219	Rotating Washing Line not exceeding 3m radius	No	2	3,526.91	7,053.82
220	2,0 m long Rectangular washing line 2m high off ground, made up of 2no x 2,4m (L)75mm dia galvanised steel post forming a "T" 600mm (W) cast in concrete, with 4no strains of 3mm straining wire or skie rope	No	2	3,950.13	7,900.26

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
221	4,0 m long Rectangular washing line 2m high off ground, made up of 2no x 2,4m (L)75mm dia galvanised steel post forming a "T" 600mm (W) cast in concrete, with 4no strains of 3mm straining wire or skie rope	No	2	5,925.18	11,850.36
					2,600,932.82

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
					39,516,903.16
	SUB-TOTAL <i>(Carried To Summary)</i>				
	<u>BILL NO. 13</u>				
	<u>PLASTERING</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>SCREEDS</u>				
	<u>Cement screeds wood floated on concrete</u>				
1	25mm thick on floors and landings	m2	9	91.03	819.27
2	Average 40mm thick on floors to falls	m2	9	137.83	1,240.47
3	Average 40mm thick on floors to falls and currents	m2	9	137.83	1,240.47
4	25mm thick treads and risers of stairs	m2	9	96.23	866.07
	<u>Cement screeds steel floated on concrete</u>				
5	25mm thick on floors and landings	m2	9	91.03	819.27
6	Average 40mm thick on floors to falls	m2	9	137.83	1,240.47
7	Average 40mm thick on floors to falls and currents	m2	9	137.83	1,240.47
8	25mm thick treads and risers of stairs	m2	9	96.23	866.07
	<u>Repairing superficial cracks in cement screeds on concrete or brick surfaces not exceeding 1mm wide by opening cracks, preparing and applying a suitable thick slurry finishing flush to match existing (floor finishers where applicable measured elsewhere)</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
9	On horizontal top surfaces	m	9	7.80	70.20
10	On vertical surfaces	m	9	7.80	70.20
11	On treads and risers of stairs	m	9	9.11	81.99
	<u>Repairing cracks in cement screeds on concrete or brick surfaces exceeding 1mm wide by hacking up/off screeds 150mm wide on both sides of crack, preparing existing surface and laying new screeds on and including chicken mesh spiked to base finishing flush with existing surface to match existing</u>				
12	On horizontal top surfaces	m	9	41.62	374.58
13	On vertical surfaces	m	9	41.62	374.58
14	On treads and risers of stairs	m	9	42.91	386.19
	<u>GRANOLITHIC</u>				
	<u>Untinted granolithic on concrete</u>				
15	25mm thick on floors and landings	m2	9	96.23	866.07
16	Average 40mm thick on floors to falls	m2	9	144.34	1,299.06
17	Average 40mm thick on floors to falls and currents	m2	9	144.34	1,299.06
18	25mm thick treads and risers of stairs	m2	9	101.43	912.87
19	25mm thick treads and risers of stairs including reeding	m2	9	115.73	1,041.57
20	25mm thick on narrow widths	m2	9	96.23	866.07
21	Skirting 75mm high	m	9	13.01	117.09
22	Skirting 75mm high stepped over treads and risers	m	9	19.50	175.50
23	Skirting 75mm high average 150mm high racked over treads and risers	m	9	24.70	222.30
	<u>Repairing superficial cracks in untinted granolithic screeds on concrete or brick surfaces not exceeding 1mm wide by opening cracks, preparing and applying a suitable thick slurry finishing flush to match existing</u>				
24	On horizontal top surfaces	m	9	7.80	70.20

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
25	On vertical surfaces	m	9	7.80	70.20
26	On treads and risers of stairs	m	9	9.11	81.99
	<u>Repairing cracks in untinted granolithic screeds on concrete or brick surfaces exceeding 1mm wide by hacking up/off screeds 150mm wide on both sides of crack, preparing existing surface and laying new screeds on and including chicken mesh spiked to base finishing flush with existing surface to match existing</u>				
27	On horizontal top surfaces	m	9	42.91	386.19
28	On vertical surfaces	m	9	42.91	386.19
29	On treads and risers of stairs	m	9	44.21	397.89
	<u>Sundries</u>				
30	Fix in position steel/uPVC underfloor cable duct 150 x 30mm deep overall including levelling by means of wedges and mortar packing, securing in position whilst screeding and working screed around and under duct and junction boxes, to finish levels with floor finish	m	9	63.72	573.48
	<u>INTERNAL PLASTER</u>				
	<u>Two coat cement plaster with gypsum finish on brickwork/concrete</u>				
31	On walls	m2	9	102.74	924.66
32	On walls in sunk/raised panels	m2	9	107.93	971.37
33	On walls between timber grounds (area of grounds not deducted)	m2	9	107.93	971.37
34	On circular walls	m2	9	102.74	924.66
35	On narrow widths	m2	9	102.74	924.66
	<u>Cement plaster steel trowelled on brickwork/concrete</u>				
36	On walls	m2	9	70.23	632.07
37	On walls in sunk/raised panels	m2	9	74.12	667.08

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
38	On walls between timber grounds (area of grounds not deducted)	m2	9	74.12	667.08
39	On circular walls	m2	9	70.23	632.07
40	On narrow widths	m2	9	70.23	632.07
41	On ceilings	m2	9	79.33	713.97
42	On raking soffits of stairs	m2	9	79.33	713.97
43	On projecting and isolated columns/beams	m2	9	70.23	632.07
	<u>Cement plaster wood floated on brickwork/concrete</u>				
44	On walls	m2	9	70.23	632.07
45	On walls in sunk/raised panels	m2	9	74.12	667.08
46	On walls between timber grounds (area of grounds not deducted)	m2	9	74.12	667.08
47	On circular walls	m2	9	70.23	632.07
48	On narrow widths	m2	9	70.23	632.07
49	On ceilings	m2	9	79.33	713.97
50	On raking soffits of stairs	m2	9	79.33	713.97
51	On projecting and isolated columns/beams	m2	9	70.23	632.07
	<u>Fine rough-cast plaster on brickwork/concrete</u>				
52	On walls	m2	9	70.23	632.07
53	On walls in sunk/raised panels	m2	9	74.12	667.08
54	On walls between timber grounds (area of grounds not deducted)	m2	9	74.12	667.08
55	On circular walls	m2	9	70.23	632.07
56	On narrow widths	m2	9	70.23	632.07
57	On ceilings	m2	9	79.33	713.97

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
58	On raking soffits of stairs	m2	9	79.33	713.97
59	On projecting and isolated columns/beams	m2	9	70.23	632.07
	<u>Repairing cracks in internal cement plaster on concrete or brick surfaces exceeding 1mm wide by hacking off plaster 150mm wide on both sides of crack, preparing existing surface and applying new plaster on and including chicken mesh spiked to base finishing flush with existing surface (painting measured elsewhere)</u>				
60	On horizontal top surfaces	m	9	36.40	327.60
61	On sloping top surfaces	m	9	36.40	327.60
62	On vertical surfaces	m	9	36.40	327.60
63	On vertical surfaces circular	m	9	36.40	327.60
64	On horizontal soffits	m	9	37.70	339.30
65	On horizontal soffits circular	m	9	37.70	339.30
66	On raking soffits	m	9	37.70	339.30
	<u>EXTERNAL PLASTER</u>				
	<u>Cement plaster on brickwork/concrete</u>				
67	On walls	m2	9	76.73	690.57
68	On walls in sunk/raised panels	m2	9	81.92	737.28
69	On walls between timber grounds (area of grounds not deducted)	m2	9	81.92	737.28
70	On circular walls	m2	9	76.73	690.57
71	On narrow widths	m2	9	76.73	690.57
72	On ceilings	m2	9	87.12	784.08
73	On raking soffits of stairs	m2	9	87.12	784.08
74	On projecting and isolated columns/beams	m2	9	76.73	690.57
	<u>Rough-cast plaster on brickwork/concrete</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
75	On walls	m2	9	76.73	690.57
76	On walls in sunk/raised panels	m2	9	81.92	737.28
77	On walls between timber grounds (area of grounds not deducted)	m2	9	81.92	737.28
78	On circular walls	m2	9	76.73	690.57
79	On narrow widths	m2	9	76.73	690.57
80	On ceilings	m2	9	87.12	784.08
81	On raking soffits of stairs	m2	9	87.12	784.08
82	On projecting and isolated columns/beams	m2	9	76.73	690.57
	<u>Repairing cracks in external cement plaster on concrete or brick surfaces exceeding 1mm wide by hacking off plaster 150mm wide on both sides of crack, preparing existing surface and applying new plaster on and including chicken mesh spiked to base finishing flush with existing surface (painting measured elsewhere)</u>				
83	On horizontal top surfaces	m	9	39.01	351.09
84	On sloping top surfaces	m	9	39.01	351.09
85	On vertical surfaces	m	9	39.01	351.09
86	On vertical surfaces circular	m	9	39.01	351.09
87	On horizontal soffits	m	9	40.31	362.79
88	On horizontal soffits circular	m	9	40.31	362.79
89	On raking soffits	m	9	40.31	362.79
	<u>SPECIALIST PLASTER WALL COVERINGS</u>				
	All specialist plaster wall coverings are to be executed in strict accordance with the manufacturer's instructions				
	<u>Gamma Zenith or equal and approved 2,5mm thick "Striato Medium" pure acrylic plasticised coating with trowel on finish on plaster</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
90	On walls	m2	9	76.73	690.57
91	On walls in sunk/raised panels	m2	9	80.62	725.58
92	On walls between timber grounds (area of grounds not deducted)	m2	9	80.62	725.58
93	On circular walls	m2	9	76.73	690.57
94	On narrow widths	m2	9	76.73	690.57
95	On ceilings	m2	9	89.72	807.48
96	On raking soffits of stairs	m2	9	89.72	807.48
97	On projecting and isolated columns/beams	m2	9	76.73	690.57
	<u>Repairing cracks in "Gumma Zenith" or equal and approved 2,5mm thick</u> <u>"Striato Medium" pure acrylic plasticised coating with trowel on finish</u> <u>on plastered concrete or brick surfaces exceeding 1mm wide by</u> <u>carefully cutting out in sections using straight horizontal and/or vertical</u> <u>saw cuts, hacking up/off and removing plaster 150mm wide on both</u> <u>sides of crack, preparing existing surface and applying new cement</u> <u>plaster on and including chicken mesh spiked to base, and finishing</u> <u>flush with "Gamma Zenith" covering to match existing surface</u>				
98	On horizontal top surfaces	m	9	54.62	491.58
99	On sloping top surfaces	m	9	54.62	491.58
100	On vertical surfaces	m	9	54.62	491.58
101	On vertical surfaces circular	m	9	54.62	491.58
102	On horizontal soffits	m	9	61.11	549.99
103	On horizontal soffits circular	m	9	61.11	549.99
104	On raking soffits	m	9	61.11	549.99
	<u>Gamma Zenith or equal and approved 3,0mm thick "Granitico" pure</u> <u>acrylic plasticised coating with stone finish on plaster</u>				
105	On walls	m2	9	97.53	877.77

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
106	On walls in sunk/raised panels	m2	9	101.43	912.87
107	On walls between timber grounds (area of grounds not deducted)	m2	9	101.43	912.87
108	On circular walls	m2	9	97.53	877.77
109	On narrow widths	m2	9	1.06	9.54
110	On ceilings	m2	9	111.82	1,006.38
111	On raking soffits of stairs	m2	9	111.82	1,006.38
112	On projecting and isolated columns/beams	m2	9	97.53	877.77
	<u>Repairing cracks in "Gumma Zenith" or equal and approved 3,0mm thick "Granitico" pure acrylic plasticised coating with stone finish on plastered concrete or brick surfaces exceeding 1mm wide by carefully cutting out in sections using straight horizontal and/or vertical saw cuts, hacking up/off and removing plaster 150mm wide on both sides of crack, preparing existing surface and applying new cement plaster on and including chicken mesh spiked to base, and finishing flush with "Gamma Zenith" covering to match existing surface</u>				
113	On horizontal top surfaces	m	9	61.11	549.99
114	On sloping top surfaces	m	9	61.11	549.99
115	On vertical surfaces	m	9	61.11	549.99
116	On vertical surfaces circular	m	9	61.11	549.99
117	On horizontal soffits	m	9	67.62	608.58
118	On horizontal soffits circular	m	9	67.62	608.58
119	On raking soffits	m	9	67.62	608.58
	<u>Two coats gypsum plaster "Rhinolite" polished to a smooth finish</u>				
120	Plaster	m2	9	117.03	1,053.27
121	Plaster in patches	m2	9	117.03	1,053.27
122	Gypsum plasterboard ceilings, bulkheads, etc	m2	9	143.05	1,287.45

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
123	Gypsum plasterboard ceilings, bulkheads, etc in patches	m2	9	146.94	1,322.46
124	Gypsum plasterboard partitioning	m2	9	117.03	1,053.27
125	Gypsum plasterboard partitioning in patches	m2	9	39.01	351.09
	<u>Two coats gypsum plaster "Rhinolite" to a brushed finish</u>				
126	Plaster	m2	9	117.03	1,053.27
127	Plaster in patches	m2	9	117.03	1,053.27
128	Gypsum plasterboard ceilings, bulkheads, etc	m2	9	143.05	1,287.45
129	Gypsum plasterboard ceilings, bulkheads, etc in patches	m2	9	146.94	1,322.46
130	Gypsum plasterboard partitioning	m2	9	117.03	1,053.27
131	Gypsum plasterboard partitioning in patches	m2	9	39.01	351.09
	<u>Two coats gypsum plaster "Rhinolite" polished to a textured finish</u>				
132	Plaster	m2	9	117.03	1,053.27
133	Plaster in patches	m2	9	117.03	1,053.27
134	Gypsum plasterboard ceilings, bulkheads, etc	m2	9	143.05	1,287.45
135	Gypsum plasterboard ceilings, bulkheads, etc in patches	m2	9	146.94	1,322.46
136	Gypsum plasterboard partitioning	m2	9	117.03	1,053.27
137	Gypsum plasterboard partitioning in patches	m2	9	39.01	351.09
	<u>AIR GRATINGS</u>				
	<u>Air gratings</u>				
138	110 x 150mm cast plaster or white plastic plain pattern air grating fixed with plaster face	No	9	20.81	187.29
	<u>CORNER PROTECTORS, DIVIDING STRIPS. ETC</u>				
	<u>Dividing strips</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
139	30 x 3mm flat brass dividing strip between different floor finishes	m	9	93.63	842.67
					94,819.05
					39,611,722.21
	SUB-TOTAL <i>(Carried To Summary)</i>				
	<u>BILL NO. 14</u>				
	<u>TILING</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	Unless described as "fixed with adhesive to plaster (plaster elsewhere)" descriptions of tiling on brick or concrete walls, columns, etc shall be deemed to include 1:4 cement plaster backing and descriptions of tiling on concrete floors etc shall be deemed to include 1:3 plaster bedding				
	<u>WALL TILING</u>				
	<u>150 x 150 x 5mm white glazed ceramic tiles or equally approved fixed with adhesive to plaster (plaster elsewhere)</u>				
1	On horizontal top surfaces	m2	4	195.06	780.24

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
2	On sloping top surfaces	m2	4	195.06	780.24
3	On vertical surfaces	m2	4	195.06	780.24
4	On vertical surfaces circular	m2	4	206.76	827.04
5	On horizontal soffits	m2	4	206.76	827.04
6	On narrow widths	m2	4	211.96	847.84
7	Circular cutting	m	4	18.21	72.84
	<u>200 x 200 x 6mm white glazed ceramic tiles or equally approved fixed with adhesive to plaster (plaster elsewhere)</u>				
8	On horizontal top surfaces	m2	4	227.56	910.24
9	On sloping top surfaces	m2	4	227.56	910.24
10	On vertical surfaces	m2	4	227.56	910.24
11	On vertical surfaces circular	m2	4	240.57	962.28
12	On horizontal soffits	m2	4	240.57	962.28
13	On narrow widths	m2	4	245.76	983.04
14	Circular cutting	m	4	18.21	72.84
	<u>Ceramic wall tiles (PC sum R220.00/m² for supply and delivery, excluding labour, waste and VAT) or equally approved fixed with adhesive to plaster (plaster elsewhere) and flush pointed with tinted waterproof jointing compound</u>				
15	On horizontal top surfaces	m2	4	241.86	967.44
16	On sloping top surfaces	m2	4	241.86	967.44
17	On vertical surfaces	m2	4	241.86	967.44
18	On vertical surfaces circular	m2	4	253.56	1,014.24
19	On horizontal soffits	m2	4	253.68	1,014.72
20	On narrow widths	m2	4	260.07	1,040.28
21	Circular cutting	m	4	18.21	72.84

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>240 x 116 x 7,4mm White glazed ceramic tiles or equally approved fixed with adhesive to plaster, screeds, etc</u>				
22	On walls	m2	4	379.19	1,516.76
	<u>100 x 100 x 5mm "Novodoma Mosaic" sheet black shiny tiles or equally approved fixed with adhesive to plaster, screed, etc</u>				
23	On walls	m2	4	460.40	1,841.60
24	Extra over for cross pattern	m2	4	126.62	506.48
	<u>250 x 250 x 5mm "Glass Mosaic B50-31-30-13" sheet blue shiny tiles or equally approved fixed with adhesive to plaster, screed, etc</u>				
25	On walls	m2	4	460.38	1,841.52
	<u>Code "311200900" White Glossy" size 244 x 119mm or equally approved fixed with adhesive to plaster, screed, etc</u>				
26	On walls	m2	4	463.78	1,855.12
	<u>Code "311200901" White Glossy" size 244 x 119mm or equally approved fixed with adhesive to plaster, screed, etc</u>				
27	On walls	m2	4	495.12	1,980.48
	<u>Code "311200710" Light Blue Glossy" size 244 x 119mm or equally approved fixed with adhesive to plaster, screed, etc</u>				
28	On walls	m2	4	480.90	1,923.60
	<u>FLOOR TILING</u>				
	<u>Ceramic floor tiles (PC sum R220.00/m² for supply and delivery, excluding labour, waste and VAT) or equally approved fixed with adhesive to bedding (bedding elsewhere) and flush pointed with tinted jointing compound</u>				
29	On horizontal top surfaces	m2	4	419.88	1,679.52
30	On vertical surfaces	m2	4	419.88	1,679.52
31	On narrow widths	m2	4	419.88	1,679.52

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
32	On horizontal surfaces to falls and currents	m2	4	419.88	1,679.52
33	On treads and risers of stairs	m2	4	428.99	1,715.96
34	Skirtings 100mm high of stretcher course tiles	m	4	36.40	145.60
35	Skirtings exceeding 100mm high and not exceeding 150mm high of stretcher course tiles	m	4	50.71	202.84
36	Circular cutting	m	4	18.21	72.84
	<u>240 x 116 x 7,4mm White glazed ceramic tiles or equally approved fixed with adhesive to plaster, screeds, etc</u>				
37	On floors	m2	4	379.19	1,516.76
	<u>100 x 100 x 5mm "Novodoma Mosaic" sheet black shiny tiles or equally approved fixed with adhesive to plaster, screed, etc</u>				
38	In lanes	m	4	73.81	295.24
39	Extra over for cross pattern	m2	4	826.62	3,306.48
40	Extra over for "City of Ekurhuleni" logo pattern	m2	4	282.42	1,129.68
	<u>295 x 295 x 5mm "Non Skid" tiles Code Union Tile "1W22WYEXSL" or equally approved</u>				
41	On floors	m2	4	460.40	1,841.60
42	Tile Skirting	m2	4	60.27	241.08
	<u>Code "311200781" Matt Glazed Azurblau" (dark blue) size 244 x 119mm or equally approved fixed with adhesive to plaster, screed, etc</u>				
43	On floors	m2	4	522.65	2,090.60
44	Tile Skirting	m2	4	68.41	273.64
	<u>Code "311200786" Non-Slip Azurblau" size 244 x 119mm or equally approved fixed with adhesive to plaster, screed, etc</u>				
45	On floors	m2	4	655.45	2,621.80
			4		0.00
46	Tile Skirting	m2	4	85.80	343.20

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Code "311200710" Light Blue Glossy" size 244 x 119mm or equally approved fixed with adhesive to plaster, screed, etc</u>				
47	On floors	m2	4	480.90	1,923.60
48	Tile Skirting	m2	4	62.91	251.64
	<u>Code "311200716" Light Blue Non-Slip" size 244 x 119mm or equally approved fixed with adhesive to plaster, screed, etc</u>				
49	On floors	m2	4	1,228.62	4,914.48
50	Tile Skirting	m2	4	160.82	643.28
	<u>Code "663130690" RP1 Small Grooved tile Beige" size 244 x 119mm or equally approved fixed with adhesive to plaster, screed, etc</u>				
51	On floors	m2	4	1,228.62	4,914.48
	<u>Code "663130690-788" RP3 Small Grooved Tile Safety Marking Beige Azurblau" size 244 x 119mm or equally approved fixed with adhesive to plaster, screed, etc</u>				
52	On floors	m2	4	3,228.98	12,915.92
	<u>Code "663130690-786" Non-slip Beige Blue Nose Rounded Azurblau Matt - Raised End Edges" size 244 x 119mm or equally approved fixed with adhesive to plaster, screed, etc</u>				
53	On floors	m2	4	3,789.46	15,157.84
	<u>Code "311200906" RHB Non-Slip White" size 244 x 119mm or equally approved fixed with adhesive to plaster, screed, etc</u>				
54	On floors	m2	4	582.36	2,329.44

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>CHANNELS</u>				
	<u>Vaal or equal and approved white glazed fireclay block channels bedded and jointed in 1:3 cement mortar and pointed with flush joints in 1:3 white cement mortar</u>				
55	150 x 100mm block SCUM channels	m	4	819.22	3,276.88
56	Extra over block channels for Fair end	No	4	236.67	946.68
57	Extra over block channels for Stopped end	No	4	236.67	946.68
58	Extra over block channels for Angle	No	4	236.67	946.68
59	Extra over block channels for T-intersection	No	4	236.67	946.68
60	Extra over block channels for X-intersection	No	4	236.67	946.68
61	Extra over block channels for Outlet	No	4	236.67	946.68
62	Extra over block channels for Stopped end with outlet	No	4	236.67	946.68
	<u>TOILET PAPER HOLDERS ETC</u>				
	<u>Johnson or equal and approved white glazed ceramic</u>				
63	150 x 150mm semi-recessed toilet paper holder	No	4	273.08	1,092.32
64	150 x 150mm semi-recessed soap dish	No	4	273.08	1,092.32
	<u>POLISHED FLOORS</u>				
	<u>Grinding and polishing of concrete floor to "HTC Superfloor" or equivalent</u>				
65	Floors not exceeding 500m2	m2	4	624.16	2,496.64
66	Floors exceeding 500m2 and not exceeding 1000m2	m2	4	452.54	1,810.16
67	Floors exceeding 1000m2 and not exceeding 2000m2	m2	4	436.91	1,747.64
68	Floors exceeding 2000m2 and not exceeding 5000m2	m2	4	421.31	1,685.24
69	Floors exceeding 5000m2 and not exceeding 10000m2	m2	4	405.70	1,622.80
70	Floors exceeding 1000m2 and not exceeding 2000m2	m2	4	390.10	1,560.40

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Grinding and polishing of concrete floor to "HTC Superfloor" in partitioned areas or equivalent</u>				
71	Floors not exceeding 500m2	m2	4	686.58	2,746.32
72	Floors exceeding 500m2 and not exceeding 1000m2	m2	4	514.94	2,059.76
73	Floors exceeding 1000m2 and not exceeding 2000m2	m2	4	499.33	1,997.32
74	Floors exceeding 2000m2 and not exceeding 5000m2	m2	4	483.73	1,934.92
75	Floors exceeding 5000m2 and not exceeding 10000m2	m2	4	468.13	1,872.52
76	Floors exceeding 1000m2 and not exceeding 2000m2	m2	4	452.54	1,810.16
	<u>HTC Twister Restoration deep clean</u>				
77	Linoleum/vinyl	m2	4	202.85	811.40
78	Powerfloat concrete floor	m2	4	234.06	936.24
79	Granite	m2	4	202.85	811.40
80	Marble	m2	4	202.85	811.40
81	Terrazo	m2	4	202.85	811.40
	<u>HTC Stain Resistance</u>				
82	Single coat	m2	4	78.03	312.12
	<u>Cementation overlay</u>				
83	Placement	m2	4	1,396.58	5,586.32
84	Door raising	No	4	265.28	1,061.12
	<u>Polished Porcelain floor tiles (PC sum R250.00/m² for supply and delivery, excluding labour, waste and VAT) or equally approved fixed with adhesive to bedding (bedding elsewhere) and flush pointed with tinted jointing compound</u>				
85	On horizontal top surfaces	m2	4	457.81	1,831.24
86	On vertical surfaces	m2	4	457.81	1,831.24
87	On narrow widths	m2	4	457.81	1,831.24

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
88	On horizontal surfaces to falls and currents	m2	4	442.38	1,769.52
89	On treads and risers of stairs	m2	4	442.38	1,769.52
90	Skirtings 100mm high of stretcher course tiles	m	4	44.23	176.92
91	Skirtings exceeding 100mm high and not exceeding 150mm high of stretcher course tiles	m	4	66.35	265.40
92	Circular cutting	m	4	88.47	353.88
					150,105.20

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	SUB-TOTAL <i>(Carried To Summary)</i>				39,761,827.41
	<u>BILL NO. 15</u>				
	<u>GLAZING</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>GLAZING TO STEEL WITH PUTTY</u>				
	<u>4mm Clear float glass:</u>				
1	4mm Glass	m2	4	325.09	1,300.36
2	4mm Glass in cottage sashes	m2	4	357.61	1,430.44
3	4mm Glass in shapes other than rectangular	m2	4	357.61	1,430.44
	<u>4mm Patterned glass</u>				
4	4mm Glass	m2	4	422.62	1,690.48
5	4mm Glass in cottage sashes	m2	4	464.87	1,859.48
6	4mm Glass in shapes other than rectangular	m2	4	464.87	1,859.48

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>6,38mm clear toughened safety glass</u>				
7	6,38mm Glass	m2	4	821.83	3,287.32
			4		0.00
8	6,38mm Glass in shapes other than rectangular	m2	4	905.04	3,620.16
	<u>GLAZING TO WOOD WITH PINNED ON BEADS (BEADS MEASURED ELSEWHERE)</u>				
	<u>4mm Clear float glass:</u>				
9	4mm Glass	m2	4	325.09	1,300.36
10	4mm Glass in cottage sashes	m2	4	357.61	1,430.44
11	4mm Glass in shapes other than rectangular	m2	4	357.61	1,430.44
	<u>4mm Patterned glass</u>				
12	4mm Glass	m2	4	422.62	1,690.48
13	4mm Glass in cottage sashes	m2	4	464.87	1,859.48
14	4mm Glass in shapes other than rectangular	m2	4	464.87	1,859.48
	<u>6,38mm Clear toughened safety glass</u>	H3			
15	6,38mm Glass	m2	4	821.83	3,287.32
16	6,38mm Glass in shapes other than rectangular	m2	4	905.04	3,620.16
	<u>GLAZING TO ALUMINIUM WITH CLIP ON BEADS (BEADS MEASURED ELSEWHERE)</u>				
	<u>4mm Clear float glass:</u>				
17	4mm Glass	m2	4	330.17	1,320.68
18	4mm Glass in cottage sashes	m2	4	335.37	1,341.48
19	4mm Glass in shapes other than rectangular	m2	4	358.78	1,435.12
	<u>4mm Patterned glass</u>				
20	4mm Glass	m2	4	404.41	1,617.64
21	4mm Glass in cottage sashes	m2	4	408.31	1,633.24

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
22	4mm Glass in shapes other than rectangular <u>6,38mm Clear toughened safety glass</u>	m2	4	448.62	1,794.48
23	6,38mm Glass	m2	4	821.83	3,287.32
			4		0.00
24	6,38mm Glass in shapes other than rectangular <u>GLASS LOUVRE BLADES</u> <u>6mm Clear Glass Louvre Blades</u>	m2	4	905.04	3,620.16
25	Louvre blades not exceeding 150mm wide with polished edges <u>GLASS IN TOPS, SHELVES, DOORS, MIRRORS, ETC</u> <u>5mm Silvered float glass copper backed mirrors with polished edges holed for and fixed with chromium plated dome capped mirror screws with rubber buffers to plugs in brickwork or concrete</u>	m	4	227.56	910.24
26	Mirror 300 x 300mm high with four screws	No	4	502.74	2,010.96
27	Mirror 400 x 400mm high with four screws	No	4	650.85	2,603.40
28	Mirror 400 x 600mm high with four screws	No	4	1,210.65	4,842.60
29	Mirror size 400 x 600mm and screw fixing in recess to match existing <u>5mm Silvered float glass copper backed mirrors with 10mm bevelled and polished edges holed for and fixed with chromium plated dome capped mirror screws with rubber buffers to plugs in brickwork or concrete</u>	m2	4	500.00	2,000.00
30	Mirror 300 x 300mm high with four screws	No	4	593.76	2,375.04
31	Mirror 400 x 400mm high with four screws	No	4	667.86	2,671.44
32	Mirror 400 x 600mm high with four screws	No	4	1,360.20	5,440.80
33	Mirror size and screw fixing in recess to match existing <u>Sundries</u> <u>Sandblasting</u>	m2	4	550.00	2,200.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
34	To glazing	m2	4	461.63	1,846.52
	<u>Vinyl films and tinting</u>				
35	Vinyl film to glazing	m2	4	461.63	1,846.52
36	Vinyl film including muriels to glazing	m2	4	1,105.29	4,421.16
	<u>Awnings</u>				
37	Vinyl tinted awning including frame fixed to walls, concrete, wood, etc not exceeding 1200mm lengths	No	4	2,925.79	11,703.16
38	Vinyl tinted awning including frame fixed to walls, concrete, wood, etc exceeding 1200mm and not exceeding 2400mm lengths	No	4	5,120.13	20,480.52
					114,358.80
	SUB-TOTAL <i>(Carried To Summary)</i>				39,876,186.21
	<u>BILL NO. 16</u>				
	<u>PAINTWORK</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>SUPPLEMENTARY PREAMBLES</u>				
	<u>Descriptions</u>				
	Description of paintwork shall be deemed to include for all cutting in				
	<u>Paint Specifications</u>				
	All painting shall be carried out in strict accordance with "Plascon" or equally approved specification				
	<u>PAINTWORK, ETC. TO NEW WORK</u>				
	<u>ON BRICKS OR QUARRY TILES</u>				
	<u>Two coats solvent based UV resistant clear gloss acrylic brick dressing</u>				
1	On sills, thresholds, etc	m2	17	78.03	1,326.51
2	On flush pointed face walls	m2	17	78.03	1,326.51
3	On recessed pointed face walls	m2	17	78.03	1,326.51
	<u>ON FLOATED PLASTER</u>				
	<u>One coat alkaline resistant plaster primer, one coat universal alkyd based undercoat and one coats alkyd based eggshell enamel paint</u>				
4	On internal walls	m2	17	71.52	1,215.84
	<u>One coat alkaline resistant plaster primer and two coats superior acrylic PVA emulsion paint</u>				
5	On internal walls	m2	17	71.52	1,215.84
6	On ceilings	m2	17	71.52	1,215.84
	<u>One coat resin based bonding liquid two coats superior acrylic PVA emulsion paint</u>				
7	On external walls	m2	17	78.03	1,326.51

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>One coat resin based bonding liquid and two coats UV resistant water based mica and marble waterproof fine texture paint</u>				
8	On external walls	m2	17	63.72	1,083.24
	<u>ON FAIR FACE BRICKWORK</u>				
	<u>One coat alkaline resistant plaster primer, one coat universal alkyd based undercoat and two coats superior acrylic PVA emulsion paint</u>				
9	On internal walls	m2	17	78.03	1,326.51
10	On external walls	m2	17	78.03	1,326.51
	<u>ON PLASTER BOARD</u>				
	<u>One coat alkaline resistant plaster primer and two coats superior acrylic PVA emulsion paint</u>				
11	On ceilings and cornices	m2	17	71.52	1,215.84
12	On drywall partitions	m2	17	71.52	1,215.84
	<u>ON FIBRE-CEMENT</u>				
	<u>One coat resin based bonding liquid two full coats UV resistant water based acrylic roof paint</u>				
13	On profiled roof sheets (measured on flat)	m2	17	71.52	1,215.84
14	On fascias and barge boards	m2	17	71.52	1,215.84
	<u>One coat alkaline resistant plaster primer and two coats superior acrylic PVA emulsion paint</u>				
15	On internal fibre cement ceilings including priming steel joints and nail heads with one coat zinc phosphate alkyd resin prime	m2	17	71.52	1,215.84
16	On fascias and barge boards	m2	17	71.52	1,215.84
17	On internal fibre cement sills not exceeding 300mm girth	m	17	71.52	1,215.84
18	On fascia and barge boards not exceeding 300mm girth	m	17	71.52	1,215.84
	<u>ON METAL</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Spot prime defects in pre-primed surfaces with zinc chromate primer and apply one universal alkyd based undercoat and two coats alkyd based high gloss enamel paint</u>				
19	On door frames	m2	17	71.52	1,215.84
20	On record room and strong room doors and frames	m2	17	71.52	1,215.84
21	On window frames	m2	17	71.52	1,215.84
22	On window frames with burglar bars	m2	17	71.52	1,215.84
23	On gates, grilles, burglar screens, balustrades, steel palisade, etc (both sides measured over full flat area)	m2	17	71.52	1,215.84
	<u>One coat water based galvanised iron primer, one coat universal alkyd based undercoat and two coats alkyd based high gloss enamel paint</u>				
24	On corrugated iron profile roof sheeting (measured on flat)	m2	17	78.03	1,326.51
25	On IBR profile roof sheeting (measured on flat)	m2	17	78.03	1,326.51
26	On eaves gutters	m2	17	78.03	1,326.51
27	On rails, bars, pipes etc	m	17	23.40	397.80
28	On eaves gutters/rainwater downpipes not exceeding 300mm girth	m	17	29.91	508.47
29	On rails, bars, pipes etc not exceeding 300mm girth	m	17	29.91	508.47
	<u>ON WOOD</u>				
	<u>One coat wood primer, one universal alkyd based undercoat and two coats alkyd based eggshell enamel paint</u>				
30	On boarded panelling	m2	17	71.52	1,215.84
31	On boarded ceilings	m2	17	71.52	1,215.84
32	On doors	m2	17	71.52	1,215.84
33	On fittings	m2	17	71.52	1,215.84
34	On roof timbers at eaves and verges	m2	17	71.52	1,215.84

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
35	Skirtings, rails, etc. not exceeding 300mm. girth <u>Three coats clear polyurethane suede varnish</u>	m	17	23.40	397.80
36	On doors	m2	17	78.03	1,326.51
37	Skirtings, rails, etc. not exceeding 300mm. girth	m	17	27.32	464.44
	<u>PAINTWORK, ETC. TO PREVIOUSLY PAINTED WORK</u>				
	<u>PREPARATORY WORK TO EXISTING WORK</u>				
	<u>Previously painted plastered surfaces</u> Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with suitable filler and finished smooth				
	<u>Previously painted metal surfaces</u> Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed down to bare metal				
	<u>Previously painted wood surfaces</u> Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth				
	<u>ON BRICKS OR QUARRY TILES</u>				
	<u>Two coats solvent based UV resistant clear gloss acrylic brick dressing</u>				
38	On sills, thresholds, etc	m2	17	71.52	1,215.84
39	On flush pointed face walls	m2	17	71.52	1,215.84
40	On recessed pointed face walls	m2	17	71.52	1,215.84
	<u>ON FLOATED PLASTER</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>One coat alkaline resistant plaster primer, one coat universal alkyd based undercoat and one coats alkyd based eggshell enamel paint on work in poor condition</u>				
41	On internal walls	m2	17	71.52	1,215.84
42	On columns	m2	17	71.52	1,215.84
	<u>One coat resin based bonding liquid two coats superior acrylic PVA emulsion paint on work in poor condition</u>				
43	On internal walls	m2	17	71.52	1,215.84
44	On external walls	m2	17	71.52	1,215.84
45	On ceilings	m2	17	71.52	1,215.84
	<u>ON GAMMA ZENNITH</u>				
	<u>One coat resin based bonding liquid two coats superior glamour paint on work in poor condition</u>				
46	On internal walls	m2	17	87.12	1,481.04
47	On external walls	m2	17	87.12	1,481.04
48	On ceilings	m2	17	87.12	1,481.04
	<u>ON FAIR FACE BRICKWORK</u>				
	<u>One coat alkaline resistant plaster primer, one coat universal alkyd based undercoat and one coats alkyd based eggshell enamel paint on work in poor condition</u>				
49	On internal walls	m2	17	78.03	1,326.51
	<u>One coat resin based bonding liquid and two coats superior acrylic PVA emulsion paint on work in poor condition</u>				
50	On internal walls	m2	17	78.03	1,326.51
51	On external walls	m2	17	78.03	1,326.51
	<u>ON PLASTER BOARD</u>				
	<u>One coat resin based bonding liquid and two coats superior acrylic PVA emulsion paint on work in poor condition</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
52	On ceilings and cornices	m2	17	71.52	1,215.84
53	On drywall partitions	m2	17	71.52	1,215.84
	<u>ON FIBRE-CEMENT</u>				
	<u>One coat resin based bonding liquid and two full coats UV resistant water based acrylic roof paint on work in poor condition</u>				
54	On profiled roof sheets (measured on flat)	m2	17	71.52	1,215.84
55	On fascias and barge boards	m2	17	71.52	1,215.84
	<u>Two coats superior acrylic PVA emulsion paint on work in sound condition</u>				
56	On internal fibre cement ceilings including priming steel joints and nail heads with one coat zinc phosphate alkyd resin primer	m2	17	71.52	1,215.84
57	On fascias and barge boards	m2	17	71.52	1,215.84
58	On internal fibre cement sills not exceeding 300mm girth	m	17	23.40	397.80
59	On fascia and barge boards not exceeding 300mm girth	m	17	23.40	397.80
	<u>ON METAL</u>				
	<u>Two coats alkyd based high gloss enamel paint on previously painted steel in sound condition</u>				
60	On door frames	m2	17	71.52	1,215.84
61	On recordroom, strongroom, combination doors and frames	m2	17	71.52	1,215.84
62	On window frames	m2	17	71.52	1,215.84
63	On window frames with burglar bars	m2	17	71.52	1,215.84
64	On gates, grilles, burglar screens, balustrades, etc (both sides measured over full flat area)	m2	17	71.52	1,215.84
65	On eaves gutters/rainwater downpipes not exceeding 300mm girth	m	17	33.81	574.77
66	On rails not exceeding 300mm girth	m	17	33.81	574.77

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
67	On eaves gutters	m	17	71.52	1,215.84
68	On palisade fencing	m	17	71.52	1,215.84
	<u>One coat water based galvanised iron primer, one coat Universal alkyd based undercoat and two coats alkyd based high gloss enamel paint on galvanised steel in poor condition (rusted)</u>	H3			
69	On corrugated iron profile roof sheeting (measured on flat)	m2	17	84.52	1,436.84
70	On IBR profile roof sheeting (measured on flat)	m2	17	84.52	1,436.84
71	On eaves gutters	m2	17	84.52	1,436.84
72	On gates, grilles, burglar screens, balustrades, etc (both sides measured over full flat area)	m2	17	84.52	1,436.84
73	On Steel Palisade (both sides measured over full flat area)	m2	17	84.52	1,436.84
74	On rails, bars, pipes exceeding 300mm girth	m	17	37.70	640.90
75	On eaves gutters/rainwater downpipes not exceeding 300mm girth	m	17	37.70	640.90
	<u>ON WOOD</u>				
	<u>Spot prime bare wood surfaces with wood primer and apply one universal alkyd based undercoat and two coats alkyd based eggshell enamel paint on previously painted surfaces in poor condition</u>				
76	On doors	m2	17	71.52	1,215.84
			17		0.00
77	On fittings	m2	17	71.52	1,215.84
78	Skirtings, rails, etc. not exceeding 300mm. girth	m	17	23.40	397.80
79	On roof timbers at eaves and verges	m	17	71.52	1,215.84
	<u>Two coats alkyd based eggshell enamel paint on previously painted surfaces in sound condition</u>				
80	On doors	m2	17	71.52	1,215.84
81	On fittings	m2	17	71.52	1,215.84

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
82	Skirtings, rails, etc. not exceeding 300mm. girth	m	17	23.40	397.80
83	On roof timbers at eaves and verges	m2	17	71.52	1,215.84
	<u>Three coats clear polyurethane suede varnish</u>		17		0.00
84	On doors	m2	17	78.03	1,326.51
85	Skirtings, rails, etc. not exceeding 300mm. girth	m	17	27.32	464.44
	<u>MURIELS AND PAINTINGS</u>				
86	TOWNSHIP THEME: Customized two dimensional puzzle designed and the pieces set back and forth to give dimension - vivid colours are used. Materials: Puzzle pieces cut out of masonite board fixed onto wall.	m2	1	3,125.19	3,125.19
87	BEACH THEME: Individual bear figure activities on the beach set back and forth to create dimension on backing board. Materials: Masonite figures cut out and placed on masonite backing board. Acrylic formulated sand mixture to backing board.	m2	1	2,621.80	2,621.80
88	INSECT THEME: Insects on flowers and leafs in three dimension. Materials: Gupsym board backing with formulated pastes to create dimension	m2	1	6,408.87	6,408.87
89	SPACE THEME: Moon and planets in a dimensional space with astronaut. Materials: Gupsym board backing with formulated paste to create dimension.	m2	1	2,778.62	2,778.62
90	ANCIENT THEME: figures (to be finalised) on dimensional Ancient Castle doing every day life. Materials: Masonite figures cut out to create dimension on a backing board	m2	1	2,621.80	2,621.80
91	PIRATE SHIPS AND UNDER SEA THEME: Dimensional Fighting battle ships above and sea life below - to be finalised. Materials: Masonite battle ships and sea creatures cut out and placed on backing boards	m2	1	2,621.80	2,621.80
92	BUTTERFLY / MOUSE THEME: Pictures of everyday life at home - bright colours to be used. Materials: Bold Acrylic colours on Masonite board, final coat using varnish, paint brushes and rollers, glue, pencils, etc	m2	1	1,463.69	1,463.69

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
93	FLOWERS / BIRD THEME: Pictures of everyday life at home - bright colours to be used. Materials: Pastel collars colours on Masonite board, final coat using vanish, paint brushes and rollers, glue, pencils, etc	m2	1	1,549.65	1,549.65
94	BIG FIVE THEME: Pictures of everyday life at home - bright colours to be used. Materials: Pastel collars colours on Masonite board, final coat using vanish, paint brushes and rollers, glue, pencils, etc	m2	1	1,549.65	1,549.65
					121,147.05
					39,997,333.26

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	SUB-TOTAL <i>(Carried To Summary)</i>				
	<u>BILL NO. 17</u>				
	<u>PROVISIONAL SUMS, ETC.</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	Works listed under the heading 'SPECIALIST SUB-CONTRACTORS' are works that will commence during the execution of various contracts and the contractor shall allow free access to the site for these specialist contractors. The contractor shall prepare a programme in conjunction with these sub-contractors in order to complete the works successfully. Payment to the specialist sub- contractor will be made via the contractor. The estimated value of these works will vary between the different contracts. However, the tenderer is to list his/her profit and attendance percentage in the rate column, if required				
	<u>SPECIALIST SUB-CONTRACTORS</u>				
	<u>PREFABRICATED TIMBER ROOF TRUSSES</u>				
1	For the design, manufacture, delivery to site of prefabricated timber trusses and erection by an approved sub contractor	Item	1	1,950.00	1,950.00
2	Allow for profit (insert percent only in rate column)	%IT	1	195.00	195.00
3	Allow for attendance (insert percent only in rate column)	%IT	1	195.00	195.00
	<u>REHABILITATION OF SWIMMING POOLS</u>				
4	For the supply, installation and commissioning of pool cleaning equipment by an approved sub contractor	Item	1	2,350.00	2,350.00
5	Allow for profit (insert percent only in rate column)	%IT	1	235.00	235.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
6	Allow for attendance (insert percent only in rate column)	%IT	1	235.00	235.00
	<u>STRUCTURAL STEELWORK</u>				
7	For the design, manufacture, delivery to site, repairs and maintenance of structural steelwork by an approved sub-contractor	Item	1	1,750.00	1,750.00
8	Allow for profit (insert percent only in rate column)	%IT	1	175.00	175.00
9	Allow for attendance (insert percent only in rate column)	%IT	1	175.00	175.00
	<u>PLUMBING AND DRAINLAYING</u>				
10	For the supply, delivery to site of plumbing, drain laying, including rainwater disposal, sewerage disposal, sanitary fittings, sanitary plumbing, water and fire reticulation, etc and installation by an approved sub contractor	Item	1	1,500.00	1,500.00
11	Allow for profit (insert percent only in rate column)	%IT	1	150.00	150.00
12	Allow for attendance (insert percent only in rate column)	%IT	1	150.00	150.00
	<u>ELECTRICAL INSTALLATION</u>				
13	For the supply, delivery to site of the electrical reticulation including light fittings, etc and installed by an approved sub contractor	Item	1	2,000.00	2,000.00
14	Allow for profit (insert percent only in rate column)	%IT	1	200.00	200.00
15	Allow for attendance (insert percent only in rate column)	%IT	1	200.00	200.00
	<u>ART WORK AND SIGNAGE</u>				
16	For the design and installation of art work and/or signage by an approved sub contractor	Item	1	2,000.00	2,000.00
17	Allow for profit (insert percent only in rate column)	%IT	1	200.00	200.00
18	Allow for attendance (insert percent only in rate column)	%IT	1	200.00	200.00
	<u>ALUMINIUM SHOPFRONTS/CURTAIN WALLING</u>				
19	For the supply, delivery to site of aluminium shopfronts/curtain walling and installed by an approved sub contractor	Item	1	2,000.00	2,000.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
20	Allow for profit (insert percent only in rate column)	%IT	1	200.00	200.00
21	Allow for attendance (insert percent only in rate column)	%IT	1	200.00	200.00
<u>SECURITY GATES, SCREENS, ROLLER SHUTTERS AND GRILLES</u>					
22	For the manufactured, delivered to site of security gates, screens, roller shutters and grilles and the erection by an approved sub contractor	Item	1	2,000.00	2,000.00
23	Allow for profit (insert percent only in rate column)	%IT	1	200.00	200.00
24	Allow for attendance (insert percent only in rate column)	%IT	1	200.00	200.00
<u>STEEL ROLLER SHUTTER AND GRILLES</u>					
25	For the manufactured, delivered to site of steel roller shutters/grilles and the erection by an approved sub contractor	Item	1	2,000.00	2,000.00
26	Allow for profit (insert percent only in rate column)	%IT	1	200.00	200.00
27	Allow for attendance (insert percent only in rate column)	%IT	1	200.00	200.00
<u>ELECTRIC, SOLAR WATER HEATING AND GENERATOR</u>					
28	For the design, supply, installation, commissioning and maintenance of electric, solar water heating system, generators involving, solar geysers, boiler, heat pumps, generator etc by an approved sub contractor	Item	1	2,000.00	2,000.00
29	Allow for profit (insert percent only in rate column)	%IT	1	200.00	200.00
30	Allow for attendance (insert percent only in rate column)	%IT	1	200.00	200.00
<u>AIR CONDITIONING / VENTILATION / EXTRACTORS/ COOLING UNITS</u>					
31	For the design, manufactured, delivered to site of air conditioning/ventilation system and the erection by an approved sub contractor	Item	1	2,000.00	2,000.00
32	Allow for profit (insert percent only in rate column)	%IT	1	200.00	200.00
33	Allow for attendance (insert percent only in rate column)	%IT	1	200.00	200.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
<u>FIRE DETECTION SYSTEMS</u>					
34	For the designed, supply, installation, commissioning, repair and maintenance of fire protection / prevention systems by an approved sub contractor	Item	1	1,500.00	1,500.00
35	Allow for profit (insert percent only in rate column)	%IT	1	150.00	150.00
36	Allow for attendance (insert percent only in rate column)	%IT	1	150.00	150.00
<u>VANITY SLAB TOPS</u>					
37	For the supply, delivery to site and installation of granite vanity slab tops, etc an approved sub contractor	Item	1	1,500.00	1,500.00
38	Allow for profit (insert percent only in rate column)	%IT	1	150.00	150.00
39	Allow for attendance (insert percent only in rate column)	%IT	1	150.00	150.00
<u>MISCELLANEOUS</u>					
40	For any specialized miscellaneous items	Item	1	1,800.00	1,800.00
41	Allow for profit (insert percent only in rate column)	%IT	1	180.00	180.00
42	Allow for attendance (insert percent only in rate column)	%IT	1	180.00	180.00
<u>CONCRETE SPALL REPAIRS</u>					
43	For concrete spall repairs / rehabilitation done by an approved spall repair sub contractor	Item	1	1,600.00	1,600.00
44	Allow for profit (insert percent only in rate column)	%IT	1	160.00	160.00
45	Allow for attendance (insert percent only in rate column)	%IT	1	160.00	160.00
<u>BIOMETRICS / ACCESS CONTROL</u>					
46	For the supply, installation, repairs and maintenance of biometrics /access control systems done by a specialist sub-contractor	Item	1	3,000.00	3,000.00
47	Allow for profit (insert percent only in rate column)	%IT	1	300.00	300.00
48	Allow for attendance (insert percent only in rate column)	%IT	1	300.00	300.00
<u>BOOK DETECTION SYSTEMS FOR LIBRARIES</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
49	For the supply, commissioning, installation, repairs, maintenance of Book detection systems, book check units and hardware warranty systems done by a specialist sub-contractor	Item	1	800.00	800.00
50	Allow for profit (insert percent only in rate column)	%IT	1	80.00	80.00
51	Allow for attendance (insert percent only in rate column)	%IT	1	80.00	80.00
<u>PRE-FABRICATED STRUCTURES</u>					
52	For the supply and installation pre-fabricated /stroke mobile structures /cottages supplied and installed by a specialist sub-contractor	Item	1	600.00	600.00
53	Allow for profit (insert percent only in rate column)	%IT	1	60.00	60.00
54	Allow for attendance (insert percent only in rate column)	%IT	1	60.00	60.00
<u>LIFTS, ESCALATORS AND HOISTS</u>					
55	For the supply, installation, repair, servicing and warranty to lifts, escalators and hoists installed by an accredited specialist sub-contractor	Item	1	700.00	700.00
56	Allow for profit (insert percent only in rate column)	%IT	1	70.00	70.00
57	Allow for attendance (insert percent only in rate column)	%IT	1	70.00	70.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
<u>PROFESSIONAL CONSULTING SERVICES</u>					
58	For the designs, investigations, cost estimates, and project management services supplied by a professional accredited consultant, such as an Architect, Quantity Surveyor, Civil Engineer, Electrical Engineer, Structural Engineer, Fire Rational Engineer, Land Surveyor, etc	Item	1	850.00	850.00
59	Allow for profit (insert percent only in rate column)	%IT	1	85.00	85.00
60	Allow for attendance (insert percent only in rate column)	%IT	1	85.00	85.00
<u>SHOPFITTING, CAPENTRY AND JOINERY</u>					
61	For the fabrication, and installation of shop fitting, carpentry and joinery by an approved sub contractor	Item	1	4,500.00	4,500.00
62	Allow for profit (insert percent only in rate column)	%IT	1	450.00	450.00
63	Allow for attendance (insert percent only in rate column)	%IT	1	450.00	450.00
<u>SCAFFOLDING AND STRUCTURAL SUPPORT</u>					
64	For the erection of scaffolding and structural support for complex structures and high rise building exceeding nine storey high by a licensed specialist contractor	Item	1	1,250.00	1,250.00
65	Allow for profit (insert percent only in rate column)	%IT	1	125.00	125.00
66	Allow for attendance (insert percent only in rate column)	%IT	1	125.00	125.00
<u>FIRE DETECTION SYSTEMS</u>					
67	For the supply, installation, commissioning, repair and maintenance of book detection systems by an approved sub contractor	Item	1	950.00	950.00
68	Allow for profit (insert percent only in rate column)	%IT	1	95.00	95.00
69	Allow for attendance (insert percent only in rate column)	%IT	1	95.00	95.00
<u>SURVEILLANCE AND SECURITY EQUIPMENT</u>					
70	For the supply, installation, commissioning, repair and maintenance of Surveillance and security equipment including CCTV cameras by an approved sub contractor	Item	1	750.00	750.00

Generic Bill Of Quantities
Construction And Refurbishment Of Buildings And Facilities
Generic Bill Of Quantities (Provisional)

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
71	Allow for profit (insert percent only in rate column)	%IT	1	75.00	75.00
72	Allow for attendance (insert percent only in rate column)	%IT	1	75.00	75.00
					49,620.00
	SUB-TOTAL <i>(Carried To Summary)</i>				40,046,953.26

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>BILL NO. 18</u>				
	<u>EXTERNAL WORKS</u>				
	<u>PREAMBLES</u>				
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule.				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	<u>Descriptions</u>				
	For full descriptions and supplementary preambles applicable to this section, see also previous bills				
	<u>Nature of ground</u>				
	A soil investigation will be carried out on site by the engineer, and the report will be annexed to these bills of quantities. Descriptions of all excavations shall be deemed to include all ground conditions classified as "earth" described in the annexed report and where conditions of a more difficult character are indicated these are separately measured				
	<u>Carting away of excavated material</u>				
	Description of carting away of excavated material shall deemed to include loading of excavated material onto trucks directly from the excavations, or alternatively, from stock piles situated on the building site.				
	<u>Concrete pipes</u>				
	Pipes shall be jointed with ogee joints with rubber collars or socket and spigot joints with rubber rings				
	<u>uPVC pipes and fittings</u>				
	Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings Soil, waste and vent pipes and fittings shall be solvent weld jointed				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>uPVC pressure pipes and fittings</u> Pipes for water supply shall be of the class stated Pipes of 40mm diameter and smaller shall be plain ended with solvent welded uPVC loose socket fittings Pipes of 50mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bens shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints with solvent welded uPVC loose socket fittings <u>Exposed concrete surfaces</u> Exposed surfaces of concrete stormwater channels, cover slabs, inspection eye marker slabs, gully tops, cleaning eye tops, catch pits, inspection chambers, etc. shall be finished smooth with plaster <u>Excavations</u> No claim for rock excavation will be entertained unless the contractor has timeously notified the quantity surveyor thereof prior to backfilling "Soft rock" and "hard rock" shall be as defined in "Earthworks" <u>Laying, backfilling, bedding, etc. of pipes</u> Pipes shall be laid and bedded and trenches shall be carefully backfilled in accordance with manufacturers' instructions The selection of the imported "borrow pit" pipe bending material for class or flexible pipe beddings shall be done by the contractor, and all the tendered rates for the imported material shall be deemed to include for the necessary selection of material. The selection of the imported "borrow pit" pipe bending material for class or flexible pipe beddings shall be done by the contractor, and all the tendered rates for the imported material shall be deemed to include for the necessary selection of material. Where no manufacturers' instructions exist, pipes shall be laid in accordance with clauses 5.1 and 5.2 of each of the following: SABS 1200 L: Medium-pressure pipelines LD : Sewers LE : Stormwater drainage Pipe trenches, etc. shall be backfilled in accordance with clauses 3, 5.5, 5.6, 5.7 and 7 of SABS 1200 LB : Bedding (Pipes) Unless otherwise described, bedding of rigid pipes shall be class B bedding Unless otherwise described, bedding of rigid pipes shall be class B bedding				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Densyl petrolatum anti-corrosion tape as manufactured by Denso SA (Pty) Ltd or equally approved</u>				
	Pipes to be taped shall be coated with the appropriate primer and the tape shall be applied with minimum 15mm lap per spiral unless otherwise described Couplings and fittings to pipes shall be taped in strict accordance with the manufacturers instructions, including all mastic tape "Layflat" sheeting, securing of same, etc. Unless otherwise described, bedding of rigid pipes shall be class B bedding				
	<u>ALTERATIONS</u>				
	<u>REMOVAL OF EXISTING WORK</u>				
	<u>Taking out and removing road kerbs and surfacing</u>				
1	Break up and cart away tarmac paving and crusher run base 175mm thick bedding including concrete kerbs	m2	5	33.14	165.70
2	Precast concrete vertical kerbs with 150 x 150mm cast in-situ concrete apron along sides of existing road including necessary excavation, backfilling and compaction	m	5	11.06	55.30
3	Lift up concrete, clay, etc. paving blocks and set aside for re-use	m2	5	15.60	78.00
4	Lift up concrete, clay, etc paving blocks, set aside and relay including 20mm sand bedding	m2	5	60.79	303.95
5	Break down and cart away half brickwall 1,8m high with piers at 2m centres and cart away	m	5	221.01	1,105.05
6	Break down and cart away one brickwall 1,8m high with piers at 3m centres and cart away	m	5	405.22	2,026.10
7	Break down and cart away one and half brickwall 1,8m high with piers at 3m centres and cart away	m	5	405.22	2,026.10
	<u>LANDSCAPING</u>				
	<u>Preambles</u>				
	The accuracy of bulk earthworks and landscaping will be in accordance with SABS 1200D and SABS 1200DM Degree II				
	<u>Topsoil, compost, lime and fertilizer</u>	H3	5		

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	Excavate and preserve topsoil and deposit in stockpile				
8	Topsoil obtained from prescribed stock piles on site spread and levelled over the site for grass areas including slightly wetting and rolling with light roller	m3	5	103.15	515.75
9	Topsoil obtained from prescribed stock piles on site spread and levelled over the site for grass areas including slightly wetting and rolling with light roller in plant beds, road islands, etc.	m2	5	81.05	405.25
10	Topsoil supplied by the contractor spread and levelled over the site for grass areas	m3	5	396.28	1,981.40
11	Compost in plant boxes	m3	5	530.87	2,654.35
	<u>TREES</u>				
12	Celtis africana (50l)	No	5	1,170.31	5,851.55
13	Tanalith treated eucalyptus fencing 1200mm high	m	5	590.37	2,951.85
14	Tanalith treated vertical lath (wood) handrails 1200mm high	m	5	407.27	2,036.35
	<u>GRASSING, GROUND COVERS, ETC.</u>				
	<u>Kikuyu</u>				
15	Roots in rows	m2	5	22.09	110.45
16	Areas not exceeding 1000m2	m2	5	26.21	131.05
17	Areas exceeding 1000m2	m2	5	24.96	124.80
18	Hydroseeding (Hydraulic mulch seeding, hydro-mulching)	m2	5	54.62	273.10
	<u>EARTHWORKS, ROADWORKS, ETC</u>				
	<u>Site clearance</u>				
19	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc.	m2	5	24.21	121.05
	<u>Bulk excavation, filling, etc</u>				
20	Not exceeding 2m deep	m3	5	93.72	468.60

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Open face excavation over sloping site</u>				
21	Open face excavation to reduce levels under roads, parking areas, etc. (spoil measured elsewhere)	m3	5	93.72	468.60
	<u>Extra over bulk excavation in earth for excavation in</u>				
22	Soft rock	m3	5	295.06	1,475.30
23	Hard rock	m3	5	516.11	2,580.55
	<u>Extra over excavations for carting away</u>				
24	Surplus material from excavations on site to a dumping site to be located by the contractor (100% of excavated material)	m3	5	120.91	604.55
	<u>Keeping excavations free of water</u>				
25	Keeping excavations free of water	Item	5	1,625.45	8,127.25
	<u>Keeping excavations moist</u>				
26	Extra over bulk or open face excavations to reduce levels under roads, parking areas, etc. (irrespective of depth) for keeping exposed or open excavation sides and bottoms	Item	5	5,000.00	25,000.00
	<u>Earthfilling supplied by the contractor under roads, parking areas, paving, etc. including all haul, selection, handling, etc (No designated borrow pit available)</u>				
	Road construction materials shall conform to the requirements of TRH 14: Guidelines for road construction materials				
27	Approved G7 material for use in backfilling under walkways, paths and islands in 150mm thick layers compacted to 90% Modified AASHTO density	m3	5	478.40	2,392.00
28	Selected G6 type material compacted in 150mm layers to 93% Modified AASHTO density	m3	5	478.40	2,392.00
29	150mm Sub-base layer G5 type material stabilized with 3% cement to obtain a C4 material compacted to 95% Modified AASHTO density	m3	5	534.06	2,670.30
	<u>Compaction of surfaces</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
30	Compaction of ground surface under roads and parking areas including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density	m2	5	38.46	192.30
	<u>Tests</u>				
31	Modified AASHTO Density test to 93%	No	5	676.18	3,380.90
	<u>Soil poisoning (In confined areas)</u>				
32	Trimex-S weedkiller mixed 30g/l water and applied at a rate of 1 litre/10m2 under road, parking and walkway paving	m2	5	38.51	192.55
	<u>Precast concrete block road surfacing</u>				
	Paving is to be laid in accordance with SABS 1200 MJ, SABS 1058 and the Concrete Masonry Association's specifications Paving is to be laid in herringbone pattern on 25mm (thickness after final compaction) clean river sand (preparation of ground or filling elsewhere) Clean sand is to be swept into joints between roadstones				
	<u>ASPHALT</u>				
	<u>Tar Surfacing (Parking and walkways)</u>				
33	Tar road resurfacing and making good	m2	5	224.32	1,121.60
34	Tar road resurfacing and making good in bad condition	m2	5	299.08	1,495.40
35	Saw-cutting asphalt(tar)	m2	5	34.46	172.30
	<u>PAVING</u>				
	<u>Lifting up, setting aside and re-laying paving blocks including backfilling and 20mm bedding sand</u>				
36	Precast concrete paving to falls	m2	5	94.09	470.45
	<u>450 x 450 x 50mm Precast concrete paving slabs laid on 50mm thick river sand bead including preparation of ground or filling</u>				
37	Paving of slabs laid with butt joints	m2	5	232.77	1,163.85

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
38	Paving of slabs laid with 10mm wide joints jointed with mortar and flush pointed	m2	5	241.86	1,209.30
39	Fair circular cutting	m	5	5.20	26.00
	<u>450 x 450 x 50mm precast concrete paving slabs with exposed aggregate finish laid on 50mm thick river sand bead including preparation of ground or filling</u>				
40	Paving of slabs laid with butt joints	m2	5	265.28	1,326.40
41	Paving of slabs laid with 10mm wide joints jointed with mortar and flush pointed	m2	5	274.37	1,371.85
42	Fair circular cutting	m	5	5.20	26.00
	<u>60mm Standard grey "Concor Double Zig-Zag" interlocking roadstone paving or equally approved</u>				
43	Paving to roads, parking areas, etc. to slight falls	m2	5	225.54	1,127.70
44	Circular cutting to pavers	m	5	22.35	111.75
			5		0.00
45	Joint of new paving or concrete edge beam to existing paving including all cutting, waste, filling of openings with concrete, etc.	m	5	18.21	91.05
	<u>60mm Standard grey "Concor Double Zig-Zag" interlocking roadstone paving or equally approved (For low traffic-All inclusive trade) Including earthworks, 25mm thick river sand bed with sand swept into joints including preparation of ground or filling etc</u>				
46	Paving to roads, parking areas, etc. to slight falls	m2	5	266.58	1,332.90
	<u>85mm Standard grey "Concor Double Zig-Zag" interlocking roadstone paving or equally approved</u>				
47	Paving to roads, parking areas, etc. to slight falls	m2	5	188.55	942.75
48	Circular cutting to pavers	m2	5	11.06	55.30
49	Joint of new paving or concrete edge beam to existing paving including all cutting, waste, filling of openings with concrete, etc	m	5	18.21	91.05

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Paving of 220 x 108,5 x 50mm thick "Corobrik Tuscan Blend" paving bricks or equally approved with butt joints on 25mm thick river sand bed with sand and cement mixture swept into joints and hosed down including preparation of ground or filling</u>				
50	Paving in stretcher bond pattern	m2	5	221.07	1,105.35
51	Paving in stretcher bond pattern to falls	m2	5	221.07	1,105.35
52	Paving in herringboned bond pattern	m2	5	221.07	1,105.35
53	Paving in herringboned bond pattern to falls	m2	5	221.07	1,105.35
54	75mm wide brick-on-edge edging on 50mm thick mortar bed	m	5	26.01	130.05
55	110mm wide brick-on-end edging on 50mm thick mortar bed	m	5	48.11	240.55
56	220mm wide brick-on-flat header course edging on 50mm thick mortar bed	m	5	44.21	221.05
57	220mm wide brick-on-flat header course edging on 50mm thick mortar bed circular on plan	m	5	45.51	227.55
58	220mm wide brick-on-edge header course edging on 50mm thick mortar bed	m	5	48.11	240.55
59	220mm wide brick-on-edge header course edging on 50mm thick mortar bed circular on plan	m	5	49.42	247.10
60	170mm high brick-on-flat risers on 25mm thick mortar bed	m	5	45.51	227.55
61	350mm wide treads of brick-on-flat header course and brick-on-flat stretcher course on 25mm thick mortar bed	m	5	55.93	279.65
	<u>Paving of 200 x 100 x 50mm thick precast concrete "Concor Bondbrick" chamfered paving blocks or equally approved with butt joints on 25mm thick river sand bed with sand swept into joints including preparation of ground or filling</u>				
62	Paving in stretcher bond pattern	m2	5	231.15	1,155.75
63	Paving in stretcher bond pattern to falls	m2	5	231.15	1,155.75
64	Paving in herringboned bond pattern	m2	5	231.15	1,155.75

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
65	Paving in herringboned bond pattern to falls	m2	5	231.15	1,155.75
66	100mm wide block-on-end edging on 50mm thick mortar bed	m	5	48.11	240.55
67	200mm wide block-on-flat header course edging on 50mm thick mortar bed	m	5	44.21	221.05
68	200mm wide block-on-flat header course edging on 50mm thick mortar bed circular on plan	m	5	45.51	227.55
69	200mm wide block-on-edge header course edging on 50mm thick mortar bed	m	5	48.11	240.55
70	200mm wide block-on-edge header course edging on 50mm thick mortar bed circular on plan	m	5	49.42	247.10
71	170mm high brick-on-flat risers on 25mm thick mortar bed	m	5	45.51	227.55
72	330mm wide treads of brick-on-flat header course and brick-on-flat stretcher course on 25mm thick mortar bed	m	5	55.93	279.65
73	Extra for contrasting colour blocks as marker lines	m	5	13.01	65.05
	<u>Double zig-zag (shape S-A) interlocking precast concrete blocks or equally approved complying with SABS 1058 laid with butt joints on 25mm thick river sand bed with sand swept into joints including preparation of ground or filling</u>				
74	Paving of 80mm thick blocks including edge blocks	m2	5	232.36	1,161.80
75	Paving of 80mm thick blocks including edge blocks to falls and cross falls	m2	5	232.36	1,161.80
76	Paving of 60mm thick blocks including edge blocks	m2	5	232.36	1,161.80
77	Paving of 60mm thick blocks including edge blocks to falls and cross falls	m2	5	232.36	1,161.80
78	Extra for contrasting colour blocks as marker lines	m	5	13.01	65.05
79	Fair circular cutting	m	5	15.20	76.00
	<u>Precast concrete kerb finished smooth on exposed surfaces including bedding, jointing and pointing</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
80	Vertical kerb (SABS 927 fig 7) 180 x 280mm high in 1000mm sections with 13mm thick softboard expansion joints at 20 000mm centres complete with 250 x 180mm thick class 15Mpa/19mm unreinforced cast in- situ concrete continuous anchor block strip for the full length at back of kerbing including excavation,backfilling, etc.	m	5	187.55	937.75
81	Vertical kerb (SABS 927 fig 7) 180 x 280mm high in 1000mm sections with 13mm thick softboard expansion joints at 20 000mm centres complete with 250 x 180mm thick class 15Mpa/19mm unreinforced cast in- situ concrete continuous anchor block strip for the full length at back of kerbing, circular on plan to exceeding 4 000mm radius formed with short lengths of straight kerb including excavation, backfilling, etc.	m	5	187.55	937.75
82	Vertical kerb (SABS 927 fig 7) 180 x 280mm high in 1000mm sections with 13mm thick softboard expansion joints at 20 000mm centres complete with 250 x 180mm thick class 15Mpa/19mm unreinforced cast in- situ concrete continuous anchor block strip for the full length at back of kerbing, circular on plan to not exceeding 4 000mm radius formed with short lengths (maximum 300mm long) of straight kerb including excavation, backfilling, etc.	m	5	187.55	937.75
83	Semi-mountable kerb (SABS 927 fig 7 laid flat on back) 180 x 280mm high in 1000mm sections with 13mm thick softboard expansion joints at 20 000mm centres complete with 250 x 180mm thick class 15Mpa/19mm unreinforced cast in-situ concrete continuous anchor block strip for the full length at back of kerbing including excavation, backfilling, etc.	m	5	187.55	937.75
84	Semi-mountable kerb (SABS 927 fig 7 laid flat on back) 180 x 280mm high in 1 000mm sections with 13mm thick softboard expansion joints at 20 000mm centres complete with 250 x 180mm thick class 15Mpa/19mm unreinforced cast in-situ concrete continuous anchor block strip for the full length at back of kerbing, circular on plan to exceeding 4 000mm radius formed with short lengths of straight kerb including excavation, backfilling, etc.	m	5	187.55	937.75

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
85	Semi-mountable kerb (SABS 927 fig 7 laid flat on back) 180 x 280mm high in 1 000mm sections with 13mm thick softboard expansion joints at 20 000mm centres complete with 250 x 180mm thick class 15Mpa/19mm unreinforced cast in-situ concrete continuous anchor block strip for the full length at back of kerbing, circular on plan to not exceeding 4 000mm radius formed with short lengths (maximum 300mm long) of straight kerb including excavation, backfilling, etc.	m	5	187.55	937.75
	<u>Sundries</u>				
86	Joint of new fig 7 kerb to existing kerb, including all cutting	m	5	88.21	441.05
	<u>SABS 731-1987 yellow or white roadmark paint on paving at a rate of 1 litre/m2</u>				
87	Line 100mm wide	m	5	15.60	78.00
88	Line 100mm wide (RTM 1)	m	5	15.60	78.00
89	Numeral or letter 400mm high	No	5	110.53	552.65
90	Numeral or letter 1250mm high (GM7)	No	5	139.78	698.90
91	Traffic arrow 1250 x 500mm wide extreme (G M4.1)	No	5	139.78	698.90
92	Information sign for "people with disability" parking in 150mm wide lines	m2	5	143.66	718.30
93	550 x 235 x 1600mm cast in-situ concrete dish channel	No	5	222.88	1,114.40
	<u>DRAINAGE</u>				
	<u>Stormwater drainage pipes</u>				
	<u>SABS 966 Class 9 uPVC pressure pipes, laid to falls on and including imported bedding for flexible pipes as SABS 1200LB, drawing LB-2(a) with bottom of trench compacted to 30% Modified AASHTO density (backfilling importation elsewhere measured)</u>				
94	200mm Pipes laid in and including trenches not exceeding 1m deep	m	5	351.10	1,755.50
95	200mm Pipes laid in and including trenches exceeding 1m and not exceeding 2m deep	m	5	456.41	2,282.05

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
96	200mm Pipes laid in and including trenches exceeding 2m and not exceeding 3m deep <u>SABS 966 Class 9 uPVC pressure pipes, laid to falls on and including imported bedding for flexible pipes as SABS 1200LB, drawing LB-2(a) including backfilling with soil raft foundation material</u>	m	5	593.35	2,966.75
97	200mm Pipes laid in and including trenches not exceeding 1m deep	m	5	351.10	1,755.50
98	200mm Pipes laid in and including trenches exceeding 1m and not exceeding 2m deep	m	5	456.41	2,282.05
99	200mm Pipes laid in and including trenches exceeding 2m and not exceeding 3m deep <u>Plain ended cast iron pipes with SSN couplings, laid to falls on and including imported Class B bedding for rigid pipes as SABS 1200LB drawing LB-1(b) with bottom of trench compacted to 90% Modified AASHTO density (backfilling importation measured elsewhere)</u>	m	5	593.35	2,966.75
100	200mm Pipes laid in and including trenches exceeding 1m and not exceeding 2m deep in soil raft foundation <u>Extra over uPVC Class 9 pipes for fittings</u>	m	5	754.19	3,770.95
101	200mm Bend	No	5	735.34	3,676.70
102	200mm Junction	No	5	791.92	3,959.60
103	200mm SSN coupling <u>Grid inlets, kerb inlets, field inlets, catchpits, etc. (steel and cast iron gratings and covers elsewhere measured)</u>	No	5	837.16	4,185.80
			5		0.00
104	Grid inlet 500 x 500mm and exceeding 500mm and not exceeding 750mm deep internally	No	5	2,812.72	14,063.60
105	Grid inlet 500 x 500mm and exceeding 750mm and not exceeding 1000mm deep internally	No	5	3,980.47	19,902.35
106	Grid inlet 500 x 500mm and exceeding 1000mm and not exceeding 1250mm deep internally	No	5	3,146.92	15,734.60

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
107	Grid inlet 500 x 500mm and exceeding 1250mm and not exceeding 1500mm deep internally	No	5	3,342.15	16,710.75
108	Grid inlet 500 x 500mm and exceeding 1500mm and not exceeding 1750mm deep internally	No	5	3,570.34	17,851.70
109	Junction box 500 x 500mm and not exceeding 500mm with concrete slab over	No	5	1,747.71	8,738.55
	<u>Heavy duty precast concrete circular inspection chambers including step irons, bases, etc (covers elsewhere)</u>				
110	Inspection chamber 1000mm diameter exceeding 2 500mm and not exceeding 2 750mm deep internally (on top of existing stormwater pipe including altering benching, etc	No	5	5,291.17	26,455.85
	<u>Covers, etc.</u>				
111	450 x 450 x 79kg Medium duty cast iron flat stormwater grating and frame	No	5	2,931.02	14,655.10
112	550mm Diameter x 75kg type 4A single seal cast iron manhole cover and frame	No	5	2,970.03	14,850.15
	<u>Sundries</u>				
113	Approved G6 imported imported material to be supplied by the contractor for use in pipe backfilling to trenches in 150mm thick layers compacted to 90% Modified AASHTO density	m3	5	325.09	1,625.45
114	Extra over trench excavations (irrespective of depth) for keeping exposed or open trench sides and bottoms wet at natural moisture conditions by adding or spraying of water for the whole duration of the trenching, pipe laying and backfill processes or construction duration	Item	5	149.54	747.70
	<u>Testing</u>				
115	Testing stormwater drainage pipe system	Item			
	<u>Soil drainage pipes</u>				
	<u>SABS 791 Class 34 "Mainlite" uPVC pipes with rubber-ring seal couplings, laid to falls on and including imported bedding for flexible pipes as SABS 1200LB, drawing L-B2(a) with bottom of trench compacted to a minimum of 90% Modified AASHTO density (backfilling importation elsewhere measured)</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
116	110mm Pipes laid in and including trenches not exceeding 1m	m	5	327.68	1,638.42
117	110mm Pipes laid in and including trenches exceeding 1m and not exceeding 2m deep	m	5	349.92	1,749.61
	<u>SABS 791 Class 34 "Mainlite" uPVC pipes with rubber-ring seal couplings, laid to falls on and including imported bedding for flexible pipes as SABS 1200LB, drawing L-B2(a) including backfilling with soil raft foundation material</u>				
118	110mm Pipes vertically or ramped to cleaning eyes, etc. (no excavation)	m	5	214.57	1,072.85
119	110mm Pipes laid in and including trenches not exceeding 1m deep in soil raft foundation	m	5	246.75	1,233.75
120	110mm Pipes laid in and including trenches exceeding 1m and not exceeding 2m deep in soil raft foundation	m	5	283.74	1,418.70
	<u>Extra over uPVC Class 34 pipes for fittings</u>				
121	110mm Bend	No	5	94.06	470.30
122	110mm Junction	No	5	92.09	460.45
123	110mm Access junction	No	5	105.48	527.40
124	110mm x 50mm Reducer	No	5	112.09	560.45
125	110mm x 50mm Reducing junction	No	5	121.59	607.95
126	110mm SSN coupling	No	5	120.60	603.00
	<u>uPVC gulley's</u>				
127	110mm Gulley complete with hopper head and grating, not exceeding 1 000mm deep	No	5	1,287.34	6,436.70
	<u>Heavy duty precast concrete circular inspection chambers including step irons, bases, etc (covers elsewhere)</u>				
128	Inspection chamber 1 000mm diameter exceeding 2 000mm deep internally	No	5	2,535.69	12,678.45
	<u>Covers, etc</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
129	550mm Diameter heavy duty precast concrete removable cover and frame	No	5	1,423.89	7,119.45
130	Lifting key for manhole cover	No	5	273.08	1,365.40
	<u>FENCING</u>				
	<u>Mild steel welded palisade fence including spot prime exposed metal surfaces and and two coats high gloss enamel paint</u>				
131	Palisade fence 1800mm high of 40 x 40 x 3mm angle section continuous top and bottom rails and 30 x 30 x 3mm angle section pickets with top end split and sharpened at average 150mm centres, welded to rails, rails welded 2200mm high posts of 76 x 76 x 5mm square tube with steel pyramid shaped capping on top at 2475mm centres with 500mm bottom ends cast into and including 15Mpa concrete footing in ground including excavation, ramming, removal of spoil and leaving clean and neat	m	5	1,107.09	5,535.45
132	Palisade fence 2400mm high of 40 x 40 x 3mm angle section continuous top and bottom rails and 30 x 30 x 3mm angle section pickets with top end split and sharpened at average 150mm centres, welded to rails, rails welded 2600mm high posts of 76 x 76 x 5mm square tube with steel pyramid shaped capping on top at 2475mm centres with 500mm bottom ends cast into and including 15Mpa concrete footing in ground including excavation, ramming, removal of spoil and leaving clean, neat and painted	m	5	1,292.73	6,463.65
133	Palisade pedestrian gate 900mm wide x 1800mm high overall, formed of 150 x 75 x 3mm thick hollow section frame, 100 x 75 x 3mm thick hollow section middle rail and cross bracing bars and with 25 x 25 x 2,5mm thick angle section spiked vertical bars at maximum 143mm centres welded to frame, middle rail and cross bracing bars complete with approved heavy duty hinges, security type locking device suitable for hand operated control, completely installed and painted	No	5	2,802.26	14,011.30

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
134	Palisade fence vehicle sliding gate 6000mm wide x 1800mm high overall, formed of 150 x 75 x 3mm thick hollow section frame, 100 x 75 x 3mm thick hollow section middle rail and cross bracing bars and with 25 x 25 x 2,5mm thick angle section spiked vertical bars at maximum 143mm centres welded to frame, middle rail and cross bracing bars complete with approved heavy duty castors, steel track cast in or bolted to and including concrete rail footing, security type locking device suitable for hand operated control rail, gate stops, gate guides, etc. completely installed and painted	No	5	15,994.32	79,971.60
135	Palisade fence vehicle sliding gate 6000mm wide x 2400mm high overall, formed of 150 x 75 x 3mm thick hollow section frame, 100 x 75 x 3mm thick hollow section middle rail and cross bracing bars and with 25 x 25 x 2,5mm thick angle section spiked vertical bars at maximum 143mm centres welded to frame, middle rail and cross bracing bars complete with approved heavy duty castors, steel track cast in or bolted to and including concrete rail footing, security type locking device suitable for hand operated control rail, gate stops, gate guides, etc. completely installed	No	5	18,725.06	93,625.30
136	Palisade fence vehicle swing double gate 3000mm wide x 2400mm high overall, formed of 150 x 75 x 3mm thick hollow section frame, 100 x 75 x 3mm thick hollow section middle rail and cross bracing bars and with 25 x 25 x 2,5mm thick angle section spiked vertical bars at maximum 143mm centres welded to frame, middle rail and cross bracing bars complete with approved heavy duty castors, etc. completely installed and painted	No	5	8,738.36	43,691.80
137	Palisade fence vehicle swing double gate 6000mm wide x 1800mm high overall, formed of 150 x 75 x 3mm thick hollow section frame, 100 x 75 x 3mm thick hollow section middle rail and cross bracing bars and with 25 x 25 x 2,5mm thick angle section spiked vertical bars at maximum 143mm centres welded to frame, middle rail and cross bracing bars complete with approved heavy duty castors, etc. completely installed and painted	No	5	15,669.23	78,346.15

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
138	Palisade fence vehicle swing double gate 6000mm wide x 2400mm high overall, formed of 150 x 75 x 3mm thick hollow section frame, 100 x 75 x 3mm thick hollow section middle rail and cross bracing bars and with 25 x 25 x 2,5mm thick angle section spiked vertical bars at maximum 143mm centres welded to frame, middle rail and cross bracing bars complete with approved heavy duty castors, etc. completely installed and painted	No	5	17,476.72	87,383.60
	<u>Making good complete</u>				
139	Palisade pedestrian gate 900mm wide x 1800mm high overall, formed of 150 x 75 x 3mm thick hollow section frame, 100 x 75 x 3mm thick hollow section middle rail and cross bracing bars and with 25 x 25 x 2,5mm thick angle section spiked vertical bars at maximum 143mm centres welded to frame, middle rail and cross bracing bars complete with approved heavy duty hinges, security type locking device suitable for hand operated control	No	5	419.37	2,096.85
140	Palisade fence vehicle sliding gate 6000mm wide x 1800mm high overall, formed of 150 x 75 x 3mm thick hollow section frame, 100 x 75 x 3mm thick hollow section middle rail and cross bracing bars and with 25 x 25 x 2,5mm thick angle section spiked vertical bars at maximum 143mm centres welded to frame, middle rail and cross bracing bars complete with approved heavy duty castors, security type locking device suitable for hand operated control rail, gate stops, gate guides, etc.	No	5	3,185.85	15,929.25
141	Palisade fence vehicle sliding gate 6000mm wide x 2400mm high overall, formed of 150 x 75 x 3mm thick hollow section frame, 100 x 75 x 3mm thick hollow section middle rail and cross bracing bars and with 25 x 25 x 2,5mm thick angle section spiked vertical bars at maximum 143mm centres welded to frame, middle rail and cross bracing bars complete with approved heavy duty castors, steel track cast in or bolted to and including concrete rail footing, security type locking device suitable for hand operated control rail, gate stops, gate guides, etc. completely installed	No	5	3,185.85	15,929.25
	<u>Concrete Palisade Fence</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
142	Palisade fence 1800mm high of stacked slats, slid in- between 2300mm high posts of 110 x 70mm H-section post at 1500mm centres with 500mm bottom ends cast into and including 15Mpa concrete footing in ground including excavation, ramming, removal of spoil and leaving clean and neat	m	5	887.71	4,438.55
143	Palisade fence 2400mm high of stacked slats, slid in- between 2900mm high posts of 110 x 70mm H-section post at 1500mm centres with 500mm bottom ends cast into and including 15Mpa concrete footing in ground including excavation, ramming, removal of spoil and leaving clean and neat	m	5	1,065.24	5,326.20
	<u>Precast Concrete Fence</u>				
144	Precast slatted fence 1800mm high of 110 x 70mm section continuous top and bottom rails and 140 x 70mm section with top end mitred at average 150mm centres, bolted to rails, rails bolted 2200mm high posts of 140 x 140mm square post at 2475mm centres with 500mm bottom ends cast into and including 15Mpa concrete footing in ground including excavation, ramming, removal of spoil and leaving clean and neat	m	5	756.38	3,781.90
145	Precast slatted fence 2400mm high of 110 x 70mm section continuous top and bottom rails and 140 x 70mm section with top end mitred at average 150mm centres, bolted to rails, rails bolted 2200mm high posts of 140 x 140mm square post at 2475mm centres with 500mm bottom ends cast into and including 15Mpa concrete footing in ground including excavation, ramming, removal of spoil and leaving clean and neat	m	5	945.49	4,727.45
146	Precast slatted fence panel size 1500 x 300mm	No	5	333.59	1,667.95
	<u>Diamond Wire Mesh</u>				
147	70 x 70mm Galvanised diamond wire mesh fence 1800mm high with seven horizontal strand wire of 2,9mm diameter fixed to posts, y-standards, droppers, etc with posts at 2475mm centres with 500mm bottom ends cast into and including 15Mpa concrete footing in ground including excavation, ramming, removal of spoil and leaving clean and neat	m	5	756.38	3,781.90

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
148	70 x 70mm Galvanised diamond wire mesh fence 3600mm high with fourteen horizontal strand wire of 2,9mm diameter fixed to posts, y-standards, droppers, etc with posts at 2475mm centres with 500mm bottom ends cast into and including 15Mpa concrete footing in ground including excavation, ramming, removal of spoil and leaving clean and neat	m	5	1,512.78	7,563.90
149	Post 2000 x 101 x 3mm hot dipped galvanised	No	5	509.74	2,548.70
150	Stay 2000 x 48 x 2m hot dipped galvanised	No	5	239.26	1,196.30
151	Y - standard 1850mm	No	5	102.01	510.05
152	Droppers 1200mm	No	5	29.26	146.30
	<u>Diamond Wire Mesh 1,2m high for Low Cost Housing</u>				
153	Wire mesh fencing shall be 1,2 m high formed of 50mm mesh chain link netting 2,5 mm diameter galvanised mild steel wire stained and secured to top and bottom rails and posts. Fencing shall be formed with three 4mm gauge strands of staining wire between 75 mm diameter posts inclusive of 38 mm tubular stays and intermediate rolled steel standards at approximately 3,65m. Corner posts shall have a minimum diameter of 75mm, 1,8m long for 1,2m high fencing and set 0,6 m deep in the ground with ends embedded in 15Mpa concrete. Stays shall have a minimum diameter of 38mm, 2,8mm thick. Stays shall also be neatly mitred and welded to corner and end posts. Corner posts are to be provided with two stays and end posts with one stay.	m	5	385.36	1,926.80
154	Single pedestrian gate shall be 0,9 x 1,2 m high formed of 38mm diameter x 2,8 thick pipe framing all round complete with one 38mm diameter thick x 2,8 mm thick pipe horizontal brace all neatly mitred and welded at intersections, the gate with two strands of 4mm thick galvanised mild steel straining wire.	No	5	1,840.12	9,200.60
155	Single Vehicle gate shall be 3,2 x 1,2 m high formed of 38mm diameter x 2,8 thick pipe framing all round complete with one 38mm diameter thick x 2,8 mm thick pipe horizontal brace all neatly mitred and welded at intersections, the gate with two strands of 4mm thick galvanised mild steel straining wire.	No	5	3,434.89	17,174.45
	<u>Razor barbed wire</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
156	Razor Flat-wrap - To top or bottom of fence - not exceeding 6 strands	m	5	127.44	637.20
157	Concertina Barbed Wire to top of fence	m	5	182.57	912.85
	<u>Sundries</u>				
158	40 x 40 x 2mm angle section @2m, for razor barbed wire support at 500mm length	No	5	40.81	204.05
159	Replace missing Steel Palisade fence Slats 1800mm high made of 30 x 30 x 3mm angle section pickets with top end split and sharpened, welded to top and bottom rails including painting on both sides	No	5	215.31	1,076.55
160	Replace missing Steel Palisade fence Slats 2400mm high made of 30 x 30 x 3mm angle section pickets with top end split and sharpened, welded to top and bottom rails including painting on both sides	No	5	287.06	1,435.30
161	Fix pedestrian gate including lock, hinges, slats, etc	No	5	419.37	2,096.85
162	Replace missing Concrete Palisade fence Slats 1800mm high made of 110 x 70mm reinforced concrete	No	5	239.26	1,196.30
163	Replace missing Concrete Palisade fence Slats 2400mm high made of 110 x 70mm reinforced concrete	No	5	319.02	1,595.10
	<u>Beta fence 3510 galvanised wire panels with adhesion coat coating, minimum 200micron and PVC coated to a perfect and durable finish, minimum 60micron</u>				
164	Panels 1988mm high fixed to 2600mm "Bekafix Secure" PVC coated post at 3050 centres including stainless steel mini spider brackets, M8 x 25 x 2mm bolts, M8 shear nuts and M8 x 50mm cup square and posts 600mm bottom ends cast into and including 15MPa concrete footing in ground, including excavation, ramming, removal of spoil and leaving clean and neat	m	5	1,479.80	7,399.00
165	Panels 2376mm high fixed to 3000mm "Bekafix Secure" PVC coated post at 3050 centres including stainless steel mini spider brackets, M8 x 25 x 2mm bolts, M8 shear nuts and M8 x 50mm cup square and posts 600mm bottom ends cast into and including 15MPa concrete footing in ground, including excavation, ramming, removal of spoil and leaving clean and neat	m	5	3,473.92	17,369.60

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
166	Panels 6000mm high fixed to 2600mm "Bekafix Secure" PVC coated post at 3050 centres including stainless steel mini spider brackets, M8 x 25 x 2mm bolts, M8 shear nuts and M8 x 50mm cup square and posts 600mm bottom ends cast into and including 15MPa concrete footing in ground, including excavation, ramming, removal of spoil and leaving clean and neat	m2	5	851.57	4,257.85
167	PVC coated serrated strip 3000mm long, including backing plates fixed to top of panel	m2	5	851.57	4,257.85
168	Serrated strip 3000mm long, including backing plates fixed to top of panel	m	5	107.94	539.70
169	Hot Dipped Galvanised serrated strip 3000mm long, including backing plates fixed to top of panel	m	5	93.55	467.75
170	Swing gate "Singleskin Flat" wire 3,96mm diameter PVC RAL 7021 MTO 2000mm high x 1000mm wide	No	5	8,744.86	43,724.30
171	Vehicle sliding gate "Single skin Flat" wire 3,96mm diameter PVC RAL 7021 MTO 2000mm high x 6000mm wide	No	5	27,589.62	137,948.10
	<u>Betafence 3510 galvanised wire panels with hot dipped galvanised coating, zincalu super coated to SANS 10244-2:2003 specification</u>		5		0.00
172	Panels 2000mm high fixed to 2600mm "Bekafix Secure" PVC coated post at 3050 centres including stainless steel mini spider brackets, M8 x 25 x 2mm bolts, M8 shear nuts and M8 x 50mm cup square and posts 600mm bottom ends cast into and including 15MPa concrete footing in ground, including excavation, ramming, removal of spoil and leaving clean and neat	m	5	1,236.45	6,182.25
173	Panels 2376mm high fixed to 3000mm "Bekafix Secure" PVC coated post at 3050 centres including stainless steel mini spider brackets, M8 x 25 x 2mm bolts, M8 shear nuts and M8 x 50mm cup square and posts 600mm bottom ends cast into and including 15MPa concrete footing in ground, including excavation, ramming, removal of spoil and leaving clean and neat	m	5	2,486.41	12,432.05

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
174	Panels 6000mm high fixed to 2600mm "Bekafix Secure" PVC coated post at 3050 centres including stainless steel mini spider brackets, M8 x 25 x 2mm bolts, M8 shear nuts and M8 x 50mm cup square and posts 600mm bottom ends cast into and including 15MPa concrete footing in ground, including excavation, ramming, removal of spoil and leaving clean and neat	m2	5	710.61	3,553.05
175	Hot Dipped Galvanised serrated strip 3000mm long, including backing plates fixed to top of panel	m	5	93.55	467.75
176	Swing gate "Singleskin Flat" wire 3,96mm diameter PVC RAL 7021 MTO 2000mm high x 1000mm wide	No	5	6,491.55	32,457.75
177	Vehicle sliding gate "Singleskin Flat" wire 3,96mm diameter PVC RAL 7021 MTO 2000mm high x 6000mm wide	No	5	24,800.81	124,004.05
<u>CARPOTS WITH ROOF SHEETING TO SLIGHT FALLS</u>					
<u>Carpots comprising the following: concrete foundations for columns to be 20Mpa concrete, 500 x 500 x 600mm deep including all excavations, backfilling, compaction, carting away, etc; columns 76 x 76 x 3mm hot rolled tubing with 150 x 150 x 3mm base plates and 200 x 70 x 6mm top flanges; columns 2600mm minimum height, beams; 76 x 76 x3mm hot rolled tubing with closed ends; beams bolted to columns with two 10 x 100mm bolts and nuts at each column; purlins; 150 x 75 x 20 x3mm hot rolled lipped channels bolted to cleats on beams with 0,5mm thick chromadek finished IBR profile roof sheeting; all steelwork cleaned with degreaser and painted with one each of red oxide and universal primer with two coats enamel paint</u>					
178	Carpot comprising one bay, 2,5 x 5,0m on plan, including cutting of existing paving blocks around columns	No	5	7,346.99	36,734.95
179	Range of carpots (one row) comprising two bays, each bay 2,5 x 5,0m on plan, with carpot structure stepped over sloping site if required, including cutting of existing paving blocks around columns	No	5	13,959.27	69,796.35
180	Range of carpots (one row) comprising three bays, each bay 2,5 x 5,0m on plan, with carpot structure stepped over sloping site if required, including cutting of existing paving blocks around columns	No	5	20,938.90	104,694.50

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
181	Range of carpots (one row) comprising four bays, each bay 2,5 x 5,0m on plan, with carpot structure stepped over sloping site if required, including cutting of existing paving blocks around columns	No	5	27,918.55	139,592.75
182	Range of carpots (one row) comprising five bays, each bay 2,5 x 5,0m on plan, with carpot structure stepped over sloping site if required, including cutting of existing paving blocks around columns	No	5	34,898.18	174,490.90
183	Range of carpots (one row) comprising six bays, each bay 2,5 x 5,0m on plan, with carpot structure stepped over sloping site if required, including cutting of existing paving blocks around columns	No	5	41,877.82	209,389.10
	<u>COURTS</u>				
	<u>Clay Courts "NEW"</u>				
184	Volleyball, netball, basketball, multi-purpose courts including markings (earthworks measured elsewhere)	m2	5	422.62	2,113.10
	<u>Refurbishment of Clay Courts</u>				
185	Volleyball, netball, basketball, multi-purpose courts including markings	m2	5	240.57	1,202.85
186	Volleybal, netball, basketball, multi-purpose courts including markings in bad conditions	m2	5	240.57	1,202.85
	<u>GRADING</u>				
	<u>Grading of soccer fields</u>				
187	Open face excavation to reduce levels	m2	5	25.49	127.45
	<u>Enviro Outdoor Furniture or equally approved</u>	H3			
188	Plastic jungle gym combo	No	5	25,832.42	129,162.10
189	Plastic two seater sleeper bench 1200mm with back and set in concrete base including all excavations and formwork	No	5	4,857.52	24,287.60
190	Plastic three seater sleeper bench 1800mm with back and set in concrete base including all excavations and formwork	No	5	4,380.91	21,904.55

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
191	Plastic five seater picnic set with open back bench and table set in concrete base including all excavations and formwork	No	5	8,559.91	42,799.55
192	Plastic square swivel bin	No	5	1,811.84	9,059.20
193	Rubber playground flooring	m2	5	530.54	2,652.70
	<u>Steel seaters, poles, posts, etc.</u>				
	<u>Epoxy coated</u>				
194	Four seater swing with A-frame Code "S2 Junior"	No	5	4,226.15	21,130.75
195	Tharad or equally approved three seater senior swing	No	5	13,469.56	67,347.80
196	50mm diameter aluminium mini soccer goal posts set, size 1000 x 1500 x 1000m with nets	No	5	17,724.08	88,620.40
197	Van Dyck or equally approved easy soccer outdoor carpeting secured with resin based glue to concrete surfaces	m2	5	585.16	2,925.80
	<u>Jungle Gym World or equally approved</u>				
198	Code "SP 3" Ball throwing stand	No	5	2,591.66	12,958.30
199	Code "JG3" Toddler's Beginners	No	5	9,297.51	46,487.55
200	Code "JG4" Toddler's Advanced	No	5	10,142.74	50,713.70
201	Code "JG 8" Junior Jungle Gym	No	5	10,987.97	54,939.85
202	Code "JG 9" Junior Jungle Gym	No	5	12,340.33	61,701.65
203	Code "JG 10" Senior Jungle Gym	No	5	16,059.34	80,296.70
204	Code "JG 11" Senior De Lux Jungle Gym	No	5	17,749.80	88,749.00
205	Code "JG 12" Super Senior Jungle Gym	No	5	18,978.62	94,893.10
206	Code "JG 25 A" No Tyre Tunnel	No	5	20,285.47	101,427.35
207	Code "JG 25 A" With Tyre Tunnel	No	5	21,195.73	105,978.65
208	Implanted Heavy Duty Junior Jungle Gym	No	5	16,904.56	84,522.80
209	One Seater Implanted Swing	No	5	4,226.15	21,130.75

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
210	Two-Seater A-Frame Swing	No	5	3,380.91	16,904.55
211	Four-Seater A-Frame Swing	No	5	4,226.15	21,130.75
212	Four-Seater Implanted Swing	No	5	6,761.82	33,809.10
213	Carousel Swing	No	5	8,452.28	42,261.40
214	See Saw Swing	No	5	4,226.15	21,130.75
215	Implanted Four Seat Swing	No	5	13,523.65	67,618.25
216	Code "SR 1" Rocking Horse	No	5	845.23	4,226.15
217	Code "SR 2" Four Seat Rocking Sleigh	No	5	4,226.15	21,130.75
218	Code "HD Saw" Implanted Four Seat See Saw	No	5	6,761.82	33,809.10
219	Code " HD SS" Implanted Slide Stand with 5m steel slide	No	5	20,285.47	101,427.35
220	Code "SP 8B" One soccer goal posts (pre-school)	No	5	1,690.46	8,452.30
221	Code "SP 5B" netball pole 2000mm high with ring and net	No	5	676.18	3,380.90
222	Code "SP 6B" netball pole 3000mm high with ring and net	No	5	845.23	4,226.15
223	Code "SP 8A" Soccer goal posts (pre-school)	No	5	3,380.91	16,904.55
224	Code "SP 5A" Netball posts set 2000mm high with ring and net	No	5	1,352.37	6,761.85
225	Code "SP 6A" netball pole 3000mm high with ring and net cast into concrete	No	5	1,690.46	8,452.30
226	Code "SP1" Basket and netball wall mounted ring	No	5	338.09	1,690.45
227	Code "SP2" Basketball ring with 3000mm high stand and blocker	No	5	1,352.37	6,761.85
228	Code "SP4" Jogging barrel	No	5	1,521.41	7,607.05
229	Code "SP7" set of implant rugby posts (pre-school)	No	5	3,380.91	16,904.55
	<u>Gimtrac or equally approved</u>				
230	Code "SOCC012" 3000 x 2000 x 1000mm mini soccer goal post set	No	5	12,070.46	60,352.30

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
231	Code "SOCC012" 1000 x 1500 x 1000mm Aluminium mini soccer goal post set	No	5	8,367.76	41,838.80
232	Code "SOCC012" Five seater aluminium soccer shelter	No	5	43,861.41	219,307.05
	<u>PREFABRICATED SHELTERS</u>				
	<u>WENDY HUTS</u>				
233	2400 x 2400mm "Rock Hard" wendy house with dune walls, galvanised roof including concrete surface bed	No	5	15,298.63	76,493.15
	<u>PHYSICAL BARRIERS</u>				
	<u>BOOM GATES</u>				
234	Steel boom gates not exceeding 6000mm long	No	5	17,418.47	87,092.35
	<u>BOLLARDS</u>				
235	200mm Diameter precast concrete bollards not exceeding 1500mm	No	5	595.39	2,976.95
236	200mm Diameter steel bollards with concrete infill not exceeding 1500mm	No	5	765.86	3,829.30
237	400 x 400mm precast concrete dustbin not exceeding 1500mm high	m	5	2,010.34	10,051.70
	<u>TIMBER RAILING</u>				
238	Tanalith treated vertical lath (wood) handrails 1200mm high	m	5	407.27	2,036.35
	<u>RETAINING WALL BLOCKS</u>				
239	Terraforce or Loffelstein or equally approved retaining wall blocks or equivalent retaining wall smooth finish closed face @ 9 blocks per m2. Including AG900 Bidum	m2	5	828.06	4,140.30
240	Terraforce or Loffelstein or equally approved retaining wall blocks or equivalent retaining wall smooth finish closed face @6,5 blocks per m2. Including AG900 Bidum. Earthworks elsewhere.	m2	5	634.84	3,174.20
241	Terraforce or Loffelstein or equally approved retaining wall blocks or equivalent retaining wall smooth finish closed face @9 blocks per m2. Including AG900 Bidum	m2	5	883.27	4,416.35

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
242	Terraforce or Loffelstein or equally approved retaining wall blocks or equivalent retaining wall smooth finish closed face @6,5 blocks per m2.Including AG900 Bidum. Earthworks elsewhere.	m2	5	674.71	3,373.55
	<u>GRASS BLOCKS</u>				
243	Loffelstein grass block or equivalent 600x400x120mm including earthworks @ 4.1 blocks per m2.	m2	5	492.91	2,464.56
					4,161,642.64

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	SUB-TOTAL <i>(Carried To Summary)</i>				44,208,595.89
	<u>BILL No. 19</u>				
	<u>MISCELLANEOUS CHARGES-GENERAL BUILDING ITEMS</u>				
	<u>SUPPLEMENTARY PREAMBLES</u>				
	General building services will be carried out at the discretion of The City of Ekurhuleni Department Head and Project Managers.				
	Where general building services are required, and the value can not be ascertained in terms of the rates provided by the contractor in Schedules No.1 to 17, this work will be executed in terms of the contract based on the rates hereunder.				
	<u>Call-out Charge</u>				
1	Call-out charge (once off charge applicable to work under R30,000.00 VAT inclusive)	Item	1 1	416.86	
2	Call-out charge (once off charge applicable to an emergency call-out which takes place after hours, weekends and holidays)	Item	1 1	595.51	
3	Preliminary and General (Works between R30,000.00 and R500,000.00 @ 7%) VAT exclusive	%IT	1 1	29.18	
4	Preliminary and General (Works between R500,000.00 and R5 million @ 5%) VAT exclusive	%IT	1	41.69	
	<u>LABOUR RATES - LIMITED TO BILL NO.16 (For new items with no rates)</u>				
	<u>GENERAL BUILDING</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Normal hours</u>				
5	General Labour (R220 per day)	Hrs	9	24.44	219.96
6	Semi Skilled (R297 per day)	Hrs	9	33.00	297.00
7	Artisan (R450 per day)	Hrs	9	50.00	450.00
8	Site Supervisor (R880 per day)	Hrs	9	97.77	879.93
	<u>After normal hours and Saturdays</u>				
9	General Labour	Hrs	9	36.66	329.94
10	Semi Skilled	Hrs	9	49.50	445.50
11	Artisan	Hrs	9	75.00	675.00
12	Contracts Manager	Hrs	9	146.66	1,319.90
	<u>Extra over - Sundays and holidays (for eight hour shift)</u>				
13	General Labour	Hrs	9	48.88	439.92
14	Semi Skilled	Hrs	9	66.00	594.00
15	Artisan	Hrs	9	100.00	900.00
16	Contracts Manager	Hrs	9	195.54	1,759.86
	<u>SALARY TO THE COMMUNITY LIAISON OFFICE</u>				
17	For the Community Liaison Officer (CLO) salary, including cell phone allowance. (For Projects exceeding R650,000.00 and a period of 3 months)	Hrs	9	25.00	225.00
	<u>SCAFFOLDING (To be used as directed by the Project Manager and to be deducted in whole or in part if not required)</u>				
18	Scaffolding exceeding 3,6m high and not exceeding 10m wide in normal areas, 1-storey	Hrs	9	338.70	3,048.30
19	Scaffolding exceeding 3,6m high and not exceeding 3m wide in confined areas, 1-storey	Hrs	9	338.70	3,048.30
20	Scaffolding not exceeding 8m high not exceeding 10m wide (Single Tower) in normal areas, 2-storey	Hrs	9	416.86	3,751.74

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
21	Scaffolding not exceeding 8m high not exceeding 3m wide (Single Tower) in confined/restricted areas, 2-storey	Hrs	9	416.86	3,751.74
22	Scaffolding exceeding 12m high and exceeding 10m wide in normal areas 3- storey	Hrs	9	541.91	4,877.19
23	Scaffolding exceeding 12m high and exceeding 10m wide in normal areas - 3-storey	Hrs	9	541.91	4,877.19
24	Scaffolding exceeding 16m high not exceeding 10m wide in normal areas, 4-storey	Hrs	9	602.12	5,419.08
25	Scaffolding exceeding 20m high not exceeding 10m wide in normal areas, 5-storey	Hrs	9	677.39	6,096.51
26	Scaffolding exceeding 24m high not exceeding 10m wide in normal areas, 5-storey	Hrs	9	774.16	6,967.44
27	Scaffolding exceeding 28m high not exceeding 10m wide in normal areas, 6-storey	Hrs	9	903.18	8,128.62
28	Scaffolding exceeding 32m high not exceeding 10m wide in normal areas, 7-storey	Hrs	9	1,083.83	9,754.47
29	Scaffolding exceeding 36m high not exceeding 10m wide in normal areas, 8-storey	Hrs	9	1,354.79	12,193.11
<u>UNBLOCKING AND PUMPING</u>					
30	Un-blocking of Drains and Manholes using sewer rods	Hrs	9	357.30	3,215.70
31	Water ram 32mm to 50mm dia waste pipes	Hrs	9	452.59	4,073.31
32	Electro mechanical, spring cable machine from 50 to 150mm dia	Hrs	9	893.26	8,039.34
33	Pumping out of non-contaminated water from basements or pools into roads, stormwater channels etc	Hrs	9	297.75	2,679.75
34	Pumping out of contaminated water from basements into nearest sewer manholes	Hrs	9	321.57	2,894.13
35	Disinfecting or Hygiene to contaminated areas, due to sewerage or other	Hrs	9	26.20	235.80
<u>PLANT HIRE</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Including miscellaneous items</u>				
36	Concrete Mixer STD HD GX160 5HP - Drum volume 400L dry mix input 310L, Wet Mix output 260L	Hrs	9	291.63	2,624.67
37	Concrete Saw 13HP GX350 - 13Hp petrol engine, push type, blade size350mm Diamond Blade	Hrs	9	238.61	2,147.49
38	5kVa Generator	Hrs	9	172.32	1,550.88
39	10kVA Generator	Hrs	9	238.61	2,147.49
40	19 cfm Towable Compressor including miscellaneous	Hrs	9	463.96	4,175.64
41	50mm Water pump	Hrs	9	198.85	1,789.65
42	80mm Water Pump	Hrs	9	238.61	2,147.49
43	Jolly Jumper / Rammer	Hrs	9	278.38	2,505.42
44	Concrete breaker / hammer	Hrs	9	172.32	1,550.88
45	Hydraulic Jack	Hrs	9	172.32	1,550.88
46	Crane Truck 20ton	Hrs	9	596.52	5,368.68
47	12000 l Water Truck	Hrs	9	503.73	4,533.57
48	6m high mobile scaffolding	Hrs	9	172.32	1,550.88
					135,231.35

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	SUB-TOTAL (<i>Carried To Summary</i>)				44,343,827.24
	BILL No. 20				
	<u>INSPECTION AND REPORT</u>				
	Carrying out detailed inspection and reporting to the Project Manager on roof covering defaults including ridges, hips, valleys, flashings, etc caused by cracks, breakages, dislodgement, failure, etc.				
	<u>Roof area with pitch not exceeding 50 degrees and not exceeding 500m²</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	Thatch/Concrete or terra cotta tiles	Item	1	2,138.64	2,138.64
2	Profiled fibre-cement sheeting	Item	1	1,944.22	1,944.22
3	Profiled metal sheeting	Item	1	1,749.79	1,749.79
	<u>Roof area with pitch not exceeding 50 degrees, exceeding 500m² and not exceeding 1000m²</u>				
4	Concrete or terra cotta tiles	Item	1	3,499.58	3,499.58
5	Profiled fibre-cement sheeting	Item	1	3,243.31	3,243.31
6	Profiled metal sheeting	Item	1	2,916.33	2,916.33
	<u>Roof area with pitch not exceeding 50 degrees, exceeding 1000m² and not exceeding 2000m²</u>				
7	Concrete or terra cotta tiles	Item	1	5,832.64	5,832.64
8	Profiled fibre-cement sheeting	Item	1	5,408.45	5,408.45
9	Profiled metal sheeting	Item	1	4,860.53	4,860.53
	<u>Roof area with pitch not exceeding 50 degrees and exceeding 2000m²</u>				
10	Concrete or terra cotta tiles	Item	1	8,748.96	8,748.96
11	Profiled fibre-cement sheeting	Item	1	7,582.43	7,582.43
12	Profiled metal sheeting	Item	1	6,318.69	6,318.69
					54,243.57
	SUB-TOTAL <i>(Carried To Summary)</i>				44,398,070.81
	<u>BILL NO. 21</u>				
	<u>PLUMBING AND DRAINAGE</u>				
	<u>PREAMBLES</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	Tenderers are referred to the relevant clauses in the Model Preambles for Trades (Latest Edition) as published by the Association of South African Quantity Surveyors and to the Supplementary Preambles which are incorporated in these Bills of Quantities before pricing this schedule. <u>SUPPLEMENTARY PREAMBLES</u> <u>Rates</u> Rates shall include travel to and from site within a 30km. radius of the City Centre, Materials, Labour, Tools, Equipment, Contractors Overheads and Profit except where otherwise stated. <u>Description</u> Where "Replace" or "Replacing" appears in this document it shall be deemed to include taking up/out and carting away from site <u>uPVC pipes and fittings</u> Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings Soil, waste and vent pipes and fittings shall be solvent weld jointed <u>uPVC pressure pipes and fittings</u> Pipes of water supply shall be of the class described. Pipes of 40mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings. Pipes of 50mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints. <u>Copper pipes</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	Pipes shall be hard drawn and half-hard pipes of the class stated. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard) class 2 (half-hard) and class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fitting to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground <u>Reducing fittings</u> Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm only the largest end or branch size is given. Should the contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm all sizes are given and no claim for extra bushes, reducers, etc will be entertained <u>Wire gratings</u> Descriptions of gutter outlets etc shall be deemed to include wire balloon gratings <u>Septic tanks</u> Description of septic tanks shall be deemed to include excavations, bedding and jointing, concrete base slab, jointing to drains and backfilling, compaction, etc all in accordance with manufacturer's instructions <u>Exposed concrete surfaces</u> Exposed surfaces of concrete stormwater channels, cover slabs, inspection eye marker slabs, gulley tops, cleaning eye tops, catch pits, inspection chambers, etc. shall be finished smooth with plaster. <u>Excavations</u> No claim for rock excavation will be entertained unless the contractor has timeously notified the quantity surveyor thereof prior to backfilling.				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	Soft and Hard rock shall be as defined in "Earthworks".				
	<u>Laying, backfilling, bedding, etc of pipes</u>				
	Pipes shall be laid and bedded and trenches shall be carefully backfilled in accordance with manufacturers' instructions				
	Where no manufactures' instructions exist pipes shall be laid in accordance with clause 5,1 and 5,2 of each of the following: SABS 1200 L : Medium-pressure pipelines : Sewers : Stormwater drainage Pipe trenches etc shall be backfilled in accordance with clause 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SABS 1200 LB : Bedding (Pipes).				
	Unless otherwise described bedding of rigid pipes shall be class B bedding				
	<u>Flush pans</u>				
	Flush pans shall have straight or side outlets and "P" or "S" traps as necessary				
	<u>Stainless steel basins, sinks, wash troughs, urinals, etc.</u>				
	Units shall have standard aprons on all exposed edges and tiling keys against wall where applicable.				
	<u>Waste unions</u>				
	Descriptions of waste unions shall be deemed to include rubber or vulcanite plugs and chains fixed to fittings.				
	<u>CLEAR SEWER AND WASTE WATER BLOCKAGE</u>				
	<u>Locate blockage, clear sewer pipes by means of rodding distances between access chambers/junctions (referred to as "Pipe Length") not exceeding 10m and removing all obstructions, etc. leaving pipes open and free flowing including disposal of all materials causing blockage, excavations and backfilling where required.</u>				
	<u>Pipe length not exceeding 10m Length</u>				
1	110mm diameter pipe not exceeding 10m	Item	6	298.27	1,789.62
2	160mm diameter pipe not exceeding 10m	Item	6	308.86	1,853.16

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Pipe length up to 20 m</u>		6		
3	110mm diameter pipe, exceeding 10m but not exceeding 20m	Item	6	441.69	2,650.12
4	160mm diameter pipe, exceeding 10m but not exceeding 20m	Item	6	454.68	2,728.07
	<u>Locate blockage, clear waste pipes by means of rodding distances between access eyes/open end (referred to as "Pipe Length") not exceeding 2m and removing all obstructions, etc. leaving pipes open and free flowing including disposal of all materials causing blockage.</u>				
	<u>Pipe length not exceeding 10m Length</u>				
5	Not exceeding 40mm diameter pipe, not exceeding 10m	Item	6	470.60	2,823.60
6	Exceeding 40mm diameter pipe and not exceeding 75mm diameter pipe, not exceeding 10m	Item	6	543.49	3,260.94
	<u>Pipe length exceeding 5m not exceeding 10m</u>				
7	Not exceeding 40mm diameter pipe, exceeding 10m but not exceeding 20m	Item	6	470.60	2,823.60
8	Exceeding 40mm diameter pipe and not exceeding 75mm diameter pipe, exceeding 10m but not exceeding 20m	Item	6	543.49	3,260.94
	<u>Sundries</u>				
9	Unblock 'P', 'S' or bottle trap not exceeding 40mm diameter	No	6	112.69	676.14
10	Unblock Gulley, WC pan, Trough urinal trap, etc. not exceeding 110mm diameter	No	6	139.19	835.14
	<u>CLEAR STORMWATER BLOCKAGE</u>				
	<u>Clean catch pit, with internal dimensions not exceeding 900 x 500mm or 750mm diameter, by removing all silt, etc. leaving all internal surfaces and sump free from any dirt or debris including disposal of all removed material.</u>				
	<u>Catch pits not exceeding 2m deep</u>				
11	Not exceeding 1,0m deep	Item	6	437.45	2,624.70
12	Exceeding 1,0m and not exceeding 2m deep	Item	6	523.62	3,141.72

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Catch pits exceeding 2m deep</u>				
13	Exceeding 2,0m and not exceeding 3,0m deep	Item	6	575.98	3,455.88
14	Exceeding 3,0m and not exceeding 4,0m deep	Item	6	633.57	3,801.42
	<u>Clean catch pit, with internal dimensions not exceeding 1050 x 750mm or 1000mm diameter, by removing all silt, etc. leaving all internal surfaces and sump free from any dirt or debris including disposal of all removed material.</u>				
15	Not exceeding 1,0m deep	Item	6	437.45	2,624.70
16	Exceeding 1,0m and not exceeding 2,0m deep	Item	6	523.62	3,141.72
17	Exceeding 2,0m and not exceeding 3,0m deep	Item	6	603.16	3,618.96
18	Exceeding 3,0m and not exceeding 4,0m deep	Item	6	723.78	4,342.68
19	Exceeding 4,0m and not exceeding 5,0m deep	Item	6	868.53	5,211.18
	<u>Clean and pump sewer manholes, with internal dimensions not exceeding 1050 x 750mm or 1000mm diameter, by removing all silt, etc. leaving all internal surfaces and sump free from any dirt or debris including disposal of all removed material.</u>				
20	Not exceeding 1,0m deep	Item	6	546.81	3,280.86
21	Exceeding 1,0m and not exceeding 2,0m deep	Item	6	654.51	3,927.06
22	Exceeding 2,0m and not exceeding 3,0m deep	Item	6	753.94	4,523.64
23	Exceeding 3,0m and not exceeding 4,0m deep	Item	6	904.72	5,428.32
24	Exceeding 4,0m and not exceeding 5,0m deep	Item	6	1,085.37	6,512.22
	<u>Clean pipes by means of rodding distances between access chambers/catch pits (referred to as "Pipe Length") not exceeding 30m and removing all silt, etc. leaving all internal surfaces free from any dirt or debris including disposal of all removed material.</u>				
	<u>Pipe length not exceeding 15m length</u>				
25	Not exceeding 225mm nominal diameter	Item	6	437.45	2,624.70

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
26	Exceeding 225mm and not exceeding 300mm nominal diameter	Item	6	523.62	3,141.72
27	Exceeding 300mm and not exceeding 450mm nominal diameter	Item	6	603.16	3,618.96
	<u>Pipe length exceeding 30m Length</u>				
28	Not exceeding 225mm nominal diameter	Item	6	656.18	3,937.08
29	Exceeding 225mm and not exceeding 300mm nominal diameter	Item	6	785.42	4,712.52
30	Exceeding 300mm and not exceeding 450mm nominal diameter	Item	6	904.72	5,428.32
	<u>Clean channel drains by removing all silt, etc. leaving all surfaces free from any dirt or debris including lifting and rebedding covers where required and disposal of all removed material.</u>				
	<u>Channels not exceeding 500mm deep</u>				
31	Width not exceeding 250mm	m	6	45.94	275.64
32	Width exceeding 250mm and not exceeding 500mm	m	6	53.60	321.60
33	Width exceeding 500mm and not exceeding 750mm	m	6	64.33	385.98
34	Width exceeding 750mm and not exceeding 1000mm	m	6	80.40	482.40
	<u>CLEAR GUTTER BLOCKAGE / DEBRIS</u>				
	<u>Clean out gutters by removing all silt, etc. including rodding where necessary, leaving all surfaces free from any dirt or debris including lifting and refixing grille covers where required and disposal of all removed material.</u>				
	<u>Gutters not exceeding 3m above base level</u>				
35	Eaves or box gutter not exceeding 200mm wide	m	6	14.58	87.48
36	Eaves or box gutter exceeding 200mm wide and not exceeding 500mm wide	m	6	17.90	107.40

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Gutters exceeding 3m above base level not exceeding 6m above base level</u>				
37	Eaves or box gutter not exceeding 200mm wide	m	6	20.87	125.22
38	Eaves or box gutter exceeding 200mm wide and not exceeding 500mm wide	m	6	22.80	136.80
	<u>Sundries</u>				
39	Rainwater downpipe not exceeding 175mm x 100mm or 150mm diameter including bends, elbows, etc.	m	6	22.80	136.80
40	Full - Bore outlets not exceeding 150mm diameter	No	6	72.91	437.46
	<u>REPLACE DAMAGED UNDERGROUND SEWER PIPE AND FITTINGS</u>				
	<u>Locate, excavate for and replace damage to uPVC drain pipe and / or fittings in landscaped areas including backfilling, compacting, etc. and leave in good working order.</u>				
	<u>Laid in excavations not exceeding 1m deep</u>				
41	110mm Ø pipe	m	18	252.92	4,552.56
42	160mm Ø pipe	m	18	341.75	6,151.50
	<u>Laid in excavations exceeding 1m and not exceeding 2m deep</u>				
43	110mm Ø pipe	m	18	290.84	5,235.12
44	160mm Ø pipe	m	18	393.02	7,074.36
	<u>uPVC fittings</u>				
45	110mm Access lid	No	12	50.37	604.44
46	110mm Gulley grate	No	12	50.37	604.44
47	110mm Plain bend	No	12	78.86	946.32
48	110mm Access bend	No	12	86.76	1,041.12
49	110mm Plain junction	No	12	86.76	1,041.12
50	110mm Access junction	No	12	86.76	1,041.12

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
51	110mm Rodding eye	No	12	86.76	1,041.12
52	110mm Gulley head and grate	No	12	95.45	1,145.40
53	110mm Gulley 'P' trap	No	12	105.02	1,260.24
54	160mm Access lid	No	12	55.68	668.16
55	160mm Plain bend	No	12	90.70	1,088.40
56	160mm Access bend	No	12	99.79	1,197.48
57	160mm Plain junction	No	12	99.79	1,197.48
58	160mm Access junction and cover	No	12	99.79	1,197.48
59	160mm Rodding eye	No	12	99.79	1,197.48
60	160 x 110mm Taper pipe	No	12	102.33	1,227.96
	<u>Locate, excavate for and replace damage to Vitrified Clay drain pipe and / or fittings in landscaped areas including backfilling, compacting, etc. and leave in good working order.</u>				
	<u>Laid in excavations not exceeding 1m deep</u>				
61	100mm pipe	m	12	136.69	1,640.28
62	150mm pipe	m	12	157.19	1,886.28
	<u>Laid in excavations exceeding 1m and not exceeding 2m deep</u>				
63	100mm pipe	m	12	160.70	1,928.40
64	150mm pipe	m	12	184.79	2,217.48
	<u>Vitrified clay fittings</u>				
65	100mm Access lid	No	12	72.91	874.92
66	100mm Gully grate	No	12	72.91	874.92
67	100mm Access bend	No	12	86.76	1,041.12
68	100mm Access junction	No	12	95.45	1,145.40

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
69	100mm Roding eye	No	12	95.45	1,145.40
70	150 x 100mm taper pipe	No	12	142.56	1,710.72
71	100mm Gulley head and grate	No	12	299.57	3,594.84
72	100mmGulley 'P' or 'S' trap	No	12	299.57	3,594.84
	<u>Sundries (For storm water drainage ONLY)</u>				
73	15MPa/20mm Unreinforced concrete encasing to 110mm horizontal or vertical pipe including any necessary formwork.	m	3	68.93	206.79
74	Take out, set aside concrete block or brick paving and reinstate paving including sand bedding on completion of repair works.	m2	3	99.43	298.29
75	Break up and remove concrete surface not exceeding 100mm thick and reinstate including finishers to match existing on completion of repair works.	m2	3	311.52	934.56
76	Break up and remove tarmac asphalt surface and reinstate to match existing on completion of repair works.	m2	3	311.52	934.56
77	Replace damaged concrete / brick gulley surround including making good existing finishers.	No	3	503.73	1,511.19
78	Break up and remove concrete manhole top slab including cast iron frame and cover, replace with 125mm thick precast concrete adaptor slab to suit manhole size complete with 560mm opening and Heavy duty concrete lid.	No	3	2,193.87	6,581.61
	<u>REPLACE DAMAGED GRATINGS, MANHOLE COVERS, ETC.</u>				
	<u>Carefully break out from concrete existing damaged frame and grating or manhole cover, replace with new including making good all existing finishers and leave in good working order.</u>				
79	560mm Diameter 125mm thick precast concrete removable cover	No	3	1,133.39	3,400.17
80	450 x 450mm x 28,5kg Type 14B cast iron single seal manhole cover and frame.	No	3	1,133.39	3,400.17
81	450 x 600mm x 68kg Type 9D cast iron single seal manhole cover and frame.	No	3	1,782.94	5,348.82

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
82	530 x 530mm x 67kg Type 12 cast iron single seal manhole cover and frame.	No	3	2,344.87	7,034.61
83	450 x 600mm x 72kg Type 8A cast iron double seal manhole cover and frame.	No	3	2,783.76	8,351.28
	<u>Polymer lockable concrete manhole covers - Solid Circular Manhole Covers</u>				
84	705mm dia Type 1A solid circular manhole cover and frame for sewer manhole, including bedding locks measured elsewhere	No	3	4,881.27	14,643.81
85	605mm dia Type 2A solid circular manhole cover and frame in Heavy traffic, including bedding locks measured elsewhere	No	3	3,004.74	9,014.22
86	605mm dia Type 4A solid circular manhole cover and frame in Pavements, including bedding locks measured elsewhere	No	3	1,723.40	5,170.20
87	540mm dia Telkom 500 solid circular manhole cover and frame in Pavements, including bedding locks measured elsewhere	No	3	1,407.52	4,222.56
	<u>Polymer lockable concrete manhole covers - Drainage Circular Manhole Covers</u>				
88	705mm dia Type 1B Drainage Circular Manhole cover and frame for Drainage, including bedding locks measured elsewhere	No	3	4,386.56	13,159.68
89	605mm dia Type 2B Drainage Circular Manhole cover and frame in Pavements, including bedding locks measured elsewhere	No	3	2,966.31	8,898.93
	<u>Polymer Valve Chambers / Belltobies</u>				
90	145mm dia x 320 mm deep Type 3A Valve Chamber and cover complete in heavy traffic, including bedding	No	3	790.59	2,371.77
91	140mm dia x 230 mm deep Type 3B Valve Chamber and cover complete in heavy traffic, including bedding	No	3	65.39	196.17
	<u>Polymer Rectangular Hydrant Box lockable locks for vandalism</u>				
92	405 x 320 Type 5 Hydrant cover and frame complete in pavements, including bedding locks measured elsewhere	No	3	998.10	2,994.30
93	580 x 270 Type 5A "City of Ekurhuleni" Hydrant cover and frame complete in pavements, including bedding locks measured elsewhere	No	3	678.05	2,034.15

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Polymer Rectangular Gulley Grating and Frame</u>				
94	400 x 575 mm Type T8 Gulley Grate and Frame complete for roads, including bedding locks measured elsewhere	No	3	1,970.13	5,910.39
95	400 x 450mm Three Slot Gulley Grate and Frame complete for roads, including bedding locks measured elsewhere	No	3	2,216.04	6,648.12
	<u>Polymer Square and Rectangular Manhole Covers</u>				
96	305 x 305mm Type 300SQ Square Manhole Cover and frame for walkways, including bedding, locks measured elsewhere.	No	3	1,141.65	3,424.95
97	450 x 450mm Type 450sq M Square Manhole Cover and frame Medium Duty, including bedding, locks measured elsewhere.	No	3	1,355.97	4,067.91
98	450 x 450mm Type 450sq 10 ton Square Manhole Cover and frame Heavy Duty, including bedding, locks measured elsewhere.	No	3	2,941.07	8,823.21
99	610 x 610mm Type 610sq Square Manhole Cover only without frame, including bedding, locks measured elsewhere.	No	3	1,208.61	3,625.83
100	660 x 660mm Type 9A Square Manhole Cover with Frame light Duty, including bedding, locks measured elsewhere.	No	3	1,707.83	5,123.49
101	660 x 660mm Type 9B Square Manhole Cover with Frame Medium Duty, including bedding, locks measured elsewhere.	No	3	1,957.43	5,872.29
102	450 x 600mm Type 450x600HD Rectangular Manhole Cover with Frame Heavy Duty, including bedding, locks measured elsewhere.	No	3	3,012.30	9,036.90
103	670 x 525mm Type 9D Rectangular Manhole Cover with Frame Medium Duty, including bedding, locks measured elsewhere.	No	3	1,626.04	4,878.12
104	930 x 930mm Type 900sq Square Manhole Cover with Frame light Duty, including bedding, locks measured elsewhere.	No	3	2,806.34	8,419.02
105	990 x 990mm Type 900HD Square Manhole Cover with Frame Heavy Duty, including bedding, locks measured elsewhere	No	1	10,334.79	10,334.79
	<u>CONSTRUCTED NEW INSPECTION CHAMBER</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Excavate in earth or pickable material for, and build inspection chamber with 150mm thick 15MPa/20mm concrete bottom extending 100mm all round manhole perimeter, with one brick sides of 14MPa bricks in class I mortar, the internal faces of brickwork rendered in one coat cement plaster steel trowelled smooth and covered with a 150mm thick 25MPa/20mm concrete top of walls to finish flush with surface of ground and finished on exposed faces with 25mm thick untinted granolithic with all salient angles rounded and rebated on the inner edges for manhole cover and frame (elsewhere measured); the bottom to be benched up in 15MPa/20mm concrete finished smooth including backfilling and compacting to external walls as required.</u>				
106	Inspection chamber 450 x 600mm and not exceeding 750mm deep internally.	No	1	9,312.73	9,312.73
107	Inspection chamber 900 x 600mm and exceeding 750mm and not exceeding 1000mm deep internally.	No	1	9,103.55	9,103.55
108	Inspection chamber 900 x 600mm and exceeding 1000mm and not exceeding 1250mm deep internally.	No	1	9,894.34	9,894.34
109	Inspection chamber 900 x 900mm and exceeding 1250mm and not exceeding 1500mm deep internally.	No	1	10,683.90	10,683.90
	<u>Excavate in earth or pickable material for, and build inspection chamber with 200mm thick 15MPa/20mm cast in situ concrete bottom extending 100mm all round manhole perimeter, with precast concrete circular shaft sections jointed and sealed with Denso Seal strip, covered with a precast concrete top rebated on the inner edges for manhole cover and frame (elsewhere measured) finishing flush with surface of ground; the bottom to be benched up in 15MPa/20mm concrete finished smooth including backfilling and compacting to external shaft walls as required.</u>				
110	Inspection chamber 750mm diameter and not exceeding 750mm deep internally	No	1	9,312.73	9,312.73
111	Inspection chamber 750mm diameter and exceeding 750 and not exceeding 1000mm deep internally	No	1	9,103.55	9,103.55
112	Inspection chamber 750mm diameter and exceeding 1000mm and not exceeding 1250mm deep internally	No	1	9,894.34	9,894.34

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
113	Inspection chamber 750mm diameter and exceeding 1250mm and not exceeding 1500mm deep internally	No	1	10,683.90	10,683.90
114	Inspection chamber 750mm diameter and exceeding 2000mm and not exceeding 3000mm deep internally with the lower 1,5m depth increased to 1250mm diameter and 150mm precast concrete reducer slab over enlarged bottom portion.	No	1	12,871.45	12,871.45
<u>PRE-FABRICATED TOILETS</u>					
<u>Supply and Install Water Bourne Prefabricated Concrete Toilet - ROCLA or equivalent</u>					
115	Precision-cast Latrine top structure Panel toilet system, made up of 30MPa concrete. Consisting of 1 x Concrete Roof Panel, 2 x Side Panels, 1 x Rear wall panel, 1 x Floor Slab. Including 1 x Stainless Steel door with lockable spring loaded latch, 1 x porcelain toilet pan, plastic toilet seat and flap, and 1 x Econo Cistern. Assembled on site	No	1	8,519.64	8,519.64
116	One piece, precast concrete toilet structure with water pipe above the cistern. Including Stainless Steel door with lockable spring loaded latch, 1 x porcelain toilet pan, plastic toilet seat and flap, and 1 x Econo Cistern. Including delivery to site using a Crane Truck	No	1	7,787.90	7,787.90
<u>REPLACE DAMAGED SANITARY FITTINGS</u>					
<u>Carefully take out and remove damaged sanitary fitting, replace with new including effecting all existing brackets, couplings, connections and re-fixing existing taps, valves, etc. making good existing finishers as necessary and leave in good working order.</u>					
<u>Precast Concrete Wash Troughs</u>					
117	700mm x 530mm x 340mm deep Including Concrete Pedestal height: 870mm	No	1	915.33	915.33
118	1050mm x 650mm x 340mm deep Including Concrete Pedestals height: 870mm.	No	1	1,387.90	1,387.90
<u>Econo pans - Low cost "Housing" Flats, Old Age Homes, Hostels, RDP etc</u>					
119	Standard Mode - S Trap WC Pan	No	1	775.49	775.49

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
120	Standard Mode - P Trap WC Pan	No	1	775.52	775.52
121	Replace WC Light duty double flap plastic seat	No	1	109.36	109.36
122	Replace WC Heavy duty double flap plastic seat	No	1	342.93	342.93
	<u>Econo / Plastic cisterns</u>				
123	9 litre Elf Toilet Plastic cistern complete with lid, fitments, flushing mechanism and flush pipe.	No	1	417.58	417.58
124	9 litre Elf Superior Plastic cistern complete with lid, fitments, flushing mechanism and flush pipe. With dual flush button	No	1	536.88	536.88
	<u>Shower bases and doors</u>				
125	Salina Bath/Shower Screen - F7203 or equivalent 900mm (L) x 1450 (H)	No	1	2,266.78	2,266.78
126	Salina Bath/Shower Screen - F7203 or equivalent 1300mm (L) x 1300 (H)	No	1	3,128.42	3,128.42
127	ST Marco G801 or equivalent Shower enclosure 885mm X 885mm (L) x 1850mm (H) (Base measured elsewhere)	No	1	2,850.04	2,850.04
128	Semi Frameless Square Shower 6011 or equivalent Shower enclosure 885mm X 885mm (L) x 1850mm (H) (Base measured elsewhere)	No	1	4,573.32	4,573.32
129	Pentagonal Frameless Shower 7010 or equivalent 975mm x 975mm (L) X 1850mm (H) (Base measured elsewhere)	No	1	7,502.89	7,502.89
130	Ceramic Shower Tray 1000 (L) x 1000 (W)	No	1	2,850.04	2,850.04
131	PVC Shower Tray 1000 (L) x 1000 (W)	No	1	1,729.92	1,729.92
	<u>Stainless Steel</u>		1		0.00
132	Wash hand basin approximately 450 x 350mm wide	No	1	695.94	695.94
133	Sink and drainer 900 x 530mm wide with one bowl	No	1	1,431.65	1,431.65
134	Sink and drainer 1200 x 530mm wide with one bowl	No	1	1,710.03	1,710.03
135	Sink and drainer 1350 x 530mm wide with one bowl	No	1	2,052.03	2,052.03
136	Sink and drainer 1575 x 530mm wide with two bowls	No	1	2,462.43	2,462.43

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
137	Sink and drainer 1800 x 530mm wide with two bowls	No	1	2,954.92	2,954.92
138	525 x 530mm Laundry tub with one bowl	No	1	1,710.03	1,710.03
139	1050 x 530mm Laundry tub with two bowls	No	1	2,052.03	2,052.03
140	Combination curved back trough urinal 1350mm high with standard integral automatic flushing tray, drip cock and hinged domical grating not exceeding 1200mm long.	No	1	3,860.15	3,860.15
141	Combination curved back trough urinal 1350mm high with standard integral automatic flushing tray, drip cock and hinged domical grating exceeding 1200mm and not exceeding 1800mm long.	No	1	3,860.15	3,860.15
	<u>Vitreous China Sanitaryware - "Vaal" or equally approved</u>				
142	450 x 300mm (approximately) Cloakroom basin	No	1	636.29	636.29
143	Universal basin pedestal	No	1	485.17	485.17
144	550 x 400mm (approximately) wash hand basin	No	1	737.04	737.04
145	600 x 400mm (approximately) Oval / Round vanity basin	No	1	872.22	872.22
146	Low level WC open rim washdown pan	No	1	2,579.62	2,579.62
147	Semi-close coupled WC open rim washdown pan	No	1	2,579.62	2,579.62
148	Close coupled WC open rim washdown pan	No	1	2,579.62	2,579.62
149	Wall hung WC open rim pan (flushing valve elsewhere)	No	1	1,503.23	1,503.23
150	9 litre cistern complete with lid and fitments (flush pipe elsewhere)	No	1	764.11	764.11
151	9 litre cistern complete with lid, top dual push button and fitments (flush pipe elsewhere)	No	1	802.65	802.65
152	9 litre cistern complete with lid, dual flush handle and fitments (flush pipe elsewhere)	No	1	764.11	764.11
153	Wall hung bowl urinal, overall size 420 x 320 x 280mm (approximately) with 38mm c.p. Domical grating and top inlet spreader (flushing valve elsewhere)	No	1	3,860.15	3,860.15

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
154	Wall hung bowl urinal, overall size 600 x 390 x 390mm (approximately) with 38mm c.p. Domical grating and top inlet spreader (flushing valve elsewhere)	No	1	3,860.15	3,860.15
155	510 x 400mm "Sola Medical 510" white hospital basin Code 706200 including 32mm diameter chromium plated standing overflow tube Code 8630Z0, bolted to wall	No	1	1,113.51	1,113.51
156	510 x 405mm "Hibiscus 844820" white wash hand basin with two tap holes including integrated overflow and chainstay hole, bolted to wall	No	1	996.52	996.52
157	595 x 455mm "Cameo" white drop-in vanity basin Code 0006 with two tap holes including integrated overflow and chainstay hole, and silicone sealant all round	No	1	1,193.04	1,193.04
158	Low-level white closet for paraplegics comprising "Protea(7502)" pan with "Masterbilt" double flap plastic seat and 9litre Code710631 cistern with purpose made chromed side flush handle	No	1	11,347.15	11,347.15
159	Daisy white vitreous china WC semi-close coupled pan (code 774717) with matching 9litre cistern (code 710034) and white double flap plastic seat	No	1	2,539.86	2,539.86
160	Daisy white vitreous china "Junior" 1040 WC outlet washdown pan (code 751300) and matching 6litre cistern (code 712034) complete with lid and fitments, and junior seat	No	1	2,321.12	2,321.12
161	Lavatera top inlet bowl wall urinal with spreader (Flushing valve elsewhere)	No	1	3,821.33	3,821.33
162	Built in Bath with Handles 1700 x 700 including overflow pipe (Brickwork and tiling measured elsewhere)	No	1	1,988.40	1,988.40
163	Built in Bath with Handles 1800 x 750 including overflow pipe (Brickwork and tiling measured elsewhere)	No	1	4,730.37	4,730.37
	<u>Sundries</u>				
164	Replace sink or wash hand basin stainless steel bracket including re-fixing sink or basin, connection, etc.	No	8	308.86	2,470.88
165	Re-fix existing wash hand basin to wall	No	8	145.82	1,166.56
166	Replace wash hand basin semi concealed cast iron bracket including re-fixing basin, connections, etc.	No	8	87.49	699.92

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
167	Re-fix existing high or low level wc cistern to wall	No	8	145.82	1,166.56
168	Replace WC double flap wooden seat	No	8	364.54	2,916.32
169	Replace PVC flush pipe rubber pan connector	No	8	87.49	699.92
170	Replace low level cistern PVC flush pipe, rubber pan connector and seals	No	8	145.82	1,166.56
171	Replace high level cistern PVC flush pipe, rubber pan connector and seals	No	8	112.69	901.52
172	Replace semi-close coupled cistern PVC flush pipe bend, rubber pan connector and seals	No	8	389.72	3,117.76
173	Replace high level flush chain	No	8	127.26	1,018.08
174	Replace matching cistern lid	No	8	369.18	2,953.44
175	Replace cistern float arm including ball and set water level	No	8	145.82	1,166.56
176	Replace cistern bottom inlet pedestal type float valve and ball, connect supply and set water level	No	8	278.38	2,227.04
177	Replace flushing valve mechanism complete with rubber washers, etc.	No	8	337.06	2,696.48
178	Replace Syphonic flushing valve unit complete with rubber washers, etc.	No	8	338.03	2,704.24
179	Attend to and service / fix faulty cistern including replacing all washers, seals, adjusting flushing mechanism, etc. and leave in good working order.	No	8	231.99	1,855.92
180	Replace cistern float valve and ball, connect supply and adjust water level	No	8	190.88	1,527.04
	<u>REPLACE DAMAGED WASTE UNIONS, ETC.</u>				
	<u>Carefully take out and remove damaged item, replace with new including backnut, plug and chain; and making good existing finishers as necessary.</u>				
181	32mm Chromium plated bath overflow union	No	8	127.26	1,018.08
182	32mm Chromium plated basin waste union	No	8	127.26	1,018.08

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
183	40mm chromium plated shower waste and grating	No	8	235.96	1,887.68
184	40mm Chromium plated bath or sink waste union	No	8	127.26	1,018.08
	<u>Sundries</u>				
185	Replace CP shower grating	No	8	44.27	354.16
186	Replace plug and chain	No	8	34.62	276.96
187	Replace CP anti-theft plug and spindle	No	8	294.11	2,352.88
188	Attend to, fix leaking waste union and tighten backnut	No	8	32.48	259.84
	<u>REPLACE DAMAGED TRAPS, ETC.</u>				
	<u>Carefully take out and remove damaged item, replace with new including washers, flanges, capnuts, pipe clips, etc. and making good existing finishers as necessary.</u>				
	<u>TRAPS</u>				
	<u>uPVC</u>				
189	32mm "P" or "S" trap	No	5	145.82	729.10
190	32mm Bottle trap	No	5	311.52	1,557.60
191	40mm "P" or "S" trap	No	5	167.02	835.10
192	40mm Bottle trap	No	5	348.63	1,743.15
	<u>Flexi-Rubber</u>				
193	40mm "P" or "S" trap	No	5	112.01	560.05
194	40 x 300mm sink combination for double bowl "P" trap	No	5	139.19	695.95
	<u>Brass</u>				
195	40mm Shower or bath trap	No	5	365.28	1,826.40
	<u>Chromium plated - "Cobra Watertech" or equally approved</u>				
196	32mm "345/40CP" bottle traps	No	5	869.60	4,348.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
197	32mm CP extension piece with sliding wall flange	No	5	63.63	318.15
	<u>Sundries</u>				
198	Attend to and repair leaking joint to exposed trap	No	5	32.48	162.40
199	Attend to and repair leaking joint to concealed or flush trap	No	5	32.48	162.40
	<u>REPLACE DAMAGED TAPS, VALVES, ETC.</u>				
	<u>Carefully take out and remove damaged item, replace with new including handle styles to match existing, washers, flanges, capnuts, couplers, etc. and making good existing finishers as necessary.</u>				
	<u>Brass</u>				
200	15mm Bibtap "Code 100 - 15"	No	5	417.83	2,089.15
201	15mm Hose Bibtap "Code 108 - 15"	No	5	434.87	2,174.35
202	15mm Hose Bibtap "Code 209/1 - 13 x 3/4"	No	5	272.62	1,363.10
203	20mm Hose Bibtap "Code 108 - 20"	No	5	585.40	2,927.00
204	20mm Hose bibtap with lock shield and loose key "Code 108LK-20" Removable key	No	5	858.21	4,291.05
205	15mm Hose bibtap with lock shield and loose key "Code 108LK-15" Removable key	No	5	664.01	3,320.05
206	20mm stoptap "Code 121-20"	No	5	446.04	2,230.20
207	15mm stoptap "Code 121-15"	No	5	336.14	1,680.70
208	20mm stoptap with lockshield and loose key "Code 121LK-20"	No	5	697.75	3,488.75
209	15mm stoptap with lockshield and loose key "Code 121LK-15"	No	5	561.42	2,807.10
	<u>Cobra or equivalent Red Steel - Heavy Duty Gate valve</u>				
210	25mm Fullway gate valve "Code 1001/125-25"	No	5	535.87	2,679.35
211	32mm Fullway gate valve "Code 1001/125-32"	No	5	807.49	4,037.45
212	40mm Fullway gate valve "Code 1001/125-40"	No	5	975.98	4,879.90

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
213	50mm Fullway gate valve "Code 1001/125-50"	No	5	1,372.10	6,860.50
214	100mm Fullway gate valve "Code 1001/125-100"	No	5	3,420.73	17,103.65
215	15mm Fullway heavy duty gate valve "Code 1001/125-15"	No	5	398.06	1,990.30
216	20mm Fullway heavy duty gate valve "Code 1001/125-20"	No	5	455.60	2,278.00
	<u>Cobra or equivalent Brass Check Valve</u>				
217	15mm Brass Check valve "Code 1022-15"	No	5	200.27	1,001.35
218	20mm Brass Check valve "Code 1022-20"	No	5	203.42	1,017.10
219	25mm Brass Check valve "Code 1022-25"	No	5	286.51	1,432.55
220	32mm Brass Check valve "Code 1022-32"	No	5	403.08	2,015.40
221	40mm Brass Check valve "Code 1022-40"	No	5	529.78	2,648.90
	<u>Cobra or equivalent - Brass Spring Check Valve</u>				
222	15mm Brass Spring Check valve "Code 1025-15"	No	5	250.34	1,251.70
223	20mm Brass Spring Check valve "Code 1025-20"	No	5	281.53	1,407.65
224	25mm Brass Spring Check valve "Code 1025-25"	No	5	492.48	2,462.40
225	40mm Brass Spring Check valve "Code 1025-40"	No	5	875.95	4,379.75
226	50mm Brass Spring Check valve "Code 1025-50"	No	5	1,413.66	7,068.30
	<u>Cobra or equivalent - Ball Valves</u>				
227	15mm Ball valve "Code 1030-15"	No	5	152.96	764.80
228	20mm Ball valve "Code 1080-20"	No	5	449.05	2,245.25
	<u>Chromium plated - Heavy pattern SABS 226 - 1987 - Class 1</u>				
	<u>Cobra Watertech or equally approved</u>				
229	Stella 15mm Raised nose pillartap - 3314SB including flexi pipe	No	5	493.89	2,469.45
230	Stella 20mm Raised nose pillartap - 3314ST including flexi pipe	No	5	531.86	2,659.30
231	Stella 15mm Bibtap star - 108-15	No	5	365.36	1,826.80

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
232	Stella 20mm Bibtap star - 108-20	No	5	589.32	2,946.60
233	Stella Basin mixer pillartap with aerator - 3392SB including flexi pipe	No	5	2,072.35	10,361.75
234	Stella Sink mixer pillartap with aerator - 3396SB, including flexi pipe	No	5	1,684.04	8,420.20
235	Stella Sink mixer Bibtap with aerator - 3366/041/10SB	No	5	1,477.09	7,385.45
236	Stella Bath mixer Bibtap with aerator - 3351SB-15-HQ with shower hose	No	5	2,515.73	12,578.65
237	Stella Shower Set with shower head P-63-2SB and two 15mm undertile stop taps - 3328SB026/065	No	5	1,607.83	8,039.15
238	15mm undertile stoptap star - 128-15	No	5	584.43	2,922.15
239	20mm undertile stoptap star - 128-20	No	5	953.44	4,767.20
240	21mm Medical bibtap - 500-21B Pillar Tap(Elbow action) Flexi pipes	No	5	2,147.38	10,736.90
241	21mm Medical bibtap - 500-21B BIB Tap(Elbow action)	No	5	2,147.38	10,736.90
242	21mm Medical pillartap - 503-21B / 503-21R Basin (Elbow action) with flexi pipe	No	5	1,690.99	8,454.95
243	21mm Medical pillartap - 505-21B / 505-21R Basin with Aerator (Elbow action) with flexi pipe	No	5	1,690.41	8,452.05
244	21mm Medical wall bib mixer - 511-21 (Elbow action) with flexi pipe	No	5	5,741.71	28,708.55
245	21mm Medical pillar mixer - 515-21 Pillar for Sink or Basin (Elbow action) with flexi pipe	No	5	4,886.42	24,432.10
246	21mm Medical wall mounted - 515/055-21 BIB for sink or basin (Elbow action)	No	5	4,886.42	24,432.10
247	21mm Medical wall type mixer with hand shower - 518-21 BIB for bath (Elbow action)	No	5	7,515.36	37,576.80
248	15mm "Code KM2.100" metering pillartap	No	5	2,767.48	13,837.40
249	15mm "Code KM2.302" demand stoptap	No	5	1,311.82	6,559.10

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
250	Code "SP 3" Ball throwing stand	No	5	1,372.85	6,864.25
251	15mm "Code KM2.301" metering stoptap	No	5	2,219.43	11,097.15
252	15mm "Code KM6.000" metering urinal valve	No	5	2,016.51	10,082.55
253	15mm "Code KM1.00" metering valve for basins	No	5	2,440.34	12,201.70
254	15mm Extension piece 75mm long	No	5	52.36	261.80
255	20mm Extension piece 75mm long	No	5	63.63	318.15
256	15mm Extension piece with sliding wall flange	No	5	52.36	261.80
257	20mm Extension piece with sliding wall flange	No	5	63.63	318.15
258	15mm angle regulating valve	No	5	737.04	3,685.20
259	15mm angle regulating valve with 350mm long tube and capnut	No	5	802.00	4,010.00
260	Vandalproof Shower head "Code KP2,6" CP15mm	No	5	1,496.25	7,481.25
261	Typhoon Shower Head "Code KP2,51" C/P 15mm including shower arm 300mm x 90 degree projection with wall flange and 85mm	No	5	915.72	4,578.60
262	Prestex Shower Head "Code P-065" C/P including shower arm 300mm x 90 degree projection with wall flange and 85mm	No	5	441.82	2,209.10
263	Shower CP Head "Code P-070CP" 150mm dia with Overhead shower arm 300mm x 90 degree projection with wall flange and 85mm	No	5	862.31	4,311.55
264	Shower arm with wall flange 15mm C/P "Code P-026" 68mm throw	No	5	238.61	1,193.05
265	Shower arm with wall flange 15mm C/P "Code P-027" 158mm throw	No	5	170.20	851.00
266	Tubular Shower arm with wall flange 15mm C/P "Code P-023TU-250" 250mm throw	No	5	484.27	2,421.35
267	Tubular Shower arm with wall flange 15mm C/P "Code P-023TU-400" 400mm throw	No	5	572.36	2,861.80

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
268	20mm Plain bath spout with round wall flange	No	5	737.04	3,685.20
269	20mm Plain square pattern bath spout with round wall flange	No	5	737.04	3,685.20
270	20mm Pillar type plain bath spout with 230mm throw	No	5	775.77	3,878.85
271	20mm "Flushmaster Junior" (FJ2.000) exposed type toilet flush valve CP with integral ball-o-stop valve and wallplate	No	5	3,311.75	16,558.74
272	20mm "Toilet Flushvalve" (FJ2.100) exposed type toilet flush valve CP, back entry installations, pan connector, wall flange, with integral vacuum breaker	No	5	3,748.00	18,740.00
273	20mm "Flushmaster Junior" (FJ4.001) concealed type toilet flush valve BC with integral ball-o-stop valve and captive linkage	No	5	2,054.33	10,271.65
274	20mm "Flushmaster Junior" (FJ6.000) exposed type urinal flush valve CP with integral ball-o-stop valve and wallplate	No	5	2,206.04	11,030.20
275	32mm "Standard Flushmaster" (FM1.000) exposed type toilet flush valve CP with integral vacuum breaker, non-return valve, ball-o-stop, wallplate and activation lever	No	5	5,348.22	26,741.10
276	32mm "Standard Flushmaster" (FM1.100) exposed type toilet flush valve CP with integral vacuum breaker, non-return valve, ball-o-stop, wallplate, activation lever, flush pipe and rubber pan connector	No	5	5,529.62	27,648.10
277	32mm "Standard Flushmaster" (FM2.000) exposed type toilet back entry flush valve CP with integral vacuum breaker, non-return valve, ball-o-stop and wallplate	No	5	3,582.61	17,913.06
278	Push button assembly CP with pushrod for concealed flush valves	No	5	263.21	1,316.05
279	Straight bowl type urinal flush pipe and spreader	No	5	605.49	3,027.45
280	Offset bowl type urinal flush pipe and spreader	No	5	605.49	3,027.45
281	22mm CP Straight urinal flush pipe with rubber pipe connector	No	5	309.73	1,548.65
282	22mm CP Bent urinal flush pipe with rubber pipe connector	No	5	325.49	1,627.45
283	25mm CP Straight toilet flush pipe with rubber pipe connector and seat buffer	No	5	354.31	1,771.55

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
284	25mm CP Bent toilet flush pipe with rubber pipe connector and seat buffer	No	5	394.27	1,971.35
285	38mm CP Straight toilet flush pipe with rubber pipe connector and seat buffer	No	5	457.01	2,285.05
286	38mm CP Bent toilet flush pipe with rubber pipe connector and seat buffer	No	5	515.00	2,575.00
	<u>Sundries</u>				
287	Replace tap or stoptap handle to suit base unit not exceeding 20mm including capnut or screw fixing and hot or cold indicator cap where required	No	5	324.17	1,620.85
288	Replace gate valve handwheel not exceeding 100mm diameter including capnut or screw fixing	No	5	2,196.18	10,980.90
289	Replace 15 x 350mm long flexi tube CP	No	5	327.91	1,639.55
290	Replace 15mm standard Headpart RB	No	5	350.00	1,750.00
291	Replace 15mm standard Headpart RB and spindle cover CP	No	5	582.00	2,910.00
292	Replace 20mm standard Headpart RB	No	5	415.00	2,075.00
293	Replace 20mm standard Headpart RB and spindle cover CP	No	5	415.00	2,075.00
294	Replace 15mm leaking tap or stoptap washer	No	5	355.00	1,775.00
295	Replace 15mm leaking tap or stoptap washer including spindle gland packing	No	5	391.91	1,959.55
296	Replace 20mm leaking tap or stoptap washer	No	5	350.00	1,750.00
297	Replace 20mm leaking tap or stoptap washer including spindle gland packing	No	5	350.00	1,750.00
298	Repair leaking joint to urinal flushpipe or spreader	No	5	299.43	1,497.15
299	Replace leaking or damaged rubber flushpipe connector	No	5	145.82	729.10
300	Replace leaking or damaged compression rubber flushpipe connector	No	5	145.82	729.10

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
301	Service and clean out "Flushmaster Junior Flushvalve" unit using standard washer kit including adjusting water flow and leave in good working order (replacement parts elsewhere)	No	5	247.21	1,236.05
302	Service and clean out "Standard Flushmaster Flushvalve" unit using standard washer kit and handle seal including adjusting water flow and leave in good working order (replacement parts elsewhere)	No	5	298.27	1,491.35
	<u>Replace faulty or damaged "Flushmaster Junior Flushvalve" parts</u>				
303	Piston assembly	No	5	136.58	682.90
304	Pushbutton assembly	No	5	263.47	1,317.35
305	Flushvalve cover	No	5	144.50	722.50
306	Wall flange	No	5	114.45	572.25
307	Captive linkage	No	5	430.96	2,154.80
	<u>Replace faulty or damaged "Standard Flushmaster Flushvalve" parts</u>				
308	Piston assembly	No	5	136.58	682.90
309	Plunger assembly	No	5	263.47	1,317.35
310	Control stop assembly	No	5	263.47	1,317.35
311	Top cover assembly	No	5	144.50	722.50
312	Headpart	No	5	144.50	722.50
313	Handle and nut assembly	No	5	144.50	722.50
314	Extended activation lever for disable installation conversion, 224mm in length 10mm diameter rod	No	5	430.96	2,154.80
	<u>REPLACE DAMAGED SOIL, SEWER, WASTE, VENT PIPE AND FITTINGS</u>				
	<u>PVC-U SOIL, SEWERAGE</u>				
	<u>Supply and install PVC-U class 51-100kPa Normal duty pipes, alteration, bedding and backfill measured elsewhere</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
315	110mm Pipes	m	6	96.22	577.32
316	160mm Pipes	m	6	134.16	804.96
317	200mm Pipes	m	6	206.63	1,239.78
	<u>Supply and install PVC-U class 34 - 300kPa Normal duty pipes, alteration, bedding and backfill measured elsewhere</u>				
318	110mm Pipes	m	12	119.19	1,430.28
319	160mm Pipes	m	12	203.80	2,445.60
320	200mm Pipes	m	12	320.64	3,847.68
	<u>Extra over uPVC pipes for fittings</u>				
321	110mm Bend	No	4	120.77	483.08
322	110mm Access Bend	No	4	197.63	790.52
323	110mm Rodding eye	No	4	255.34	1,021.36
324	110 x 45deg mm Rodding eye lid	No	4	45.58	182.32
325	160mm Rodding eye inspection lid	No	4	82.34	329.36
326	110 x 45deg RIB junction	No	4	148.45	593.80
327	110 x 90deg RIB junction	No	4	225.84	903.36
328	160 x 110 x 45deg RIB S/R/Junction	No	4	290.76	1,163.04
329	110mm dia single socket	No	4	72.40	289.60
330	160mm dia single socket	No	4	91.04	364.16
331	110mm dia end cap	No	4	72.40	289.60
332	160mm dia end cap	No	4	165.60	662.40
	<u>WASTE AND VENT PIPES STACKING - Freeflo</u>				
	<u>Carefully take out and remove damaged section to uPVC waste pipe and /or fittings, replace with new including holderbats, pipe clips, etc. as necessary and leave in good working order.</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
333	40mm pipe	m	9	57.89	521.01
334	50mm pipe	m	9	63.67	573.03
335	75mm pipe	m	9	88.13	793.17
336	110mm pipe	m	9	149.42	1,344.78
337	160mm pipe	m	9	247.30	2,225.70
	<u>uPVC waste fittings</u>				
338	40mm Access lid	No	2	23.42	46.84
339	40mm Single socket	No	2	52.44	104.88
340	40mm Bend	No	2	52.44	104.88
341	40mm Access bend	No	2	54.98	109.96
342	40mm Junction	No	2	52.44	104.88
343	40mm Access junction	No	2	54.98	109.96
344	40mm Adaptor	No	2	52.44	104.88
345	40mm Adaptor	No	2	52.44	104.88
346	40mm Reducing socket	No	2	48.31	96.62
347	50mm Access lid	No	2	25.77	51.54
348	50mm Single socket	No	2	57.70	115.40
349	50mm Bend	No	2	57.70	115.40
350	50mm Access bend	No	2	60.48	120.96
351	50mm Junction	No	2	57.70	115.40
352	50mm Access junction	No	2	60.48	120.96
353	50mm Adaptor	No	2	57.70	115.40
354	50mm Reducing socket	No	2	57.70	115.40

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
355	50mm Air vent cowl	No	2	53.32	106.64
356	50mm Two-Way vent valve	No	2	57.70	115.40
357	50mm Two-Way vent valve	No	2	60.48	120.96
358	75mm Single socket	No	2	28.32	56.64
359	75mm Single socket	No	2	63.46	126.92
360	75mm Bend	No	2	63.46	126.92
361	75mm Access bend	No	2	66.52	133.04
362	75mm Junction	No	2	63.46	126.92
363	75mm Access junction	No	2	66.52	133.04
364	75mm Reducing junction	No	2	66.52	133.04
365	75mm Access reducing junction	No	2	66.52	133.04
366	75mm Air vent cowl	No	2	58.64	117.28
367	75mm One-Way vent valve	No	2	63.46	126.92
368	75mm Two-Way vent valve	No	2	66.52	133.04
369	110mm Access lid	No	2	31.16	62.32
370	110mm Single socket	No	2	69.81	139.62
371	110mm Double socket	No	2	72.98	145.96
372	110mm Access bend	No	2	69.77	139.54
373	110mm Access bend with vent horn	No	2	73.18	146.36
374	110mm Single junction	No	2	76.49	152.98
375	110mm Access single junction	No	2	69.81	139.62
376	110mm Reducing junction	No	2	73.18	146.36
377	110mm Access reducing junction	No	2	73.18	146.36
378	110mm Double junction	No	2	73.18	146.36

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
379	110mm Access double junction	No	2	73.18	146.36
380	110mm Double reducing junction	No	2	76.49	152.98
381	110mm Access double reducing junction	No	2	76.49	152.98
382	110mm Pan collar	No	2	76.49	152.98
383	110mm Bent pan collar	No	2	69.81	139.62
384	110mm Access bent pan collar	No	2	73.18	146.36
385	110 x 50mm Eccentric reducer	No	2	76.49	152.98
386	110mm Air vent cowl	No	2	175.20	350.40
387	110mm One-Way vent valve	No	2	64.50	129.00
388	110mm Two-Way vent valve	No	2	73.18	146.36
389	50mm Aluminium Holderbat	No	2	73.18	146.36
390	75mm Aluminium Holderbat	No	2	28.42	56.84
391	110mm Aluminium Holderbat	No	2	47.87	95.74
	<u>Carefully take out and remove damaged section to Plain Ended Cast Iron pipe and / or fittings, replace with new including SSN couplings, holderbats, pipe clips, etc. as necessary and leave in good working order.</u>				
392	50mm pipe	m	2	52.24	104.48
393	75mm pipe	m	2	358.78	717.56
394	100mm pipe	m	2	394.67	789.34
	<u>Cast Iron fittings</u>				
395	50mm End cap	No	2	236.19	472.38
396	50mm Bend	No	2	371.24	742.48
397	50mm Junction	No	2	380.54	761.08
398	75mm End cap	No	2	259.82	519.64

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
399	75mm Access lid	No	2	259.82	519.64
400	75 x 50mm Eccentric reducer	No	2	409.79	819.58
401	75mm Bend	No	2	390.05	780.10
402	75mm Junction	No	2	399.80	799.60
403	75mm Access Junction	No	2	409.79	819.58
404	75mm Access reducing junction	No	2	420.05	840.10
405	75mm Urinal 'P' trap	No	2	420.05	840.10
406	100mm End cap	No	2	367.94	735.88
407	100mm Access lid	No	2	367.94	735.88
408	100 x 50mm Eccentric reducer	No	2	756.54	1,513.08
409	100 x 75mm Eccentric reducer	No	2	756.54	1,513.08
410	100mm Bend	No	2	738.09	1,476.18
411	100mm Access bend	No	2	756.54	1,513.08
412	100mm Junction	No	2	775.46	1,550.92
413	100mm Access Junction	No	2	794.84	1,589.68
414	100mm Double junction	No	2	814.72	1,629.44
415	100mm Access double junction	No	2	835.09	1,670.18
416	100mm Reducing junction	No	2	814.72	1,629.44
417	100mm Access reducing junction	No	2	835.09	1,670.18
418	100mm Combined junction / bend	No	2	835.09	1,670.18
419	100mm Double combined junction / bend	No	2	855.97	1,711.94
420	100mm Iron to earthenware connector	No	2	756.53	1,513.06
421	100mm ABC cleaning eye and cover	No	2	835.09	1,670.18

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Carefully take out and remove damaged section to medium duty Spigot and Socket Cast Iron pipe and / or fittings, replace with new including holderbats, pipe clips, etc. as necessary and leave in good working order.</u>				
422	100mm pipe	m	2	394.67	789.34
	<u>Medium duty Spigot and Socket Cast Iron fittings</u>				
423	100mm Access lid	No	2	367.94	735.88
424	100mm Inspection pipe	No	2	794.84	1,589.68
425	100mm Socket	No	2	738.09	1,476.18
426	100 x 50mm Taper pipe	No	2	404.53	809.06
427	100 x 75mm Taper pipe	No	2	414.65	829.30
428	100mm Junction	No	2	775.46	1,550.92
429	100mm Access junction	No	2	794.84	1,589.68
430	100mm Reducing junction	No	2	814.72	1,629.44
431	100mm Access reducing junction	No	2	835.09	1,670.18
	<u>Carefully take out and remove damaged section to Galvanised Steel pipe and/or fittings, replace with new including holderbats, pipe clips, etc. as necessary and leave in good working order.</u>				
432	32mm pipe	m	10	272.24	2,722.40
433	40mm pipe	m	10	299.47	2,994.70
434	50mm pipe	m	10	329.41	3,294.10
435	80mm pipe	m	10	368.94	3,689.40
436	100mm pipe	m	10	405.84	4,058.40
437	80mm Elbow	No	2	94.00	188.00
438	80mm Bend	No	2	94.00	188.00
439	100mm Elbow	No	2	112.79	225.58

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
440	100mm Bend	No	2	112.79	225.58
	<u>Carefully break out from concrete and remove damaged Full-bore Cast Iron Outlet, replace with new including connections, making good all existing finishers including waterproofing and paint to match existing; and leave in good working order.</u>				
441	80mm vertical outlet	No	2	359.81	719.62
442	80mm 45 or 90 degree side outlet	No	2	377.79	755.58
443	80mm two-way outlet	No	2	415.58	831.16
444	100mm vertical outlet	No	2	457.14	914.28
445	100mm side outlet	No	2	457.14	914.28
446	100mm 45 or 90 degree side outlet	No	2	502.85	1,005.70
447	100mm two-way outlet	No	2	527.99	1,055.98
	<u>Brass fittings</u>				
448	32mm Access lid	No	2	157.75	315.50
449	32mm Bend	No	2	288.31	576.62
450	32mm Access bend	No	2	295.52	591.04
451	32mm Junction	No	2	295.52	591.04
452	32mm Access junction	No	2	295.88	591.76
453	40mm Access lid	No	2	173.53	347.06
454	40mm Bend	No	2	317.14	634.28
455	40mm Access bend	No	2	325.07	650.14
456	40mm Junction	No	2	325.07	650.14
457	40mm Access junction	No	2	325.46	650.92
458	50mm Access lid	No	2	190.88	381.76
459	50mm Bend	No	2	348.85	697.70

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
460	50mm Access bend	No	2	357.56	715.12
461	50mm Junction	No	2	348.85	697.70
462	50mm Access junction	No	2	357.56	715.12
	<u>Sundries</u>				
463	Seal leaking uPVC or cast iron WC pan connector joint	No	2	72.91	145.82
464	Seal leaking uPVC waste or vent pipe joint not exceeding 75mm diameter	No	2	72.91	145.82
465	Seal leaking uPVC soil or vent pipe joint not exceeding 110mm diameter	No	2	72.91	145.82
466	Seal leaking plain ended cast iron waste or vent pipe joint not exceeding 75mm diameter	No	2	72.91	145.82
467	Seal leaking plain ended cast iron soil or vent pipe joint not exceeding 100mm diameter	No	2	72.91	145.82
468	Seal leaking spigot and socket cast iron waste or vent pipe joint not exceeding 75mm diameter	No	2	72.91	145.82
469	Seal leaking spigot and socket cast iron waste or vent pipe joint not exceeding 100mm diameter	No	2	72.91	145.82
	<u>REPLACE DAMAGED UNDERGROUND WATER PIPE AND FITTINGS</u>				
	<u>Locate, isolate affected area, excavate for and replace damage to High Density Polyethylene (HDPE) water supply line and / or fittings in landscaped areas not exceeding 1m deep including backfilling, compacting, etc. and leave in good working order.</u>				
	<u>Class 12 not exceeding 1,5m deep</u>				
470	20mm pipe	m	8	119.95	959.60
471	25mm pipe	m	8	121.15	969.20
472	32mm pipe	m	8	122.47	979.76
473	40mm pipe	m	8	123.94	991.52

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
474	50mm pipe	m	8	134.61	1,076.88
475	65mm pipe	m	8	144.68	1,157.44
476	75mm pipe	m	8	144.68	1,157.44
477	90mm pipe	m	8	173.02	1,384.16
478	110mm pipe	m	8	206.11	1,648.88
	<u>Plasson compression fittings</u>				
479	20mm fittings	No	3	46.38	139.14
480	25mm fittings	No	3	48.99	146.97
481	32mm Elbow	No	3	51.01	153.03
482	40mm Elbow	No	3	56.12	168.36
483	50mm Elbow	No	3	61.72	185.16
484	65mm Elbow	No	3	67.89	203.67
485	32mm Tee	No	3	51.01	153.03
486	40mm Tee	No	3	56.12	168.36
487	50mm Tee	No	3	61.72	185.16
488	65mm Tee	No	3	67.89	203.67
489	32mm Coupler / Adaptor	No	3	51.01	153.03
490	40mm Coupler / Adaptor	No	3	56.12	168.36
491	50mm Coupler / Adaptor	No	3	61.72	185.16
492	65mm Coupler / Adaptor	No	3	67.89	203.67
493	20mm 1/2" Plasson Saddle 2- Bolt	No	3	69.02	207.06
494	20mm 3/4" Plasson Saddle 2- Bolt	No	3	69.02	207.06
495	20mm 1" Plasson Saddle 2- Bolt	No	3	69.02	207.06
496	25mm 1/2" Plasson Saddle 2- Bolt	No	3	71.47	214.41

Generic Bill Of Quantities
Construction And Refurbishment Of Buildings And Facilities
Generic Bill Of Quantities (Provisional)

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
497	25mm 3/4" Plasson Saddle 2- Bolt	No	3	71.47	214.41
498	25mm 1" Plasson Saddle 2- Bolt	No	3	71.47	214.41
499	32mm 1/2" Plasson Saddle 2- Bolt	No	3	76.51	229.53
500	32mm 3/4" Plasson Saddle 2- Bolt	No	3	76.51	229.53
501	32mm 1" Plasson Saddle 2- Bolt	No	3	76.51	229.53
502	40mm 1/2" Plasson Saddle 2- Bolt	No	3	84.03	252.09
503	40mm 3/4" Plasson Saddle 2- Bolt	No	3	84.03	252.09
504	40mm 1" Plasson Saddle 2- Bolt	No	3	84.03	252.09
505	50mm 1/2" Plasson Saddle 2- Bolt	No	3	92.24	276.72
506	50mm 3/4" Plasson Saddle 2- Bolt	No	3	92.24	276.72
507	50mm 1" Plasson Saddle 2- Bolt	No	3	92.24	276.72
508	63mm 1/2" Plasson Saddle 2- Bolt	No	3	155.23	465.69
509	63mm 3/4" Plasson Saddle 4 - Bolt	No	3	155.23	465.69
510	63mm 1" Plasson Saddle 4 - Bolt	No	3	155.23	465.69
511	63mm 1.1/4" Plasson Saddle 4 - Bolt	No	3	155.23	465.69
512	75mm 1/2" Plasson Saddle 4 - Bolt	No	3	187.04	561.12
513	75mm 3/4" Plasson Saddle 4 - Bolt	No	3	187.04	561.12
514	75mm 1" Plasson Saddle 4 - Bolt	No	3	187.04	561.12
515	75mm 1.1/4" Plasson Saddle 4 - Bolt	No	3	187.04	561.12
516	90mm 1/2" Plasson Saddle 4 - Bolt	No	3	218.30	654.90
517	90mm 3/4" Plasson Saddle 4 - Bolt	No	3	218.30	654.90
518	90mm 1" Plasson Saddle 4 - Bolt	No	3	218.30	654.90
519	90mm 1.1/4" Plasson Saddle 4 - Bolt	No	3	218.30	654.90

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
520	110mm 1/2" Plasson Saddle 4 - Bolt	No	3	265.78	797.34
521	110mm 3/4" Plasson Saddle 4 - Bolt	No	3	265.78	797.34
522	110mm 1" Plasson Saddle 4 - Bolt	No	3	265.78	797.34
523	110mm 1.1/4" Plasson Saddle 4 - Bolt	No	3	265.78	797.34
524	20mm x 1/2" Plasson Male / Female Adaptor	No	3	78.14	234.42
525	25mm x 1/2" Plasson Male / Female Adaptor	No	3	86.58	259.74
526	32mm x 1/2", 3/4", 1" Plasson Male / Female Adaptor	No	3	102.45	307.35
527	40mm x 1/2, 3/4", 1" Plasson Male / Female Adaptor	No	3	160.28	480.84
528	50mm x 1/2", 3/4", 1" Plasson Male / Female Adaptor	No	3	192.08	576.24
529	63mm x 1/2", 3/4", 1" Plasson Male / Female Adaptor	No	3	280.02	840.06
530	75mm x 1/2", 3/4", 1" Plasson Male / Female Adaptor	No	3	415.68	1,247.04
531	90mm x 1/2", 3/4", 1" Plasson Male / Female Adaptor	No	3	650.14	1,950.42
532	110mm x 2" or 3" or 4" Plasson Male / Female Adaptor	No	3	1,103.31	3,309.93
<u>Sprinklers and hoses</u>					
533	Hunter or equivalent Code "PGJ-4" 19cm, pop up height 10cm spray radius 4,9 - 14m	No	3	372.66	1,117.98
534	Hunter or equivalent Code "PGP-00" 19cm, pop up height 10cm spray radius 4,9 - 14m	No	3	389.55	1,168.65
535	20mm Field Nozzle and Sprinkler Code "5004"	No	3	590.27	1,770.81
536	Hunter or equivalent Code "I-25" 43cm, spray radius 40-71m for timer	No	3	1,235.56	3,706.68
537	Hunter or equivalent Code "I-90" 43cm, spray radius 73-104m for timer	No	3	4,345.72	13,037.16
538	Hunter or equivalent Code "01104 -Gold Range" 43cm, complete sprinkler with valve spray radius 22.3-31.7m for timer	No	3	6,956.91	20,870.73

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Locate, isolate affected area, excavate for and replace damage to Galvanised Steel water supply line and / or fittings in landscaped areas not exceeding 1m deep including backfilling, compacting, etc. and leave in good working order.</u>				
539	15mm pipe	m	6	201.67	1,210.02
540	20mm pipe	m	6	221.81	1,330.86
541	25mm pipe	m	6	244.00	1,464.00
542	32mm pipe	m	6	268.40	1,610.40
543	40mm pipe	m	6	295.25	1,771.50
544	50mm pipe	m	6	324.77	1,948.62
545	65mm pipe	m	6	357.25	2,143.50
	<u>Galvanised Steel fittings</u>				
546	15mm fittings	No	1	97.67	97.67
547	20mm fittings	No	1	98.45	98.45
548	25mm fittings	No	1	115.30	115.30
549	32mm bend	No	1	150.20	150.20
550	40mm bend	No	1	150.00	150.00
551	50mm bend	No	1	165.00	165.00
552	65mm bend	No	1	183.61	183.61
553	32mm tee / reducing tee	No	1	165.00	165.00
554	40mm tee / reducing tee	No	1	150.00	150.00
555	50mm tee / reducing tee	No	1	165.68	165.68
556	65mm tee / reducing tee	No	1	183.61	183.61
557	32mm union	No	1	150.20	150.20
558	40mm union	No	1	150.00	150.00

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
559	50mm union	No	1	150.21	150.21
560	65mm union	No	1	183.61	183.61
	<u>REPLACE DAMAGED WATER PIPE AND FITTINGS</u>				
	<u>Locate, isolate affected area and replace damage to Galvanised Steel water supply line and / or fittings including holderbats, pipe clips, etc. as necessary and leave in good working order.</u>				
561	15mm pipe	m	5	201.67	1,008.35
562	20mm pipe	m	5	221.81	1,109.05
563	25mm pipe	m	5	244.00	1,220.00
564	32mm pipe	m	5	268.40	1,342.00
565	40mm pipe	m	5	295.25	1,476.25
566	50mm pipe	m	5	324.77	1,623.85
567	65mm pipe	m	5	357.25	1,786.25
	<u>Galvanised Steel fittings</u>				
568	15mm fittings	No	2	97.67	195.34
569	20mm fittings	No	2	98.45	196.90
570	25mm fittings	No	2	115.30	230.60
571	32mm bend	No	2	150.20	300.40
572	40mm bend	No	2	150.00	300.00
573	50mm bend	No	2	165.00	330.00
574	65mm bend	No	2	183.61	367.22
575	32mm tee / reducing tee	No	2	165.00	330.00
576	40mm tee / reducing tee	No	2	150.00	300.00
577	50mm tee / reducing tee	No	2	165.68	331.36
578	65mm tee / reducing tee	No	2	183.61	367.22

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
579	32mm union	No	2	150.20	300.40
580	40mm union	No	2	150.00	300.00
581	50mm union	No	2	150.21	300.42
582	65mm union	No	2	183.61	367.22
	<u>Locate, isolate affected area and replace damage to SABS 460 Class 0 hard drawn Copper piping and / or fittings including holderbats, pipe clips, etc. as necessary and leave in good working order.</u>				
583	15mm Pipes	m	7	51.83	362.81
584	22mm pipes	m	7	91.93	643.51
585	28mm pipes	m	7	101.12	707.84
586	35mm pipes	m	7	111.24	778.68
	<u>Conex Compression fittings</u>				
587	15mm fittings	No	1	34.51	34.51
588	22mm fittings	No	1	37.97	37.97
589	28mm fittings	No	1	41.76	41.76
590	35mm bend	No	1	45.94	45.94
591	35mm tee	No	1	45.94	45.94
592	35mm reducer tee	No	1	47.07	47.07
593	35mm union	No	1	45.94	45.94
594	15mm Straight Coupler "Code D604M-15"	No	1	60.65	60.65
595	22mm Straight Coupler "Code D604M-22"	No	1	62.93	62.93
596	28mm Straight Coupler "Code D604M-28"	No	1	88.38	88.38
597	35mm Straight Coupler "Code D604M-35"	No	1	180.51	180.51
598	42mm Straight Coupler "Code D604M-42"	No	1	204.64	204.64

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
599	54mm Straight Coupler "Code D604M-54"	No	1	306.83	306.83
600	76mm Straight Coupler "Code D604M-76"	No	1	769.52	769.52
	<u>Copcal Capillary fittings</u>				
601	15mm fittings	No	1	34.51	34.51
602	22mm fittings	No	1	37.97	37.97
603	28mm fittings	No	1	41.76	41.76
604	35mm bend	No	1	45.94	45.94
605	35mm tee	No	1	45.94	45.94
606	35mm reducer tee	No	1	47.07	47.07
607	35mm union	No	1	45.94	45.94
	<u>Sundries</u>				
608	Carefully chase brickwork / concrete exposing damaged piping and / or fitting not exceeding 35mm diameter including making good plaster on completion (ceramic tiling and replacement elsewhere).	m	1	168.43	168.43
609	Carefully chase brickwork / concrete exposing damaged piping and / or fitting not exceeding 35mm diameter including making good plaster and paint to match existing on completion (replacement elsewhere).	m	1	168.43	168.43
610	Apply new ceramic tiles to plastered or screeded finish including tile adhesive and grouting to match existing (in patches).	m2	10	391.63	3,916.30
	<u>REPLACE DAMAGED ELECTRIC WATER HEATERS AND ACCESSORIES</u>				
	All repairs, servicing and replacement to geysers shall comply with SANS 10254 Dated 15/10/2004				
	<u>KWIKOT OR EQUIVALENT: Geyser with a 5-year warranty</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Locate damage, isolate affected area including draining existing geyser, uncoupling water and electrical connection, lift and remove where required and replace with new geyser and / or accessories complete with re-fitting connections and bond to earth, all fixings, mountings brackets, etc. and leave in good working order.</u>				
611	100 Litre standard high pressure universal wall or roof void mounted water heater complete with connection points for water inlet and outlet, safety valve connection point, sacrificial anode, spiral element and adjustable thermostat, drip tray, vacuum breakers (all other accessories elsewhere).	No	1	6,766.36	6,766.36
612	150 Litre standard high pressure universal wall or roof void mounted water heater complete with connection points for water inlet and outlet, safety valve connection point, sacrificial anode, spiral element and adjustable thermostat, drip tray, vacuum breakers (all other accessories elsewhere).	No	1	7,207.96	7,207.96
613	200 Litre standard high pressure universal wall or roof void mounted water heater complete with connection points for water inlet and outlet, safety valve connection point, sacrificial anode, spiral element and adjustable thermostat, drip tray, vacuum breakers (all other accessories elsewhere).	No	1	9,009.96	9,009.96
614	150 Litre solar water heater roof mounted water heater including solar heating panel complete with connection points for water inlet and outlet, safety valve connection point, sacrificial anode, spiral element and adjustable thermostat, drip tray, vacuum breakers (all other accessories elsewhere).	No	1	20,294.95	20,294.95
615	200 Litre solar water heater roof mounted water heater including solar heating panel complete with connection points for water inlet and outlet, safety valve connection point, sacrificial anode, spiral element and adjustable thermostat, drip tray, vacuum breakers (all other accessories elsewhere).	No	1	22,203.82	22,203.82
	<u>HEAT PUMPS: KWIKOT OR QUIVALENT</u>				
	<u>Supply and install heat pumps complete with pipes, valves, vacuum breakers etc</u>				
616	Integrated 190 heat pump	No	1	19,053.85	19,053.85
617	Retrofit 3,0kW heat pump "Code HP-3.0W"	No	1	20,238.62	20,238.62
618	Retrofit 4,7 kW heat pump :Code HP-4.7W"	No	1	24,425.94	24,425.94

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
619	Retrofit 7,2kW heat pump	No	1	28,089.83	28,089.83
	<u>HYDRO BOILER supply and install complete with a 1-year warranty</u>				
620	2,5 Lt Kwikot Kwikboil or equivalent Instant Water Dispenser	No	1	8,932.17	8,932.17
621	5,0 Lt Kwikot Kwikboil or equivalent Instant Water Dispenser	No	1	10,089.49	10,089.49
622	7,5 Lt Kwikot Kwikboil or equivalent Instant Water Dispenser	No	1	11,371.40	11,371.40
	<u>Replacement Accessories</u>				
623	20mm Brass cold water inlet and draincock	No	1	511.81	511.81
624	20mm Brass temperature and pressure relief valve	No	1	547.81	547.81
625	Spiral element with thermostat pocket for 2,3 or 4kW thermostat (thermostat elsewhere).	No	1	527.40	527.40
626	Sacrificial anode to match existing	No	1	527.58	527.58
627	2kW thermostat integrated double pole contact	No	1	603.57	603.57
628	3kW thermostat integrated double pole contact	No	1	663.93	663.93
629	4kW thermostat integrated double pole contact	No	1	730.33	730.33
630	20mm MI or 22mm CxC Brass vacuum breaker	No	1	435.84	435.84
631	22mm CxC Brass Hi-Flow Mono 100 or 200kPa pressure control valve with integral expansion relief valve.	No	1	547.81	547.81
632	22mm CxC Brass Hi-Flow Mono 400 or 600kPa pressure control valve with integral expansion relief valve.	No	1	779.92	779.92
633	20mm MI or 22mm CxC Brass Hi-Flow Mono 100 or 200kPa pressure control valve with integral isolating valve and expansion relief.	No	1	779.92	779.92
634	20mm MI or 22mm CxC Brass Hi-Flow Mono 400 or 600kPa pressure control valve with integral isolating valve and expansion relief.	No	1	1,000.80	1,000.80
	<u>Sundries</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
635	Drain water heater, isolate and uncouple water and electrical connections, lift water heater, replace / install new uPVC tray complete with 40mm diameter outlet and discharge pipe not exceeding 5m long, and re-fit connection on completion.	No	1	1,391.89	1,391.89
636	Drain water heater, isolate and uncouple water and electrical connections and remove existing geyser / water heater	No	1	463.96	463.96
637	Allowance for new piping into an existing geyser, vacuum breakers and pressure valve measured elsewhere	No	1	397.68	397.68
<u>REPLACE DAMAGED FIRE APPLIANCES, ETC</u>					
<u>Locate damage, isolate affected area, drain existing pipe system where required, and replace with new SABS approved fitting including all fixings, mountings brackets, etc. and leave in good working order.</u>					
638	Hose reel complete with 30m x 19mm diameter rubber hose, chromium plated stopcock, shut-off nozzle and wall bracket.	No	1	2,371.24	2,371.24
639	Hose reel complete with 30m x 19mm diameter plastic hose, chromium plated stopcock, shut-off nozzle and wall bracket.	No	1	2,188.84	2,188.84
640	9kg Dry chemical fire extinguisher	No	1	1,239.45	1,239.45
641	4,5kg Carbon dioxide fire extinguisher	No	1	805.64	805.64
642	4,5kg Carbon dioxide fire extinguisher	No	1	805.64	805.64
643	100mm Diameter 2500 kPa pressure gauge and stopcock	No	1	462.31	462.31
644	80 x 65mm Brass hydrant booster connection with cap and chain	No	1	1,987.47	1,987.47
645	80 x 65mm Brass double hydrant booster connection with cap and chain	No	1	2,285.59	2,285.59
646	Hose reel cabinet according to SABS 1475 Regulations	No	1	4,133.88	4,133.88
<u>Sundries</u>					

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
647	Fire hydrant pedestal comprising of unreinforced concrete 900mm high cast around vertical pipe with bottom 300mm below ground, 300 x 300mm square at base and tapering to octagonal shaped top 200 x 200mm overall including necessary excavations, formwork and two coats of paint to exposed surfaces.	No	1	4,346.59	4,346.59
648	Bracket for Fire Extinguisher supply and install complete	No	1	127.26	127.26
649	290 x 290 Extinguisher signs	No	1	53.02	53.02
	<u>Servicing of Fire Extinguishers including re-fill</u>				
650	2,5kg dry chemical powder fire extinguisher	No	1	118.76	118.76
651	4,5kg dry chemical powder fire extinguisher	No	1	133.62	133.62
652	9kg dry chemical powder fire extinguisher	No	1	145.50	145.50
653	Testing and servicing of Fire Hydrants	No	1	1,126.76	1,126.76
	<u>AQUATICS</u>				
	<u>Water Cleansing and Disinfection Chemicals</u>				
654	25kg Chlorine Chips - HTH Scientific Chips or equivalent	No	1	850.14	850.14
655	28kg Pool Acid - Hydrochloric Acid 30%	No	1	139.11	139.11
656	20kg Pool Stabilizer - STAB 20	No	1	725.39	725.39
	<u>Pool testing</u>				
657	DPD Testing Liquid - Controller Reagents	No	1	829.99	829.99
	<u>Taking out and removing piping, fittings, etc. including cutting off as necessary, disconnecting piping from fittings and making good floor and wall finishes</u>				
658	Pump strainer box set	No	1	178.97	178.97
659	160mm Diameter PVC pipe and setting aside for re-use	m	6	58.32	349.92
660	160mm Diameter PVC pipe and setting aside for re-use	m	6	58.32	349.92
661	200mm Diameter PVC pipe and setting aside for re-use	m	6	58.32	349.92

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
662	300mm Diameter flanged steel pipe	m	6	72.91	437.46
663	160mm Diameter valve and setting aside for re-use	No	1	112.69	112.69
	<u>ACQUATICS</u>				
	<u>WATER SUPPLIES - TO SWIMMING POOLS</u>				
	<u>uPVC class 4 pressure pipes with integral rubber ring joint, Excavation (bedding and backfill elsewhere)</u>				
664	50mm Pipe	m	9	116.72	1,050.48
665	63mm Pipe	m	9	123.22	1,108.98
666	75mm Pipe	m	9	130.89	1,178.01
667	90mm Pipe	m	9	135.19	1,216.71
668	110mm Pipe	m	9	148.27	1,334.43
669	125mm Pipe	m	9	156.02	1,404.18
670	140mm Pipe	m	9	163.16	1,468.44
671	160mm Pipe	m	9	192.54	1,732.86
672	200mm Pipe	m	9	223.19	2,008.71
673	250mm Pipe	m	9	299.21	2,692.89
674	315mm Pipe	m	9	447.71	4,029.39
	<u>uPVC class 6 pressure pipes with integral rubber ring joint</u>				
675	50mm Pipe	m	9	116.72	1,050.48
676	63mm Pipe	m	9	123.22	1,108.98
677	75mm Pipe	m	9	130.89	1,178.01
678	90mm Pipe	m	9	135.19	1,216.71
679	110mm Pipe	m	9	148.27	1,334.43
680	125mm Pipe	m	9	156.02	1,404.18

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
681	140mm Pipe	m	9	163.16	1,468.44
682	160mm Pipe	m	9	192.54	1,732.86
683	200mm Pipe	m	9	223.19	2,008.71
684	250mm Pipe	m	9	299.21	2,692.89
685	315mm Pipe	m	9	447.71	4,029.39
	<u>uPVC class 9 pressure pipes with integral rubber ring joint</u>				
686	50mm Pipe	m	9	116.72	1,050.48
687	63mm Pipe	m	9	123.22	1,108.98
688	75mm Pipe	m	9	130.89	1,178.01
689	90mm Pipe	m	9	135.19	1,216.71
690	110mm Pipe	m	9	148.27	1,334.43
691	125mm Pipe	m	9	156.02	1,404.18
692	140mm Pipe	m	9	163.16	1,468.44
693	160mm Pipe	m	9	192.54	1,732.86
694	200mm Pipe	m	9	223.19	2,008.71
695	250mm Pipe	m	9	299.21	2,692.89
696	315mm Pipe	m	9	745.56	6,710.04
	<u>uPVC class 12 pressure pipes with integral rubber ring joint</u>				
697	50mm Pipe	m	9	106.72	960.48
698	63mm Pipe	m	9	106.72	960.48
699	75mm Pipe	m	9	106.72	960.48
700	90mm Pipe	m	9	126.96	1,142.64
701	110mm Pipe	m	9	128.34	1,155.06
702	125mm Pipe	m	9	162.67	1,464.03

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
703	140mm Pipe	m	9	206.80	1,861.20
704	160mm Pipe	m	9	263.45	2,371.05
705	200mm Pipe	m	9	405.51	3,649.59
706	250mm Pipe	m	9	635.12	5,716.08
707	315mm Pipe	m	9	895.31	8,057.79
	<u>PVC Fittings for uPVC pipes</u>				
708	63mm Serrated stub	No	1	95.99	95.99
709	75mm Serrated stub	No	1	100.01	100.01
710	90mm Serrated stub	No	1	114.25	114.25
711	110mm Serrated stub	No	1	125.74	125.74
712	125mm Serrated stub	No	1	291.38	291.38
713	140mm Serrated stub	No	1	316.98	316.98
714	160mm Serrated stub	No	1	276.26	276.26
715	200mm Serrated stub	No	1	599.03	599.03
716	250mm Serrated stub	No	1	1,182.88	1,182.88
717	50mm Tee	No	1	66.26	66.26
718	63mm Tee	No	1	84.47	84.47
719	75mm Tee	No	1	132.11	132.11
720	90mm Tee	No	1	179.36	179.36
721	110mm Tee	No	1	256.19	256.19
722	160mm Tee	No	1	635.68	635.68
723	200mm Tee	No	1	977.78	977.78
724	250mm Tee	No	1	1,923.96	1,923.96

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
725	45 degree x 50mm Elbow	No	1	68.52	68.52
726	45 degree x 63mm Elbow	No	1	90.27	90.27
727	45 degree x 75mm Elbow	No	1	125.74	125.74
728	45 degree x 90mm Elbow	No	1	161.24	161.24
729	45 degree x 110mm Elbow	No	1	291.68	291.68
730	45 degree x 160mm Elbow	No	1	454.34	454.34
731	45 degree x 200mm Elbow	No	1	700.35	700.35
732	45 degree x 250mm Elbow	No	1	622.95	622.95
733	90 degree x 50mm Elbow	No	1	59.88	59.88
734	90 degree x 63mm Elbow	No	1	72.77	72.77
735	90 degree x 75mm Elbow	No	1	123.09	123.09
736	90 degree x 90mm Elbow	No	1	155.75	155.75
737	90 degree x 110mm Elbow	No	1	202.99	202.99
738	90 degree x 160mm Elbow	No	1	800.30	800.30
739	90 degree x 200mm Elbow	No	1	1,746.50	1,746.50
740	90 degree x 250mm Elbow	No	1	5,295.45	5,295.45
741	110 x 90mm Reducing socket plain	No	1	216.61	216.61
742	160 x 110mm Reducing socket plain	No	1	651.64	651.64
743	250 x 200mm Reducing socket plain	No	1	1,270.07	1,270.07
744	63 x 50mm Reducing bush plain	No	1	47.22	47.22
745	75 x 63mm Reducing bush plain	No	1	92.03	92.03
746	90 x 75mm Reducing bush plain	No	1	76.08	76.08
747	110 x 63mm Reducing bush plain	No	1	96.64	96.64
748	110 x 90mm Reducing bush plain	No	1	96.64	96.64

Generic Bill Of Quantities
Construction And Refurbishment Of Buildings And Facilities
Generic Bill Of Quantities (Provisional)

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
749	140 x 110mm Reducing bush plain	No	1	298.06	298.06
750	160 x110mm Reducing bush plain	No	1	398.32	398.32
751	160 x140mm Reducing bush plain	No	1	327.70	327.70
752	200 x160mm Reducing bush plain	No	1	551.50	551.50
753	250 x160mm Reducing bush plain	No	1	1,541.34	1,541.34
754	250 x200mm Reducing bush plain	No	1	1,541.34	1,541.34
755	63mm Cap	No	1	54.52	54.52
756	90mm Cap	No	1	108.54	108.54
757	110mm Cap	No	1	144.53	144.53
758	140mm Cap	No	1	382.60	382.60
759	160mm Cap	No	1	333.52	333.52
760	200mm Cap	No	1	1,678.78	1,678.78
761	250mm Cap	No	1	1,681.89	1,681.89
762	63mm Socket	No	1	55.42	55.42
763	75mm Socket	No	1	92.86	92.86
764	90mm Socket	No	1	131.75	131.75
765	110mm Socket	No	1	175.74	175.74
766	160mm Socket	No	1	359.36	359.36
767	200mm Socket	No	1	1,129.46	1,129.46
768	250mm Socket	No	1	2,022.15	2,022.15
769	50mm Union	No	1	163.28	163.28
770	63mm Union	No	1	215.63	215.63
771	75mm Union	No	1	607.89	607.89

Generic Bill Of Quantities
Construction And Refurbishment Of Buildings And Facilities
Generic Bill Of Quantities (Provisional)

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
772	90mm Union	No	1	745.39	745.39
773	110mm Union	No	1	882.43	882.43
774	160mm Union	No	1	1,147.16	1,147.16
775	200mm Union	No	1	1,491.32	1,491.32
776	50mm Valve PVC Double union	No	1	429.34	429.34
777	63mm Valve PVC Double union	No	1	631.99	631.99
778	75mm Valve PVC Double union	No	1	1,842.44	1,842.44
779	90mm Valve PVC Double union	No	1	1,842.44	1,842.44
780	110mm Valve PVC Double union	No	1	1,982.24	1,982.24
781	160mm Valve PVC Double union	No	1	2,432.47	2,432.47
782	200mm Valve PVC Double union	No	1	1,114.47	1,114.47
783	63mm Diameter clips	No	1	100.36	100.36
784	90mm Diameter clips	No	1	211.78	211.78
785	110mm Diameter clips	No	1	228.42	228.42
786	160mm Diameter clips	No	1	447.21	447.21
787	200mm Double clips	No	1	447.21	447.21
788	160 x 63mm "Aquatek" saddle	No	1	164.34	164.34
789	PVC Saddle 110 x 2" - 4 Bolt	No	1	164.34	164.34
790	PVC Saddle 160 x 2" - 6 Bolt	No	1	547.36	547.36
791	PVC Saddle 200 x 2" - 6 Bolt	No	1	547.36	547.36
792	90 degree x 63mm Bend	No	1	402.83	402.83
793	90 degree x 75mm Bend	No	1	470.52	470.52
794	90 degree x 90mm Bend	No	1	577.05	577.05
795	90 degree x 110mm Bend	No	1	636.98	636.98

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
796	90 degree x 160mm Bend	No	1	1,357.52	1,357.52
797	90 degree x 200mm Bend	No	1	2,143.70	2,143.70
	<u>Stainless steel SH10 316 Grade pipes</u>				
798	50mm Pipe	m	6	1,020.33	6,121.98
799	100mm Pipe	m	6	1,285.61	7,713.66
800	150mm Pipe	m	6	1,732.78	10,396.68
801	150mm Pipe off-cuts	m	6	1,732.78	10,396.68
802	200mm Pipe	m	6	3,796.85	22,781.10
803	250mm Pipe	m	6	4,946.82	29,680.92
	<u>Extra over stainless steel pipes for fittings</u>				
804	50 x 90 degree Bend	No	1	797.60	797.60
805	80 x 90 degree Bend	No	1	877.36	877.36
806	100 x 90 degree Bend	No	1	1,039.68	1,039.68
807	150 x 90 degree Bend	No	1	1,492.43	1,492.43
808	200 x 90 degree Bend	No	1	3,555.00	3,555.00
809	250 x 90 degree Bend	No	1	5,282.19	5,282.19
	<u>Table D304 stainless steel fittings</u>				
810	50mm Diameter flanges	No	1	608.13	608.13
811	80mm Diameter flanges	No	1	766.26	766.26
			1		0.00
812	100mm Diameter flanges	No	1	924.37	924.37
813	125mm Diameter flanges	No	1	1,164.70	1,164.70
814	150mm Diameter flanges	No	1	1,405.04	1,405.04
815	200mm Diameter flanges	No	1	2,135.66	2,135.66

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
816	250mm Diameter flanges	No	1	4,511.58	4,511.58
	<u>Table D mild steel fittings</u>				
817	50mm Diameter flanges	No	1	132.57	132.57
818	80mm Diameter flanges	No	1	167.05	167.05
819	100mm Diameter flanges	No	1	201.51	201.51
820	125mm Diameter flanges	No	1	253.90	253.90
821	150mm Diameter flanges	No	1	306.30	306.30
822	200mm Diameter flanges	No	1	465.55	465.55
823	250mm Diameter flanges	No	1	707.65	707.65
	<u>Galvanised fittings</u>				
824	15mm Equal tee	No	1	7.29	7.29
825	22mm Equal tee	No	1	9.85	9.85
826	32mm Equal tee	No	1	13.28	13.28
827	15mm Barrel nipples	No	1	4.48	4.48
828	22mm Barrel nipples	No	1	6.04	6.04
829	32mm Barrel nipples	No	1	7,248.52	7,248.52
	<u>TABLE D Galvanised backing ring</u>				
830	63mm Diameter	No	1	175.12	175.12
831	75mm Diameter	No	1	207.95	207.95
832	90mm Diameter	No	1	254.89	254.89
833	110mm Diameter	No	1	301.85	301.85
834	160mm Diameter	No	1	469.52	469.52
835	200mm Diameter	No	1	637.22	637.22
836	250mm Diameter	No	1	1,236.59	1,236.59

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>TYPE BS4504 Galvanised backing ring</u>				
837	63mm Diameter	No	1	148.17	148.17
838	75mm Diameter	No	1	180.75	180.75
839	110mm Diameter	No	1	372.64	372.64
840	160mm Diameter	No	1	469.52	469.52
841	200mm Diameter	No	1	637.22	637.22
842	250mm Diameter	No	1	1,341.51	1,341.51
	<u>Rubber Flex Couplings fittings</u>				
843	50mm Rubberflex couple	No	1	394.22	394.22
844	80mm Rubberflex couple	No	1	544.03	544.03
845	100mm Rubberflex couple	No	1	750.76	750.76
846	150mm Rubberflex couple	No	1	1,036.03	1,036.03
847	200mm Rubberflex couple	No	1	1,429.75	1,429.75
848	63mm Diameter gasket	No	1	8.40	8.40
849	80mm Diameter gasket	No	1	8.81	8.81
850	100mm Diameter gasket	No	1	9.23	9.23
851	160mm Diameter gasket	No	1	14.67	14.67
852	200mm Diameter gasket	No	1	16.03	16.03
853	250mm Diameter gasket	No	1	47.51	47.51
	<u>TAPS, VALVES, ETC</u>				
854	0 - 100KpA PM/63 utility gauge	No	1	88.02	88.02
855	15mm Fullbore ball valve	No	1	49.78	49.78
856	50mm Fullbore ball valve	No	1	84.62	84.62

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>FILTER ROOM - Swimming pools</u>				
	<u>Colliquip Industrial Filters or equally approved</u>				
857	Type "IF 36/1 JHB Type" filter tanks	No	1	24,299.86	24,299.86
858	Purpose-made strainer tank complete with pipes and flanges (Steel)	No	1	37,647.07	37,647.07
859	40kg Filter bags media 0,6 - 1,5mm grade	No	1	138.73	138.73
	<u>RSV Valves - To swimming pools</u>				
860	50mm Diameter RHC c/w CAP/Hand wheel	No	1	2,388.46	2,388.46
861	80mm Diameter RHC c/w CAP/Hand wheel	No	1	2,721.23	2,721.23
862	100mm Diameter RHC c/w CAP/Hand wheel	No	1	3,342.52	3,342.52
863	200mm Diameter RHC c/w CAP/Hand wheel	No	1	8,026.88	8,026.88
864	250mm Diameter RHC c/w CAP/Hand wheel	No	1	13,834.52	13,834.52
	<u>PVC Butter Fly Valves - To swimming pools</u>				
865	63mm Diameter	No	1	714.75	714.75
866	75mm Diameter	No	1	777.28	777.28
867	90mm Diameter	No	1	837.65	837.65
868	110mm Diameter	No	1	1,093.60	1,093.60
869	160mm Diameter	No	1	1,491.63	1,491.63
870	200mm Diameter	No	1	2,227.51	2,227.51
	<u>Gaskets for PVC Stubs</u>				
871	63mm Diameter	No	1	15.76	15.76
872	75mm Diameter	No	1	20.52	20.52
873	90mm Diameter	No	1	26.66	26.66
874	110mm Diameter	No	1	34.66	34.66

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
875	160mm Diameter	No	1	45.07	45.07
876	200mm Diameter	No	1	67.08	67.08
877	250mm Diameter	No	1	100.62	100.62
	<u>Pumps</u>				
878	Submersible Pumps 0,75kW 220V submersible	No	1	7,788.43	7,788.43
879	Submersible Pumps 1,1kW 220V submersible	No	1	8,956.70	8,956.70
880	Submersible Pumps 0,75kW 380V submersible	No	1	15,119.39	15,119.39
881	Submersible Pumps 1,5kW 380V submersible	No	1	22,679.11	22,679.11
	<u>MOTORS, PUMPS, ETC.</u>				
882	7,5kW pump, motor and base set complete with star delta starter	No	1	54,781.69	54,781.69
883	11,5kW pump, motor and base set complete with star delta starter	No	1	60,259.84	60,259.84
884	22kW pump, motor and base set complete with star delta starter	No	1	90,389.77	90,389.77
885	32kW pump, motor and base set complete with star delta starter	No	1	119,540.47	119,540.47
886	37kW pump, motor and base set complete with star delta starter	No	1	137,471.54	137,471.54
	<u>WATER TANKS - To Roofs</u>				
	<u>Supply and install water tanks to roof complete with connectors, pipes, valves, taps, etc. 40mm tank connector, Inlet and over flow with a 40mm fitting, 450mm lid on top of tank. Including hoisting to up to 12m high roof. Pumps measured elsewhere</u>				
887	2 500 Lt Jojo or equivalent Vertical Water Tank	No	1	7,332.44	7,332.44
888	5 000 Lt Jojo or equivalent Vertical Water Tank	No	1	10,986.69	10,986.69
889	10 000 Lt Jojo or equivalent Vertical Water Tank	No	1	26,411.32	26,411.32

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
890	15 000 Lt Jojo or equivalent Vertical Water Tank	No	1	39,145.56	39,145.56
891	20 000 Lt Jojo or equivalent Vertical Water Tank	No	1	56,113.26	56,113.26
<u>PLUMBING WORKS - LABOUR RATES (Limited to Bill no.16 - For items without rates)</u>					
<u>Normal hours</u>					
892	General Labour (R206 per day)	Hrs	9	22.88	205.92
893	Semi Skilled (R297 per day)	Hrs	9	33.00	297.00
894	Plumbing Artisan (R480 per day)	Hrs	9	53.33	479.97
<u>After normal hours and Saturdays</u>					
895	General Labour	Hrs	9	34.32	308.88
896	Semi Skilled	Hrs	9	49.50	445.50
897	Plumbing Artisan	Hrs	9	80.00	719.96
<u>Sundays and holidays</u>					
898	General Labour	Hrs	9	45.76	411.84
899	Semi Skilled	Hrs	9	66.00	594.00
900	Plumbing Artisan	Hrs	9	106.66	959.94
<u>TESTING AND COMMISIONING</u>					
901	Leak detection	No	1	5,729.08	5,729.08
902	Certificate of Compliance for Geyser installations and other new piping installation. (No COC for repair work)	No	1	463.96	463.96
<u>POOL HEATING SYSTEM</u>					
<u>Marshall-Fowler or equally approved</u>					
903	Model "EW40/380V Electrode hot water heater including shells, electrode assemblies with automatic load adjustment mechanisms, IP54 electrical control panels with controls, safety valves and instruments, all mounted on channel bases and in accordance with specifications	No	1	227,304.81	227,304.81

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
904	2500 Litre hot water storage tank, with 450NB flange complete with safety valve, air vent, sockets, lagging and cladding, epoxy coated inside, isolating valve and thermostat	No	1	81,236.21	81,236.21
905	SPT12 Single water softener based on 24hour boiler operation complete with start-up chemicals to ensure good quality water to boiler system and chemical dosing pump.	No	1	27,741.77	27,741.77
906	Hot water circulating pump between hot water heaters, storage tank and plate heat exchanger	No	1	18,614.19	18,614.19
907	Titanium plate heat exchanger Model APV SR2 MG-16E/1	No	1	71,628.91	71,628.91
908	Inter-connecting pipework between hot water heater, storage tank, pumps and heat exchanger complete with 200litre expansion tank, air vent, temperature gauge, lagging, cladding and flow switch.	No	1	79,716.07	79,716.07
909	Inter-connecting pipework between heat exchanger and swimming pool pumps including modification to water lines, valves and fittings	No	1	35,045.38	35,045.38
910	Installation and commissioning of complete pool heating reticulation system	No	1	66,948.87	66,948.87
	<u>Skimmers, Weirs and Drains</u>				0.00
	<u>Stainless Steel</u>				0.00
					0.00
					0.00
					0.00
911	250mm Diameter weir with heavy duty skimmer baskets	No	1	4,273.27	4,273.27
	<u>SINKS AND TABLES</u>				
	<u>Sinks</u>				
	<u>Stainless Steel</u>				
	<u>Vulcan or equally approved</u>				
912	Model "DCBPS 1850" Double Bowl pot sink with splashback	No	1	13,103.37	13,103.37
913	Model "DCBPS 2250" Double Bowl pot sink with splashback	No	1	15,068.91	15,068.91
914	Model "DCBS 18" Double Bowl preparation sink with splashback	No	1	12,920.81	12,920.81

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
915	Model "DCBS 22" Double Bowl preparation sink with splashback	No	1	14,858.92	14,858.92
	<u>Swimming Pool Sundries</u>				
	<u>Gingoni or equally approved</u>				
916	Code "GR200/X" 200mm wide level deck grid	m	1	452.43	452.43
917	Code "GR250/X" 250mm wide level deck grid	m	1	455.79	455.79
918	Code "GR300/X" 300mm wide level deck grid	m	1	512.26	512.26
919	50m Jumbo (150mm) anti-turbulent swimming lanes complete with stainless steel ratchets	No	1	9,146.64	9,146.64
920	Storage trolleys and drums for lanes (galvanised) consisting of two trolleys and eleven drums	No	1	44,742.34	44,742.34
921	Refurbishment of starting blocks and fibreglassing of platforms	No	1	800.33	800.33
922	25m Jumbo (150mm) anti-turbulent swimming lanes complete with stainless steel ratchets	No	1	4,573.32	4,573.32
923	Storage trolleys and drums for lanes (galvanised) consisting of one trolley and five drums	No	1	20,732.40	20,732.40
					3,465,025.63
	SUB-TOTAL (Carried To Summary)				47,863,096.44

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>BILL No. 22</u>				
	<u>ELECTRICAL INSTALLATION , AIRCONDITION UNITS & AUDIO VISUAL EQUIPMENT</u>				
	<u>Bare Stranded Copper Earth Wire</u>				
	<u>Supply, delivery and installation of bare stranded copper fixed to cable tray or rack (tray measured elsewhere):</u>				
1	70mm ²	m	5	185.30	926.48
2	50mm ²	m	5	118.33	591.64
3	25mm ²	m	5	87.37	436.87
4	16mm ²	m	5	63.71	318.57
5	10mm ²	m	5	45.53	227.64
6	6mm ²	m	5	11.06	55.30
7	4mm ²	m	5	8.46	42.30
8	2,5mm ²	m	5	7.80	39.00
	<u>Supply, delivery and installation of terminations including fastening materials and lugs, and the connection to the specified terminal equipment:</u>				
9	70mm ²	m	5	149.54	747.70
10	50mm ²	m	5	104.02	520.10
11	25mm ²	m	5	97.53	487.65
12	16mm ²	m	5	71.52	357.60
13	10mm ²	m	5	36.40	182.00
14	6mm ²	m	5	32.52	162.60
15	4mm ²	m	5	26.01	130.05
16	2,5mm ²	m	5	26.01	130.05

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>LIGHTING AND SMALL POWER</u>				
	<u>CONDUITS</u>				
	<u>PVC CONDUIT</u>				
	Supply, deliver and install of conduit including bushes, couplings, saddles, bends, wastage etc				
	<u>Surface mounted to brickwork, concrete, steel, wood, roof members, etc exceeding 3000mm above floor level</u>				
17	20mm Diameter	m	5	19.50	97.50
18	25mm Diameter	m	5	28.61	143.05
19	50mm Diameter	m	5	41.62	208.10
	<u>Chased and/or fixed in brickwork not exceeding 3000mm above floor level (making good of chase by others)</u>				
20	20mm Diameter	m	5	58.51	292.55
21	25mm Diameter	m	5	71.52	357.60
22	50mm Diameter	m	5	97.53	487.65
	<u>GALVANISED CONDUIT</u>				
	<u>Surface mounted to brickwork, concrete, steel, wood, roof members, etc exceeding 3000mm above floor level</u>				
			5		0.00
23	20mm Diameter	m	5	64.02	320.10
			5		0.00
24	25mm Diameter	m	5	81.54	407.70
	<u>LIGHTING AND SMALL POWER</u>				
	<u>CONDUIT BOXES AND FITTINGS</u>				
25	Cover plate for 100mm x 100mm box	No	5	58.51	292.55
26	Cover plate for 100mm x 50mm box	No	5	39.01	195.05
	<u>POWER SKIRTING</u>				
	The rates include for splices, joining, drilling, etc				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Power skirting complete with cover surface mounted to brickwork or concrete</u>				
27	One-compartment	m	5	455.38	2,276.90
28	Two-compartment	m	5	529.24	2,646.20
29	16A Normal power sso on power skirting,complete with pre-punched cover	m	5	140.19	700.95
30	16A Normal power sso on power skirting. complete with pre punched cover.	m	5	185.96	929.80
31	16A DUO SSO IN Power skirting	m	5	294.32	1,471.60
32	16A Red dedicated	m	5	207.41	1,037.05
33	20A DP Isolator c/w cord grip in power skirting	m	5	214.92	1,074.60
34	One-compartment end cap	No	5	128.05	640.25
35	Two-compartment end cap	No	5	195.06	975.30
36	One-compartment 90 degree bend	No	5	278.71	1,393.55
	<u>SWITCHES AND PLUGS</u>				
	<u>Switches, etc complete with cover plate fixed in flush box</u>				
37	16A One-lever one-way switch	No	5	115.73	578.65
38	16A Two-lever one-way switch	No	5	136.54	682.70
39	16A Three-lever one-way switch	No	5	143.05	715.25
40	16A Four-lever one-way switch	No	5	214.57	1,072.85
41	16A One-lever two-way switch	No	5	123.53	617.65
42	16A Two-lever two-way switch	No	5	140.43	702.15
43	2 Lever / 3 Lever - Grid plate with surround	No	5	55.26	276.30
44	2x4 Grid Plate with surround	No	5	71.52	357.60
45	4x4 Grid Plate with surround	No	5	84.52	422.60

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
46	16A Three-pin Single switched socket outlet	No	5	157.35	786.75
47	16A Three-pin Double switched socket outlet	No	5	214.57	1,072.85
48	Round Three pin socket outlet	No	5	74.77	373.85
49	Bell push button complete with surround	No	5	120.28	601.40
50	16A One lever dimmer switch	No	5	416.11	2,080.55
51	Single telephone socket outlet (RJ11) complete with surround	No	5	237.31	1,186.55
52	Single TV socket outlet complete with surround	No	5	243.17	1,215.85
53	16 A 1-way Light switch insert	No	5	71.52	357.60
54	16 A 2-way Light switch insert	No	5	84.52	422.60
55	4 x 4 Extension box with spouts	No	5	71.52	357.60
56	4 x 2 Extension box with spouts	No	5	58.51	292.55
57	Stove one-way switch	No	5	156.04	780.20
	<u>WIRING</u>				
	<u>Supply, delivery and installation of cables</u>				
	<u>PVC Multicore Armoured Cable</u>				
58	4 mm 3-core	m	5	54.88	274.40
59	2,5 mm 3-core	m	5	38.75	193.75
60	2,5 mm 4-core	m	5	45.29	226.45
61	4 mm 4-core	m	5	62.97	314.85
62	6 mm 3-core	m	5	71.84	359.20
63	6 mm 4-core	m	5	88.57	442.85
64	10 mm 3-Core	m	5	103.42	517.10
65	10 mm 4-Core	m	5	129.56	647.80

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
66	16 mm 3-Core	m	5	132.61	663.05
67	16 mm 4-Core	m	5	165.16	825.80
68	25 mm 3-Core	m	5	203.29	1,016.45
69	25 mm 4-Core	m	5	256.16	1,280.80
70	35 mm 3-Core	m	5	283.44	1,417.20
71	35 mm 4-Core	m	5	356.74	1,783.70
72	70 mm 3-Core	m	5	542.66	2,713.30
73	70 mm 4-Core	m	5	675.06	3,375.30
74	95 mm 4-Core	m	5	710.16	3,550.80
	<u>Flexible Cable and Cord</u>				
75	1,5mm2 twin rip cord	m	5	20.46	102.30
76	2,5mm2 twin rip cord	m	5	28.25	141.25
77	1,5mm2 PVC carb tyre flex 3-core	m	5	27.28	136.40
78	2,5mm2 PVC carb tyre flex 3-core	m	5	35.94	179.70
79	4mm2 PVC carb tyre flex 3-core	m	5	58.18	290.90
80	6mm2 PVC carb tyre flex 3-core	m	5	100.58	502.90
81	1,5mm2 Suffix Cable 3-core and earth	m	5	31.35	156.75
82	2,5mm2 Suffix Cable 3-core and earth	m	5	38.52	192.60
83	4,0mm2 Suffix Cable 3-core and earth	m	5	52.31	261.55
84	6,0mm2 Suffix Cable 3-core and earth	m	5	70.82	354.10
85	1,5mm2 Suffix Cable 4-core and earth	m	5	34.53	172.65
86	2,5mm2 Suffix Cable 2-core and earth	m	5	32.87	164.35
87	6,0mm2 Suffix Cable 2-core and earth	m	5	58.77	293.85
88	1,5mm2 Flat twin and earth	m	5	25.10	125.50

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
89	2,5mm2 Flat twin and earth	m	5	30.55	152.75
90	4,0mm2 Flat twin and earth	m	5	42.03	210.15
91	6,0mm2 Flat twin and earth	m	5	55.36	276.80
	<u>LIGHT FITTINGS</u>				
	<u>Supply and install luminaires or equipment complete with lamps, connections, etc mounted in position</u>				
92	2 # 1200mm Surface florescent	No	5	853.17	4,265.85
93	2 # 1500mm Surface florescent	No	5	910.25	4,551.25
94	2 # 18W Round bulkhead	No	5	422.62	2,113.10
95	2 # 18W Square bulkhead	No	5	455.12	2,275.60
96	CFL light fitting for energy lights wall mounted	No	5	455.12	2,275.60
97	4FT - CFL CFL Fluorescent light for energy lights	No	5	715.19	3,575.95
98	30W MH Highbay	No	5	2,481.07	12,405.35
99	50W MH Highbay	No	5	2,925.79	14,628.95
100	70W Mercury Vapour Floodlight	No	5	975.26	4,876.30
101	400W Mercury Vapour Floodlight	No	5	1,394.63	6,973.15
102	Fluorescent lights starters: 220..240v	No	5	292.58	1,462.90
103	Photo cells	No	5	280.35	1,401.75
104	Poly bulkhead	No	5	143.05	715.25
105	60W down light	No	5	266.58	1,332.90
106	125W Mercury Vapour Reef light	No	5	1,495.47	7,477.35
107	250W HPS Flood Light	No	5	1,399.80	6,999.00
108	400W HPS Flood Light	No	5	1,655.95	8,279.75
109	125W Pole Mounted Street Light	No	5	2,403.05	12,015.25

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
110	1000W HPS Flood Light	No	5	7,712.39	38,561.95
	<u>LED LIGHT FITTINGS</u>				
	<u>BEKA OR EQUALLY APPROVED</u>				
111	LEDflood48/117N1600A1G	No	5	8,870.41	44,352.05
112	LEDflood60/145N1600A1G	No	5	9,758.21	48,791.05
113	EC 35.1140-18W LED downlight, C/W LED engine and driver	No	5	3,159.13	15,795.65
114	BEKA T-BAY 4 x FQ53W/940, medium beam complete with lamps	No	5	3,170.96	15,854.80
115	Vapourlux 280 EVG, T5 complete with lamp (Alternative Ecolux 2 x 80W T5)	No	5	2,186.19	10,930.95
116	Ecolux 2 x 58W, electronic ballast complete with lamp	No	5	1,383.73	6,918.65
117	Bekabulk 12 LED, colour: RAL 7045 Telegrey 1	No	5	3,348.78	16,743.90
	<u>LIGHT BULBS AND GLOBES</u>				
	<u>Changing light bulbs/globes with energy saving bulbs</u>				
118	60 W Bulb	No	5	32.52	162.60
119	100 W Bulb	No	5	32.52	162.60
120	4FT Florescent bulb	No	5	52.01	260.05
121	5FT Florescent bulb	No	5	54.62	273.10
122	8FT Florescent bulb	No	5	78.03	390.15
123	Ballast 220V DBL 75W	No	5	455.12	2,275.60
124	200W Mercury bulb	No	5	654.93	3,274.65
125	125W Mercury bulb	No	5	137.60	688.00
126	400 W Mercury bulb	No	5	654.93	3,274.65
127	60W downlight bulb	No	5	62.93	314.65

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>LIGHTNING PROTECTION SYSTEMS</u>				
	Installed in accordance with the latest SANS Codes of Practise 10199 (2004) and 10313 (2008) in conjunction with SANS 62305-1-2-3-4: 2007 and IEC 62305-1-2-3-4 :2006				
	<u>Conductors, etc</u>				
128	Reinforced concrete bonding terminal	No	5	650.17	3,250.85
129	Earth electrode test joint	No	5	390.10	1,950.50
130	Tail type bonding terminal fixed to concrete reinforcing rods	No	5	1,040.28	5,201.40
	<u>DISTRIBUTION BOARDS</u>				
	<u>Flush and Surface Mounted Distribution Boards</u>				
131	12-Way Steel Distribution Board, complete with 1 Plastic Cover and 1 Steel Tray (Mini Rail) Flush Mounted	No	5	845.23	4,226.15
132	12-Way Steel Distribution Board, complete with 1 Steel Cover and 1 Steel Tray (Mini Rail) Flush Mounted	No	5	845.23	4,226.15
133	13-Way DMC Polyester Flush Distribution Board adjustable with plaster Gauge, 1 Polyester Cover and 1 Polyester Tray (Mini Rail) Flush and Surface Mounted	No	5	845.23	4,226.15
134	13-Way Surface Mount Distribution Board (Mini Rail) Surface Mounted	No	5	715.19	3,575.95
135	20-Way Steel Distribution Board, complete with 1 Steel Cover and 1 Steel Tray (Mini Rail) Flush Mounted	No	5	1,105.29	5,526.45
136	20-Way Steel Distribution Board, complete with 1 Steel Cover and 1 Steel Tray (Mini Rail) Flush Mounted	No	5	1,105.29	5,526.45
137	40-Way Architrave Board (2x20-Way and Tray)	No	5	2,733.34	13,666.70
138	60-Way Architrave Board (3 x 20-Way and Tray)	No	5	3,297.69	16,488.45
139	Labelling of DB Board (per label)	No	5	1.30	6.50
	<u>CIRCUIT BREAKERS</u>				
	<u>Fully Installed complete to DB including interconnecting cables</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Residential - 13mm Hydraulic Magnetic:</u>				
	<u>Single Pole</u>				
140	5A (3kA) 1-Pole mcb's	No	5	294.65	1,473.25
141	10A, 15A, 20A (3kA) 1-Pole mcb's	No	5	303.24	1,516.20
142	25A, 30A, 35A, 40A (3kA) 1-Pole mcb's	No	5	343.29	1,716.45
143	40A, 50A, 60A (3kA) 1-Pole mcb's	No	5	360.46	1,802.30
144	80A (3kA) 1-Pole mcb's	No	5	534.44	2,672.20
145	100A (3kA) 1-Pole mcb's	No	5	620.27	3,101.35
	<u>Double Pole</u>				
146	5A (3kA) 2-Pole mcb's	No	5	1,124.29	5,621.45
147	10A, 15A, 20A (3kA) 2-Pole mcb's	No	5	1,155.75	5,778.75
148	25A, 30A, 35A, 40A (3kA) 2-Pole mcb's	No	5	1,201.52	6,007.60
149	40A, 50A, 60A (3kA) 2-Pole mcb's	No	5	1,278.77	6,393.85
150	80A (3kA) 2-Pole mcb's	No	5	2,273.02	11,365.10
151	100A (3kA) 2-Pole mcb's	No	5	2,273.02	11,365.10
	<u>Triple Pole</u>				
152	5A (3kA) 3-Pole mcb's	No	5	1,662.11	8,310.55
153	10A, 15A, 20A (3kA) 3-Pole mcb's	No	5	1,805.15	9,025.75
154	25A, 30A, 35A, 40A (3kA) 3-Pole mcb's	No	5	1,833.76	9,168.80
155	40A, 50A, 60A (3kA) 3-Pole mcb's	No	5	1,888.10	9,440.50
	<u>Single Pole and Neutral</u>				
156	5A (3kA) 1-Pole N mcb's	No	5	795.29	3,976.45
157	10A, 15A, 20A, (3kA) 1-Pole N mcb's	No	5	795.29	3,976.45
158	25A, 30A, 35A, 40A, 50A (3kA) 1-Pole N mcb's	No	5	846.79	4,233.95

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
159	60A (3kA) 1-Pole N mcb's <u>Triple Pole and Neutral</u>	No	5	858.24	4,291.20
160	5A, 10A, 15A, 20A, 25A (3kA) 3-Pole N mcb's	No	5	2,159.89	10,799.45
161	30A, 35A, 40A, 50A (3kA) 1-Pole N mcb's <u>Commercial / Industrial- 13mm Hydraulic Magnetic:</u> <u>Single Pole</u>	No	5	2,208.51	11,042.55
162	5A (6kA) 1-Pole mcb's	No	5	323.27	1,616.35
163	10A, 15A, 20A (6kA) 1-Pole mcb's	No	5	331.85	1,659.25
164	25A (6kA) 1-Pole mcb's <u>Double Pole</u>	No	5	369.04	1,845.20
165	5A (6kA) 2-Pole mcb's	No	5	1,224.41	6,122.05
166	10A, 15A, 20A (6kA) 2-Pole mcb's	No	5	1,258.74	6,293.70
167	25A (6kA) 2-Pole mcb's <u>Triple Pole</u>	No	5	1,370.30	6,851.50
168	5A (6kA) 3-Pole mcb's	No	5	1,962.48	9,812.40
169	10A, 15A, 20A (6kA) 3-Pole mcb's	No	5	1,916.71	9,583.55
170	25A (6kA) 3-Pole mcb's <u>Single Pole and Neutral</u>	No	5	2,002.54	10,012.70
171	5A, 10A, 15A, 20A (6kA) 1-Pole N mcb's	No	5	863.94	4,319.70
172	25A (6kA) 1-Pole N mcb's <u>Triple Pole and Neutral</u>	No	5	918.31	4,591.55
173	5A, 10A, 15A, 20A (6kA) 3-Pole N mcb's	No	5	2,351.55	11,757.75
			5		0.00
174	25A (6kA) 3-Pole N mcb's	No	5	2,431.66	12,158.30

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>ISOLATORS / SWITCH CONNECTORS</u>				
175	63A (3kA) 1-Pole Isolator	No	5	291.80	1,459.00
176	63A (3kA) 2-Pole Isolator	No	5	583.59	2,917.95
177	63A (3kA) 3-Pole Isolator	No	5	898.29	4,491.45
178	63A (3kA) 4-Pole Isolator	No	5	1,130.00	5,650.00
179	63A (6kA) 1-Pole Isolator	No	5	340.43	1,702.15
180	63A (6kA) 2-Pole Isolator	No	5	635.09	3,175.45
181	63A (6kA) 3-Pole Isolator	No	5	992.69	4,963.45
182	63A (6kA) 4-Pole Isolator	No	5	1,273.04	6,365.20
183	100A (6kA) 1-Pole Isolator	No	5	635.09	3,175.45
184	100A (6kA) 2-Pole Isolator	No	5	1,218.68	6,093.40
185	100A (6kA) 3-Pole Isolator	No	5	2,013.99	10,069.95
186	100A (6kA) 4-Pole Isolator	No	5	2,683.40	13,417.00
	<u>EARTH LEAKAGE PROTECTION</u>				
187	63A (N/A) 1-Pole N	No	5	1,304.90	6,524.50
188	63A (3kA) 1-Pole N	No	5	2,660.52	13,302.60
189	63A (N/A) 3-Pole N	No	5	2,773.65	13,868.25
190	63A (3kA) 3-Pole N	No	5	4,841.21	24,206.05
191	63A (6kA) 1-Pole N	No	5	3,193.01	15,965.05
192	100A (6kA) 1-Pole N	No	5	4,474.50	22,372.50
193	63A (6kA) 3-Pole N	No	5	5,121.37	25,606.85
194	80A (6kA) 3-Pole N	No	5	7,242.31	36,211.55
195	100A (6kA) 1-Pole N	No	5	3,454.38	17,271.90
	<u>STOVES</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Supply and install Domestic Cable stove including a 2-year warranty and guarantee</u>				
	<u>Free Standing Stoves</u>				
196	Free standing Defy or equivalent 4-plate compact electric stove. Dimensions Height:975, Width:500, Depth:620 Features 4 Solid plates Static oven with 3 function selector switch Easy clean enamel oven interior 57 Litre oven capacity Temperature range 70°C to 230°C Air-cooled oven door Chrome-plated oven shelf Roasting pan	No	5	5,331.44	26,657.20
197	Free standing Defy or equivalent 3-plate compact electric plug in stove. Dimensions: Height:975, Width:500, Depth:620. Features: 3 Solid plates , Static oven with 3 function selector switch, Easy clean enamel oven interior, 57 Litre oven capacity, Temperature range 70°C to 230°C, Air-cooled oven door, 1 Chrome-plated oven shelf, Roasting pan	No	5	4,486.21	22,431.05
	<u>Built in stoves</u>				
	<u>Supply, deliver and installation complete:</u>				
198	Built in Defy Model DHD 316/S/S DHD 319 or equivalent 2-plate HOB. Solid plates, control knobs and switch indicator lights. Dimensions: Length: 510, Width: 288, Depth: 71mm. Built in cupboard measured elsewhere.	No	5	1,365.36	6,826.80
199	Built in Defy Model BLK DHD 332 or equivalent 4-plate HOB. Solid plates. Dimensions: Length: 592, Width: 500, Depth: 60mm. Built in cupboard measured elsewhere. Connected with built in Oven	No	5	1,950.53	9,752.65
200	Built in Defy Model BLK DHD 330 or equivalent 4-plate HOB. Solid plates, plate indicator lights, vitreous enamel panel with control knobs (6-heat options). Dimensions: Length: 592, Width: 500, Depth: 90mm. Built in cupboard measured elsewhere.	No	5	2,275.62	11,378.10
201	Built in Defy Model: BLK DBO451 or equivalent slimline oven. Static oven with grill and baking functions. Ringer timer, Oven light, Oven Thermostat, Plate Pilot lights and adjustable chrome lights	No	5	3,706.00	18,530.00
	<u>Miscellaneous:</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
202	Solid plate 6inch- r-dot 4mm b-trim	No	5	314.04	1,570.20
203	Solid plate 8inch- r-dot 4mm b-trim	No	5	397.91	1,989.55
204	Stove fuse 10amp	No	5	110.40	552.00
205	Stove fuse 15amp	No	5	115.59	577.95
206	Stove fuse 20amp	No	5	115.59	577.95
207	Stove fuse 25amp	No	5	115.34	576.70
208	Stove fuse 30amp	No	5	110.40	552.00
209	Fuse holder twin screw	No	5	378.40	1,892.00
210	Stove knob	No	5	115.73	578.65
	<u>CONNECTIONS</u>				
	<u>These items are for connecting geysers, stoves, etc</u>				
211	Geyser connection	No	5	181.26	906.30
212	Stove connection	No	5	303.13	1,515.65
213	Handryer connection	No	5	181.26	906.30
214	Gate motor connection	No	5	455.12	2,275.60
215	Air conditioning connection	No	5	455.12	2,275.60
	<u>SUNDRIES</u>				
216	Testing and commissioning	No	5	1,840.12	9,200.60
217	Coc on existing installation	No	5	715.19	3,575.95
218	Coc on new installation	No	5	1,300.36	6,501.80
219	Cable warning tape placed 150mm above cables in excavations	m	5	52.01	260.05
220	Fault tracing	No	5	715.19	3,575.95
221	Geyser timer	No	5	643.67	3,218.35
	<u>ALTERATIONS (Electrical works)</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Removal of faulty electrical components and carting off site</u>				
222	Removal of plugs, light switches, sockets etc	No	5	42.26	211.30
223	Removal of cables and wires	m	5	6.51	32.55
224	Removal of faulty stove connection, cover up and make good	No	5	202.85	1,014.25
225	Removal of faulty Airconditioning connection	No	5	455.12	2,275.60
226	Removal of faulty gate motor including base plate	No	5	455.12	2,275.60
	<u>GATE MOTORS</u>				
	<u>Supply and installation of a Gate Motor complete with backup battery, foundation plate, 4m rack, adaptor kit, lightning protection, sensor, intelligent speed control, lockable manual over ride, with two remotes, (electrical installation measured elsewhere). With a 12 months guarantee and 5-year warranty.</u>				
227	Centurion D2 or equivalent sliding gate motor for gates up to 250kg	No	5	6,973.14	34,865.70
228	Centurion D5 or equivalent sliding gate motor for gates up to 500kg	No	5	9,655.12	48,275.60
229	Centurion D10 or equivalent sliding gate motor for gates up to 1000kg	No	5	15,126.33	75,631.65
	<u>AIR CONDITIONING UNITS</u>				
	<u>Supply and install BTU Split Unit airconditioner complete, with a standard back to back installation, 2m of copper pipe, cable and drain pipe, an electrical power supply to nearest plug socket, and mounting brackets. Features must include a cooling and heating, minimum temp of 18°C and maximum temp of 30°C. With auto cool, power failure auto restart, electronic touch controls with remote, 12 hour on/off timer. With a 5-year warranty</u>				
230	9 000 BTU	No	5	9,655.12	48,275.60
231	12 000 BTU	No	5	10,942.46	54,712.30
232	18 000 BTU	No	5	15,233.62	76,168.10

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
233	24 000 BTU	No	5	19,953.89	99,769.45
234	30 000 BTU	No	5	43,886.86	219,434.30
235	36 000 BTU	No	5	50,388.62	251,943.10
	<u>Supply and install BTU Cassette Unit airconditioner complete, with a standard installation, 2m of copper pipe, cable and drain pipe, an electrical power supply to nearest plug socket, and mounting brackets. Features must include a cooling and heating, minimum temp of 18°C and maximum temp of 30°C. With auto cool, power failure auto restart, electronic touch controls with remote, 12 hour on/off timer. With a 5-year warranty</u>				
236	13 000 BTU	No	5	18,237.44	91,187.20
237	19 000 BTU	No	5	23,386.81	116,934.05
238	25 000 BTU	No	5	30,016.66	150,083.30
239	36 000 BTU	No	5	36,045.73	180,228.65
240	42000 BTU	No	5	42,053.36	210,266.80
241	51 000 BTU	No	5	44,842.61	224,213.05
	<u>Supply and install BTU Ceiling / Console split Unit airconditioner complete, with a standard installation, 2m of copper pipe, cable and drain pipe, an electrical power supply to nearest plug socket, and mounting brackets. Features must include a cooling and heating, minimum temp of 18°C and maximum temp of 30°C. With auto cool, power failure auto restart, electronic touch controls with remote, 12 hour on/off timer. With a 5-year warranty</u>				
242	19 000 BTU	No	5	21,434.34	107,171.70
243	24 000 BTU	No	5	27,356.13	136,780.65
244	35 600 BTU	No	5	31,947.68	159,738.40
245	44 300 BTU	No	5	40,744.57	203,722.85
246	47 900 BTU	No	5	42,868.68	214,343.40

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>Supply and install Window Unit airconditioner complete, with a standard installation, 2m of copper pipe, cable and drain pipe, an electrical power supply to nearest plug socket, and mounting brackets. Features must include a cooling and heating, minimum temp of 18°C and maximum temp of 30°C. With auto cool, power failure auto restart, electronic touch controls with remote, 12 hour on/off timer. With a 5-year warranty</u>				
247	8 500 BTU	No	5	6,758.58	33,792.90
248	12 000 BTU	No	5	8,475.05	42,375.25
249	18 000 BTU	No	5	11,049.73	55,248.65
250	23 000 BTU	No	5	12,852.03	64,260.15
	<u>SUNDRIES</u>				
	<u>Cleaning, Servicing and re-gas Airconditioner</u>		5		0.00
251	9 000 BTU, 12 000 BTU, & 18 000 BTU Split units	No	5	975.26	4,876.30
252	24 000 BTU, 30 000 BTU, & 36 000 BTU	No	5	1,950.53	9,752.65
253	42 000 BTU & 51 000 BTU	No	5	2,340.63	11,703.15
	<u>ELECTRICAL WORKS - LABOUR RATES - (Limited to Bill no.16 - for items without rates)</u>				
	<u>Normal hours</u>				
254	General Labour (R206 per day)	Hrs	9	22.88	205.92
255	Electrician Semi Skilled (R440 per day)	Hrs	9	48.88	439.92
256	Electrician Artisan (R680 per day)	Hrs	9	75.55	679.95
	<u>After normal hours and Saturdays</u>				
257	General Labour	Hrs	9	34.32	308.88
258	Semi Skilled	Hrs	9	73.32	659.88
259	Electrician Artisan	Hrs	9	113.33	1,019.93
	<u>Sundays and holidays</u>				

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
260	General Labour	Hrs	9	45.76	411.84
261	Semi Skilled	Hrs	9	97.76	879.84
262	Electrician Artisan	Hrs	9	151.10	1,359.90
	<u>AUDIO VISUAL EQUIPMENT</u>				
263	Motorised screen 3620 x 2715mm high	No	1	31,024.96	31,024.96
264	Optoma projector Code "EX785 short throw 5000 lumens or equally approved	No	1	81,294.06	81,294.06
265	Kramer VP7289 input presentation scaler or equally approved	No	1	29,684.42	29,684.42
266	Pioneer DVD player or equally approved	No	1	1,665.10	1,665.10
267	Ecler DP400 digital loudspeaker management unit or equally approved no120 159.1020 159.10 VGA and video input connections on stage L and R no11 599.001 599.00 Projector mounting no13 471.003 471.00 AV installation cabling m155.0455.04 Audio visual and sound equipment mounting rack/ cabinet no110 991.5010 991.50 LIGHTING EQUIPMENT JB" System lighting desk scanmaster or equally approved	No	1	6,736.47	6,736.47
268	Liteputer DX626 6ch dimmer 2kW/ch	No	1	12,779.85	12,779.85
269	Par 64 1000w lights	No	1	1,673.56	1,673.56
270	LED 64 High power lights	No	1	4,817.81	4,817.81
271	LED 64 Low power lights	No	1	1,690.46	1,690.46
272	Briteq Stage colour 48 LED colour wash or equally approved	No	1	19,262.75	19,262.75
273	Briteq BT60LS LED moving head or equally approved	No	1	32,504.09	32,504.09
274	DMX splitter or equally approved	No	1	6,558.97	6,558.97
275	Lighting rack wall mount	No	1	7,809.91	7,809.91
276	Fly bars	No	1	1,627.06	1,627.06
277	Wall lighting bars	No	1	1,162.19	1,162.19
278	DMX input at FOH Position or equally approved	No	1	1,031.19	1,031.19

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	<u>SOUND EQUIPMENT</u>				
279	Sound Craft EFX 12 mixer 12ch mic input with two stereo input built in effects or equally approved	No	1	14,571.74	14,571.74
280	JB systems USB2 with two double CD - USB player or equally approved	No	1	14,737.40	14,737.40
281	Shure SM - 58 vocal mic or equally approved	No	1	4,767.09	4,767.09
282	Shure SM - 58 wireless hand-held mic or equally approved	No	1	14,732.33	14,732.33
283	AKG C 1000S podium mic or equally approved	No	1	8,012.76	8,012.76
284	Mic stand	No	1	877.35	877.35
285	Ecler Verso 12P speakers mid-high active loudspeaker 450W RMS and SPL 123dB or equally approved	No	1	25,470.95	25,470.95
286	Ecler Verso SB115P bass speaker or equally approved	No	1	32,930.09	32,930.09
287	Speaker brackets	No	1	752.26	752.26
288	Mixer/audio in and outputs breakout box	No	1	963.55	963.55
289	Audio input box - front of house	No	1	963.55	963.55
	<u>POWER GENERATOR</u>				
	<u>Including service plan for a period of three years @ 4 visits per annum and including 5 year guarantee. Supply, delivery, termination, connection and initial diesel full tank</u>				
290	3-Phase 30kVA diesel Generator with silent weather proof canopy and AMF Panel	No	1	144,066.05	144,066.05
291	3-Phase 40kVA diesel Generator with silent weather proof canopy and AMF Panel	No	1	173,576.95	173,576.95
292	3-Phase 60kVA diesel Generator with silent weather proof canopy and AMF Panel	No	1	221,772.77	221,772.77
293	3-Phase 80kVA diesel Generator with silent weather proof canopy and AMF Panel	No	1	244,007.55	244,007.55